

# stands alone.



error correction technique, the ICL7134 provides up to 14 bits of accuracy and ultra-high stability over the entire operating temperature range. Plus the same cool low-power CMOS performance.

Right now, we've got plenty of stock available. So once you see how easily the ICL7115 interfaces to your hardwired system and hooks up to 8- or 16-bit buses, you can spec the A/D chip that stands without peer.

Matter of fact, give us a call today and we'll put this super A/D converter in your hands. After all, we designed the ICL7115 for great engineers. Like you.

Call us for your free evaluation ICL7115, or write Intersil, Inc., Mail Stop R1-26, 10600 Ridgeview Court, Cupertino, CA 95014. In Europe, call (02) 673-93-79 or 660-20-14. Or write General Electric, International Operations, Chaussee de la Hulpe, 150-Bte. 5, 1170 Brussels, Belgium.

And discover—first hand—why GE stands for Great Engineering.




GE and 🚳 are registered trademarks of General Electric Company, U.S.A.

Sample the future. Call 800-626-2001.

Ext. 428. Free evaluation ICL7115s are available to the first 3000 qualified callers.

# Our ICL7115



The only 14-bit monolithic A/D converter on the market today—that's Intersil's ICL7115. It's the chip that will change the definition of signal processing.

Data acquisition and data logging applications are a whole new ball game with the ICL7115. It's monolithic, which means lower cost and higher reliability than systems built with hybrids or modules. And its successive approximation technique gives you 25,000 conversions per second, for more rapid sampling and greater digitizing capabilities.

The key to the ICL7115 is our proprietary

EPROM error correction technique. Unlike conventional techniques such as laser trimming, this unique EPROM correction method compensates for linearity and full-scale error with greater precision and stability, over the entire operating temperature range.


Though it's a hot new product, the ICL7115 is a very cool performer: thanks to our advanced CMOS technology, the whole package dissipates

only 10mW.

And if your system requires equal precision in a D/A converter, our ICL7134 meets the challenge. Utilizing the same proprietary EPROM

63 standsfo Glea neel ana SIGI cass

# more tough mixers



And the winning formula is not a secret.

Using the latest automated production and test equipment available, Mini-Circuits stress tests each individual component before assembly and then subjects each assembled SBL-1 to 17 grueling tests before acceptance, date coding and close checking for unit-to-unit repeatability.

The SBL-1 does have one drawback however. It only covers 1 to 500 MHz. That's why we've expanded the product family with additional models to cover 25 KHz to 1000 MHz. The new units are assembled with the same production and test expertise as the SBL-1; that's why we can offer 0.1% AQL on all SBL models . . . no rejects, not a single one, on every order shipped. So don't compromise your design or settle for a poor imitation. Specify Mini-Circuits SBL Mixers.

For full specifications call or write for latest RF/IF Signal Processing Handbook or refer to EEM, Gold Book, or Microwaves Directory.

#### SBL SPECIFICATIONS (typ.)


			Isolati	on,dB	Price
Model	Freq. (MHz)	Conv. Loss	L-R	L-I	(10-49)
SBL-1	1-500	5.5	45	40	\$4.50
* SBL-1X	10-1000	6.0	40	40	\$5.95
SBL-1Z	10-1000	6.5	35	25	\$6.95
SBL-1-1	0.1-400	5.5	35	40	\$6.50
SBL-3	0.25-200	5.5	45	40	\$7.50

\* If not DC coupled.

finding new ways . . . setting higher standards

P.O. Box 166, Brooklyn, New York 11235 (718) 934-4500 Domestic and International Telex 125460 International Telex 620156

C104 REV ORIG



# Amplifier Arsenal

50KHz to 2000MHz, 100mW output Gain Controlled From \$69.95

Our ZFL-2000 miniature wideband amplifier hit a bulls-eye when we introduced it last year. Now we've added more models to offer you a competitive edge in the continuing battle for systems improvement.

The ZFL-2000, flat from 10 to 2000MHz, delivers +17 dBm output and is still priced at only \$179.

Need more output? Our ZFL-1000H, flat from 10 to 1000MHz, delivers +20 dBm output.

Variable gain important? Our ZFL-1000G, flat from 10 to 1000MHz, delivers +3 dBm output with 30 dB gain control while maintaining constant input/output impedance.

Searching for a high-quality, low-cost amplifier? Our ZFL-500 flat from 50KHz to 500MHz, delivers 10 dBm output for the unbelievably low price of only \$69.

One week delivery...one year guarantee.
Gain the competitive edge...specify Mini-Circuits
RF/IF signal-processing components.

#### **SPECIFICATIONS**

OI LOII IOAI IOIG				
Model No. Freq (MHz) Gain (dB), Min.	<b>ZFL-500</b> 0.05-500 20	<b>ZFL-1000G</b> 10-1000 17	<b>ZFL-2000</b> 10-2000 20	ZFL-1000H 10-1000 28
Gain Flatness (dB) Max. Max. Power (dBm)	±1.0	±1.5	±1.5	±1.0
(1dB compression)	+10	+3	+17*	+20
NF (dB) typ. 3rd order	5.3	12.0	7.0	5.0
Intercept pt (dBm)	+18	+13	+25	+33
Current at 15V dc Price \$	80mA 69.95	90mA 199	100mA 179	150mA 219
atv.	1-24	1-9	1-9	1-9

For complete specs on these and our 1- and 2-W models refer to 1985-86 Gold Book or Microwaves directory.

+15 dBm below 1000MHz

finding new ways ... setting higher standards

# Mini-Circuits

World's largest manufacturer of Double Balanced Mixers
P.O. Box 166, Brooklyn, New York 11235 (718) 934-4500
Domestic and International Telex 125460 International Telex 620156

**CIRCLE NO 20** 

C101 REV. A



#### ELECTRONIC TECHNOLOGY FOR ENGINEERS AND ENGINEERING MANAGERS



On the cover: Graphics-controller ICs now let you implement raster-graphics systems that achieve fast drawing speeds that previously required the use of bit-slice processors. Moreover, the new controllers make medium- and low-performance graphics systems easier and less expensive to design and build. See pg 104. (Photo courtesy Texas Instruments Corporate Graphics)

#### **DESIGN FEATURES**

#### Special Report: Graphics-controller ICs

104

Recently introduced graphics-controller ICs offer faster drawing rates and better screen-refresh capabilities than do earlier models. The ICs range from simple screen-refresh controllers to highly specialized 32-bit graphics microprocessors.

#### EDN Multibus I I/O-Board Directory

120

Pacing recent developments in computer architecture, systems based on the 9-year-old Multibus I spec are using subsidiary buses and intelligent I/O boards to offer improved throughput.

#### Basic programs solve differential equations quickly

135

Differential equations that describe the performance of various devices can be difficult to solve, but you can convert them to integral equations and let a small computer solve them with Basic-language programs.

#### Designer's Guide to: Floating-point processing—Part 3


143

This final article in a 3-part series describes how to incorporate a floating-point processor in your system. It discusses criteria for the selection of the algorithms you'll use, and in particular it details the methods used to implement transcendental functions.

Continued on page 7

EDN (ISSN 0012-7515) is published biweekly with one additional issue in January, February, March, April, May, June, August, September, October, and November, by The Cahners Magazine Division of Reed Publishing USA, 275 Washington Street, Newton, MA 02158. William M Platt, President: Terrence M McDermott, Executive Vice President. Copyright 1986 by Reed Publishing USA, a division of Reed Holdings, Inc; Norman L Cahners, Honorary Chairman; Saul Goldweitz, Chairman; Ronald G Segel, President; Robert L Krakoff, Executive Vice President. Circulation records maintained at Cahners Publishing Co, 270 St Paul St, Denver, CO 80206. Second class postage paid at Denver, CO 80202 and additional mailing offices. Postmaster: Send address changes to EDN, 270 St Paul St, Denver, CO 80206.

# If you can't fix your board with the enhanced 9000 Series, it's beyond repair.





Introducing a new dimension of test capabilities for the Fluke 9000 Series Micro-System Troubleshooter line.

Finally there's a way to conquer some of the most difficult board testing problems imaginable. Take control of the situation with Fluke's 9000 Series and new **Asynchronous Signature Probe option.** You'll be able to pinpoint virtually every digital hardware fault on the entire board. Even those frustrating faults in circuits that operate independently of the microprocessor bus cycle.

Begin testing boards with the 9000 Series' built-in, preprogrammed test routines. In a single keystroke, you can automatically check the entire microprocessor kernel—Bus, ROM, RAM and I/O.

For testing beyond the bus, Fluke's new probe option eliminates the need for a logic analyzer or scope to test asynchronous circuits. One complete package, easily installed into either new or existing 9000 Series units, offers signature analysis, waveform capture and event counting. These three vital trouble-shooting functions give any 9000 Series the power to diagnose:

- DMA Controllers
- Disk Controllers
- Video Controllers
- Video-Generation Circuits
- Communication Circuits
- Peripheral Controllers
- Dynamic RAM timing relationships

Not only does the 9000 Series test more of the board, it also supports more 8-bit and 16-bit processors than any other tester on the market.

Call Fluke toll-free **1-800-426-0361** or contact your local representative, and put your most challenging board to the 9000 Series test. If it can't be fixed with the enhanced 9000, it's probably beyond repair.



IN THE U.S. AND NON-EUROPEAN COUNTRIES: John Fluke Mfg. Co., Inc., P.O. Box C9990, M/S 250C, Everett, WA 98206, Sales: (206) 356-5400, Other: (206) 347-6100 EUROPEAN HEADQUARTERS: Fluke (Holland) B.V., Po. Box 2269, 5600 CG Eindhoven, The Netherlands, (204) 459045, TLX: 51846.


© Copyright 1985 John Fluke Mfg. Co., Inc. All rights reserved. Ad No. 1003-9000.

45

61

77





Monolithic comparators offer impressive specs, but the devices' high gain and wide bandwidth can combine to make their behavior temperamental (pg 45).

#### TECHNOLOGY UPDATE

## Design challenges attend application of monolithic voltage-comparator ICs

Most of today's comparators are mature, versatile products. You can buy them in a wide range of speeds, but unwelcome characteristics (low gain, high bias current, etc) are prevalent among the older models.

## Logic analyzers evolve in response to high-level languages

Logic analyzers—in their latest incarnation as software analyzers—are becoming high-level-language instruments that promise to wreak changes on software-engineering methods.

## ISSCC '86 speakers predict future developments in solid-state technology

This year's International Solid State Circuits Conference (ISSCC), which will take place in Anaheim, CA, will provide a forum for industry experts to speculate about technological developments that you can expect to see in the near future.

#### PRODUCT UPDATE

THODOGICAL	
PC/AT-compatible data-acquisition board	87
Wireless modem and portable computer	90
18V linear/digital CMOS arrays	92
Motion-control subsystem	94

#### **DESIGN IDEAS**

Use simple circuit to program EPROMs	153
Algorithm approximates sum of quadratures	154
Drive stepper motor without missing steps	156
Pulse generators offer improved performance	158
Calculator performs binary arithmetic	162

Continued on page 9

Advertising and editorial offices: 275 Washington St, Newton, MA 02158. Phone (617) 964-3030. Subscription offices: 270 St Paul St, Denver, CO 80206. Phone (303) 388-4511. EDN is circulated without charge to those qualified. Subscription to others: Continental US \$70/year, \$5/copy; Canada and Mexico \$80/year, \$6/copy; Europe Air Mail \$120/year, \$7/copy; all others surface mail \$120/year. Special issue prices may vary. Send requests for qualification forms and/or change of address to subscription office.

© 1986 by Reed Publishing USA, Division of Reed Holdings, Inc. All rights reserved.

# How to computerize your measurements without compromising results.

Now there's a faster, more repeatable and more productive way to make waveform measurements—and not surprisingly, it comes from Tektronix. Tek's library of waveform acquisition and processing software combines the best of computer-aided measurement with the high interactivity and accuracy you enjoy in

Whatever your application, whatever your front-end processor—IBM PC, H-P Series 200 or Tek's own 4041 controller—Tek software

Tek scopes

can help you store and retrieve data, process, analyze, display and document results. Powerful, flexible operation is common to all Tek packages:
we accommodate

your way of working; you don't have to conform to ours.


For more information contact the nearest Tektronix Office. Tektronix, Inc. P.O. Box 1700 Beaverton, OR

In Europe: Tektronix Europe B.V., Postbox 827 1180 AV Amstelveen


The Netherlands.

97075






Delay time measurement using an IBM PC/XT/AT as controller with Tek's Time and Amplitude Measurement Software. Instruments: the Tek 7D20 Programmable Digitizer and Tek 7603 oscilloscope.



Automated pulse parameter analysis using a Tek 4041 Controller and Tek Time and Amplitude Measurement Software to direct the efforts of the 7D20 in a 7603 mainframe. Hard copy generated by a Tek 4695 Color Copier.



Computing and displaying frequency domain data (FFT), using an HP Series 200 Technical Computer as controller. Tek software for these results accommodates the HP Series 200 with the Tek 7D20 or the Tek 7854 Waveform Processing Oscilloscope.



Editing a Tek 7854 RPN program, including comments, for downloading to the 7854 or archiving to disk. Performed with the HP 200 Series Technical Computer, the Tek 7854, and Tek 7854/HP Series 200 Software. Similar facility available in COMMUTE.





	VP/Publisher
F	Warren Dickson

VP/Editorial Director Roy Forsberg

> Editor Gary Legg

Managing Editor Rick Nelson

Assistant Managing Editor
Joan Morrow

Home Office Editorial Staff 275 Washington St, Newton, MA 02158 (617) 964-3030

Tom Ormond, Senior Editor
Jonathan Titus, Senior Editor
Bill Travis, Senior Editor
Deborah Asbrand, Staff Editor
Joanne Clay, Staff Editor
Tarlton Fleming, Associate Editor
Eva Freeman, Associate Editor
Clare Mansfield, Staff Editor
George D Miller, Staff Editor
George D Miller, Staff Editor
Charles Small, Associate Editor
David Smith, Associate Editor
George Stubbs, Staff Editor
Chris Terry, Associate Editor
Valerie DeSalvo, Assistant Editor
Cynthia B Rettig, Assistant Editor
Steven Paul, Production Editor

Editorial Field Offices Denny Cormier, Western Editor San Jose, CA: (408) 296-0868

Bob Cushman, Special Features Editor Port Washington, NY: (516) 944-6524

Chris Everett, Western Editor San Jose, CA: (408) 296-0868

Steven H Leibson, Southwestern Editor Boulder, CO: (303) 494-2233

J D Mosley, Texas Editor Arlington, TX: (817) 465-4961 Edward Teja, Western Editor Santa Cruz, CA: (408) 725-0376 Maury Wright, Western Editor San Diego, CA: (619) 748-6785

San Diego, CA: (619) 748-6785
Peter Harold, European Editor
0603-630782

(St Francis House, Queens Rd, Norwich, Norfolk NR1 3PN, UK) Contributing Editors

Robert Pease, Bob Peterson, Don Powers

Editorial Services

Kathy Leonard, Supervisor Laureen Ouellette, Darlene Thomas

Art Staff
Susan Barrow-Williams, Director
Kathleen Ruhl, Assistant Director
Roseanne D Coveney, Illustrator
Chin-Soo Chung, Illustrator
Debi Queally, Illustrator

Production/Manufacturing Staff
William Tomaselli, Production Supervisor
Donna Pono, Production Manager
Patricia Hadidian, Production Assistant
Elizabeth Wojciechowicz, Production Assistant
Diane Malone, Composition

Graphics Director Norman Graf

VP/Production/Manufacturing Wayne Hulitzky

Director of Production/Manufacturing John R Sanders

> VP/Research Ira Siegel

Marketing Communications
Deborah Virtue, Manager
Jennifer Ware, Promotion Manager
Corie Rand, Promotion Coordinator

#### EDITORIAL

41

For once, the hardware folks and the software folks are cooperating in a way that'll benefit all of us. The result of this cooperation? The Computer Graphics Interface.

#### **NEW PRODUCTS**

Computer-Aided Engineering
Computers & Peripherals
Components & Packaging176
ICs & Semiconductors
Computer-System Subassemblies
Instrumentation & Power Sources
International
Software

#### PROFESSIONAL ISSUES

#### LOOKING AHEAD

213

1990 connector market to top \$7.5 billion . . . Market for 32-bit  $\mu$ Ps may reach \$1B by 1990.

#### DEPARTMENTS

News Breaks	. 17
News Breaks International	
Signals & Noise	
Calendar	. 34
Leadtime Index	
Literature	
Business/Corporate Staff	205
Career Opportunities	206
Advertisers Index	212

### Φ

#### **VBPA** ABP

Cahners Publishing Company ☐ Publishers of specialized business magazines in Building & Construction ☐ Electronics & Computers ☐ Foodservice ☐ Manufacturing ☐ Medical/Health Care ☐

WE COULD HAVE
CALLED IT A
32-BIT
MICROPROCESSOR.

WE COULD HAVE
CALLED IT A

10-MIP
MPUTING ELEMENT.

WE COULD HAVE CALLED IT THE FIRST CONCURRENT SOLUTION.

INSTEAD
WE CALL IT THE
TRANSPUTER.

INMOS introduces the transputer family. A range of evaluation boards for the first transputers is available now.

The transputer is a fast, easy to use VLSI component designed for applications ranging from single microprocessor systems to supercomputers.

The IMS T414 is the first transputer, integrating a 32 bit microprocessor, four inter-transputer communication links, 2 Kbytes of RAM, a 32 bit memory interface and a memory controller onto a CMOS chip.

The microprocessor runs at 10 MIPS and is designed specifically for the execution of high level languages. It combines direct support for multi-tasking, floating point, block transfer and record handling with sub-microsecond procedure call and task switching.

Each transputer link provides a full duplex, 10 Mbits/sec, point to point connection with an on chip DMA controller. Links are used for intertransputer communication or, via an INMOS Link Adaptor, interfacing to industry standard byte wide peripherals.

The memory interface provides access to a linear 4 Gbyte address space at a data transfer rate of up to 25 Mbytes/sec.

Transputers are designed for ease of engineering. All transputer family devices operate from a single 5 MHz clock input, which is used to derive high speed internal clocks for all on chip systems

When transputers are directly connected via links, additional components are not necessary. Independent or common clocking can be used, regardless of timing skew.

The configurable memory controller also requires no external components. It provides all

	TRANSPUTER PRODUCTS	
IMS T414	32 Bit, 2 Kbyte RAM, 4 Transputer links	
IMST212	16 Bit, 2 Kbyte RAM, 4 Transputer links	
IMS C001	Transputer Link Adaptor, Separate	
	8-Bit input and output	
IMS C002	Transputer Link Adaptor, Multiplexed	
	8-Bit input/output	

DEVELOPMENT TOOLS		
 IMS D100	INMOS Transputer Development System	
IMS D600	Transputer Development Software, VAX-VMS	
IMS D700	Transputer Development Software, IBM-PC	

	EVALUATION BOARDS
IMS B001	Double Eurocard, IMS T414,
	64 Kbyte RAM, 2 x RS232C ports
IMS B002	Double Eurocard, IMS T414,
	2 Mbyte RAM, 2 x RS232C ports
IMS B004	IBM-PC add on card, IMS T414,
	1 Mbyte RAM

inmos IMS and occam are trademarks of the INMOS Group of Companies.

the necessary timing and refresh signals for memory systems, comprising any mix of ROM, SRAM, DRAM and memory mapped peripherals.

Transputers are designed for ease of programming. INMOS offers development systems which provide integrated editing, compiling and source level debugging for both single and multiple transputer applications, using C, Pascal, Fortran and occam.

In applications requiring only a single computing element, the transputer's speed, minimal support component requirements and programming efficiency provide significant cost/performance advantages over conventional microprocessors.


Systems of any size can be built from interconnected transputers, using the links. The same program can be configured to run on one, tens or thousands of transputers allowing a simple trade off between performance and cost.

The transputer family already includes 32 bit and 16 bit transputers, peripheral controllers, evaluation boards and development tools. Start assessing its capability for yourself now with an IMS T414 evaluation board.

INMOS Corporation, PO. Box 16000, Colorado Springs, Colorado 80935. USA. Tel (303) 630-4000. Tx: (910) 920-4904 INMOS Limited, Whitefriars, Lewins Mead. Bristol, U.K. BS1 2NP. Tel 0272 290861 Tx: 444723. INMOS GmbH, Danziger Strasse 2, 8057 Eching, West Germany. Tel 089 319 10 28. Tx. 522645. INMOS Sarl, Immeuble Monaco, 7 Rue Le Corbusier, Silic 219, 94518 Rungis Cedex, France. Tel: (1) 687.22 01. Tx: 201 222.

For a complete data pack on the Transputer and its support products, fill in the response coupon, and post to INMOS Corporation P.O. Box 16000 Colorado Springs, Colorado 80935, USA. For faster response, call (303) 630-4000
Name
Title
Company
Street/PO address
Y
City/State/Zip
Country
Telephone
Please send Transputer data pack
Please have a salesman call
I am interested in ordering an Evaluation Board
in <b>mos</b> °
TRANSPUTER FAMILY

# Get a grip on voltage surges



# with new SURGECTOR.



### A breakthrough in surge protection.

Now there is something new in the world of surge protection. Surgectors are unlike zeners, MOVs, carbon arrestors or gas discharge devices.

Surgectors respond rapidly and handle a lot of energy. They are ideal for protecting sensitive or expensive components from lightning strikes, load changes, switching transients, commutation spikes, electro-static discharge and line crosses.

#### How Surgectors work.

Surgectors are monolithic structures integrating a zener diode and an SCR into one reliable, cost-effective device.

At low voltages, the Surgector is "off," representing high forward impedance (only 50nA leakage current). The instant clamping voltage is exceeded, Surgector turns "on." The zener starts to conduct immediately. Current flows from the zener region into the thyristor gate and within nanoseconds the SCR turns on to handle heavy currents. Destructive surges are shunted to ground. Once the voltage surge passes, the Surgector makes a fast transition back to the "off" state.

#### Five Surgector choices.

Our opening Surgector line-up is three 2-terminal devices (30V, 60V and 230V), one bidirectional (230V) and one 3-terminal (100V).

The 3-terminal Surgector gives you access to the SCR gate lead, allowing the device to be triggered with your voltage level detector.


Туре		Rating	Price (1K)
SGT03U13	2-terminal	30V	.60
SGT06U13	2-terminal	60V	.62
SGT23U13	2-terminal	230V	.70
SGT23B13	bi-directional	230V	.99
SGT10S10	3-terminal	100V	.72

#### Surgector vs. zener and MOV.


Surgectors are as fast as zener diodes (<1ns response time) yet can handle ten times as much energy. At breakdown voltage, Surgectors are two orders of magnitude lower in impedance than zeners (0.1 ohm vs. 10 ohms).

Compared with MOVs, Surgectors have a much better clamping ratio. An MOV with operat-

ing voltage of 100V may allow a 300V surge before it offers any protection. A 100V Surgector turns "on" with only a 110V surge. Surgectors are ten times faster, dissipate much less power and have longer lives than MOVs.



Surgectors are much faster than gas discharge tubes or carbon arrestors, but can carry less surge




current. The transient peak current capability of the Surgector is 300A for 1 \( \mu \text{x} \) 2 \( \mu \text{s} \) pulse and 75A for a 10 \( \mu \text{s} \text{ x} \) 1000 \( \mu \text{s} \text{ pulse} \) other surge protectors, Surgectors will eventually fail if

pushed beyond specifications. But Surgectors normally fail shorted, rather than open. And even shorted Surgectors protect expensive components. Only beyond triple the rated surge current will the Surgector blow open.

For more information on Surgectors, call our Power Application Hotline (800-RCA-APPL), your RCA sales office or distributor, or write: RCA Solid State, Box 2900, Somerville, NJ 08876.

Call: Hamburg, 49-4106-6130; London, 44-93-2785511; Paris, 33-3-946-5656; Hong Kong, 8-52-3-723-6339; Sao Paulo, 55-11-210-4033.





# Seventy-two hours ago you didn't know you needed an emulator.

# Applied Microsystems emulators solve problems you don't expect.

Before you spend another long night trying to debug your system, call Applied Microsystems. Whether you're working with an 8-bit, 16-bit or even a 32-bit microprocessor. Intel, Motorola or Zilog. One processor or several. No bug is buried too deep for Applied Microsystems emulators.

## Making a reliable 8-bit favorite even better.

Our 8-bit EM has been cited by a leading engineering magazine as the best 8-bit in-circuit emulator on the market. It's a big favorite among engineers because they can rely on it 99.8% of the time.

But instead of relaxing, we started improving.

Now, drive your EM with a VAX, Sun, Apollo or PC using our host-resident remote control software. The optional logic state probe lets you qualify breakpoints with logic conditions anywhere in the system and cross-trigger to your 16-bit ES emulator. So you can find bugs caused by the interaction of the two. We've also

included new high performance cross-assemblers.

Best of all, in addition to more capabilities, we've even held our low price.

#### Our 16-bit emulator keeps state-of-the-art system debug from turning into a state of siege.

It takes a powerful emulator, not promises, to get a bug-free product to market quickly. Applied Microsystems' 16-bit ES emulator runs identically to the processor in your target system. At the full-rated clock speed.

Our unique Event Monitor System lets you precisely control and monitor emulation flow with a combination of address, data, status, pass counter, and logic state events. You can quickly sort through thousands of bytes of code to find the small sections where bugs are embedded. Once discovered, use our resident symbolic debug to quickly patch in new code and test it in real time.

# Dig out bugs from the source to the bit.

Validate,™ our new family of enhanced development environments, offers you the combined power of integrated hardware and software tools. Centered around a true source-level debugger, Validate works with "C" and Pascal on UNIX and VMS systems.

## New! Real-time emulation for the 32-bit 68020.

Working with the 68020? Applied Microsystems has a new 32-bit emulator for our ES series. All the powerful debug features you expect from the ES. And it's available now.

#### PROCESSORS SUPPORTED BY APPLIED MICROSYSTEMS

**8-BIT:** 8080, 8048 family, 8085, 8088, 80188, Z80, NSC-800, 6800 family, 6809, 6809E, 68008, V20

**16-BIT:** 68000, 68010, 8086, 80186, Z800X, V30

32-BIT: 68020

# Ask us for the facts. You'll like what you hear.

Call toll-free for the technical and applications information that supports our promises: 1-800-426-3925. In Washington, call (206) 882-2000. Or write Applied Microsystems, P.O. Box 97002, Redmond, WA 98073-9702.

In Europe: Brooke House, Market Square, Aylesbury, Buckinghamshire, HP20 1SN, England. Tel: 44 (0296) 34822.



Applied Microsystems Corporation

# WRING THE POWER FROM YOUR LOW OFFSET OP AMP ....



### TELEDYNE SEMICONDUCTOR

1300 Terra Bella Avenue • P.O. Box 7267 • Mountain View, CA 94039-7267 • (415) 968-9241

☐ Please send me mo	☐ Please send me more information on the TSC7650.						
☐ Please have a	Name		Title				
Teledyne salesperson	Company		_Address				
call me.	City	State	Zip	Tel: (			
	CIRCLE NO	25				186EDN900	

# NEWS BREAKS

EDITED BY JOAN MORROW

#### PC SOFTWARE HELPS IMPLEMENT $\mu$ P, PLA, AND GATE-ARRAY DESIGNS

The Master schematic logic analyzer and companion products provide engineers with an economical design tool that allows you to translate schematics into  $\mu$ P-based, PLA-based, or gate-array designs. Aldec-Automated Logic Design Co (Newbury Park, CA, (805) 499-6867) offers Master and a suite of options that includes graphics schematic capture, Alice (Aldec logic in-circuit emulator), the Logic Networking Compiler, and various libraries. System prices range from \$3000 for just the Master logic analyzer to \$12,000 with all of the software options.

The software executes on the IBM PC, and the graphics option requires the IBM Enhanced Graphics Adapter. Using Master, you can enter schematics, simulate your design, and compile the design into  $\mu$ P object code, PLA program files, or Fujitsu-compatible gate-array files. The Alice hardware/software package allows you to connect the design you created on the PC to its intended hardware environment, enabling you to debug your design before building it. For  $\mu$ P-based systems requiring more than one  $\mu$ P, you can use the Logic Networking Compiler to produce object code for multiple  $\mu$ Ps operating in parallel.—Maury Wright

#### DIGITIZING OSCILLOSCOPE CAPTURES 300-MHz REPETITIVE SIGNALS

With Hewlett-Packard's \$17,600 54100A digitizing oscilloscope, you can view repetitive signals to 1 GHz. However, it limits your viewing of single-shot events to 10 MHz because of its 40M-sample/sec digitizing rate. The company's \$7900 54200A lets you view 50-MHz single-shot events (200M-sample/sec digitizing rate). It limits your viewing of repetitive events to 50 MHz because it doesn't use a repetitive sampling technique to digitize the waveform. Instead of an either/or choice of a scope with high single-shot bandwidth or a scope with high repetitive frequency, you can choose HP's 54201—a 300-MHz scope with a 200M-sample/sec digitizer.

Specifically, a 300-MHz front end and repetitive-sampling circuitry was added to the 54200. The scope uses a random repetitive-sampling technique to capture and display pretrigger data. Two models are included in the 54201 Series: the 54201A (\$7900) and the 54201D (\$9800). The D model has all the measurement capabilities of the A plus additional triggering capabilities for triggering the scope with digital circuitry.

In addition to the increase in repetitive signal-measurement bandwidth from 50 to 300 MHz, the 54201 has several other feature enhancements over the 54200. It can save the maximum, minimum, and mean average time-delay measurement values. This capability is added to the automatic pulse-parameter measurement capability already provided with the 54200. The company has also added waveform math capabilities and a connect-the-dots display mode.—Chris Everett

#### HANDS-ON COURSE LETS YOU DESIGN AND BUILD GAAS ICS

Triquint Semiconductor's (Beaverton, OR, (503) 629-3126) GaAs-IC design course will teach you how to use the company's IC-design tools to design your own device. You'll also receive prototypes of your design. Running from March 10 to March 13, the course contains two sections: instruction in the use of the company's IC-design tools, and layout and fabrication of your own GaAs chip. The course also covers testing, packaging, and the reliability of GaAs ICs. For \$9900, you receive lodging, layout and fabrication services, packaged samples of your design, an evaluation board, class notes, and lunches. To attend, you must respond by March 3, 1986, to Ajit Rode at Triquint Semi-conductor.—David Smith

EDN February 6, 1986

# **NEWS BREAKS**

#### 512k-BIT CHIP PACES EXPANDED EPROM FAMILY

Three new EPROMs, including a 512k-bit device, expand the family of nonvolatile memory products from VLSI Technology (San Jose, CA). The 64k-bit VT27C64, the 128k-bit VT27C128, and the 512k-bit VT27C512 join the already available 256k-bit VT27C256 to form, according to the vendor, the industry's first full family of CMOS EPROM products. The company also claims the VT27C512 is the first 512k-bit EPROM built in high-speed, low-power CMOS technology.

Several features suit these EPROMs for low-power,  $\mu$ P-based applications. A chipenable input allows you to implement a power-down mode. To eliminate bus contention, an output-enable input disables the chip's outputs. Also, the chips spec cycle times of 150 and 250 nsec, making them compatible with most  $\mu$ Ps. The 64k-, 128k-, and 512k-bit versions cost \$4.50, \$7.81, and \$15.28 (5000).—David Smith

#### CMOS FLASH A/D CONVERTERS OPERATE WITH ONE 3 TO 8V SUPPLY

Three CMOS flash A/D converters from Hybrid Systems (Billerica, MA, (617) 667-8700) require only one 3 to 8V supply for operation. The monolithic devices come in commercial or MIL-STD-883 versions and feature sampling rates from 5 to 30 MHz and power consumption no higher than 300 mW. The 6-bit HS9582 parallel flash converter is spec'd for 15-, 25-, or 30-MHz sampling rates; corresponding power consumption ranges from 50 to 200 mW. Linearity error is  $\pm \frac{1}{4}$  LSB at 15 MHz with a 5 or 8V supply. An overflow bit allows higher resolution by connecting two converters in series. The HS9582 costs \$15.40 to \$89 (100).

The 8-bit HS9583 is a 2-step flash device that converts the first three MSBs, and then converts the remaining five LSBs in a second pass. Offering 5- or 10-MHz sampling rates and 75-mW power consumption, it features  $\pm \frac{1}{4}$ -LSB linearity at 5 MHz with a 5 or 8V power supply. Housed in a 24-pin DIP, the devices costs \$44.30 to \$161 (100). The full-flash 8-bit HS9584 comes in a 28-pin DIP and contains 255 clocked comparators. Offering 10- and 20-MHz sampling rates, this converter specs a 60-psec aperture uncertainty, which allows conversion of full-amplitude signals with frequencies as high as the Nyquist limit. It costs \$46.60 to \$275 (100).—Tarlton Fleming

#### 68020/80286 DEVELOPMENT TOOLS INCLUDE COPROCESSOR EMULATION

The Tektronix (Beaverton, OR) MultiV Systems package provides design teams with software development tools and hardware/software integration tools for Motorola 68020 and Intel 80286 microprocessors. For software development, Tektronix provides a C language development system (Clands II) and a software execution system (the Software Executer). The hardware/software integration support includes a 68020 emulator and an 80286 emulator. The Clands II package, includes a C compiler, a C language directed editor, a 32-bit macroassembler, a relocating linker, an integration control system, and a C language debugging tool. After you have developed your code on Clands II, you download the code to the MultiV Systems mainframe. You then debug your code on the Software Executer, which contains a 68020 processor and 68881 coprocessor (or 80286 processor and 80287 coprocessor).

The MultiV Systems mainframe can support two Software Executers or two emulators at one time. You can couple them together for multi-emulation support or leave them uncoupled to provide two separate development environments for two users. The 68020 emulator provides real-time transparent emulation of the 16.6-MHz 68020 processor and 68881 coprocessor. The 80286 supports the 10-MHz 80286 processor and 80286 coprocessor. MultiV packages start at less than \$20,000.—Chris Everett

# If your system is only using this many colors, is nit it time to grow up?

The INMOS IMSG170 Color Look-up
Table offers a grown-up solution to video
display color enhancements. It lets you
and your RGB analog display advance
to a palette of more than a quarter
million colors.

This programmable DAC conforms to RS170A standards with pixel rates up to 50 MHz, in a 28 pin package.

And to simplify things, the table integrates the functions of a 256 word x 18 bit color mapping table, three 6-bit DACs, 75 ohm drivers and microprocessor interface into a monolithic CMOS device. The result? Reduced

board space and power consumption at a lower cost.

The Color Look-up Table from INMOS. Designing with thousands of colors just became child's play.

INMOS Corporation, Colorado Springs, Colorado, Tel. (303) 630-4000 Bristol, England, Tel. 0272-290-861 Paris, France, Tel. (1) 687-2201 Munich, Germany, Tel. (089) 319-1028



Compare your computer design colors to these crayons. If the crayons win, call INMOS.



Crayola is a registered trademark of Binney & Smith, Inc. Used with permission.

INMOS, and IMS are trademarks of the INMOS Group of Companies.

**CIRCLE NO 45** 

# NEWS BREAKS: INTERNATIONAL

**EDITED BY JOAN MORROW** 

#### JAPANESE IBM-COMPATIBLE COMPUTERS WILL BE SOLD IN US

Toshiba Corp plans to sell its 16-bit T-1100 computer in the United States starting early this year. The company, which sells approximately 5000 of the IBM-compatible portable systems per month in Europe, will initially import 1000 systems per month to the US and sell them through Toshiba America.

#### CMOS 256k-BIT EPROM FEATURES 120-nSEC ACCESS TIME

The 27C256AD, a CMOS 256k-bit EPROM from Nippon Electric Co, furnishes a 120-nsec access time. The device was designed under a 1.2- $\mu$ m rule and measures 4.73×4.45 mm. It consumes 30 mA during operation, 100  $\mu$ A in standby, and costs \\$1500 (\\$7.32) (5000).

#### MOUNTING TECHNIQUE PUTS PACKAGELESS CHIPS ONTO PC BOARD

The Chip On Board (COB) method developed by Ricoh Co allows the insertion of packageless ICs directly onto pc boards. The technology could increase pc-board density two to four times and also reduce production costs by 30%. The company might start using the technology in commercial production next summer.

The COB method employs a sealing resin that has the same protective qualities as conventional plastic or ceramic IC packages. It can be used for memory products, microprocessors, peripheral LSI devices, and gate arrays, and it can reduce the size of equipment such as printers. Many semiconductor vendors were reluctant to supply Ricoh with naked chips, but at least two companies have agreed to help Ricoh with its experimental technique.

#### SILVER-, GOLD-CONTACT SWITCHES MEASURE 5×2.5×7.5 mm

Suiting such applications as floppy-disk drives, lap computers, car stereos, and portable video cameras, microswitches from Matsushita Electric Works measure 5×2.5×7.5 mm and weigh 0.2g. Approximately one-fifth the size of conventional devices, the microswitches have silver or gold contacts and come in three categories: pin pushbutton, hinge lever, and hinge R lever. They cost ¥120 (\$0.59) to \$0.66 for silver-contact types and \$0.73 to \$0.90 for gold-contact versions.

#### 80C88-BASED HANDHELD COMPUTER COSTS \$800

The \$800 Personal Partner from Panasonic Industrial Co incorporates a 5-line×80-character LCD and is powered by rechargeable NiCd batteries. Built around an 80C88 CMOS  $\mu$ P, the computer provides 8k bytes of RAM, which is expandable to 256k bytes. It also features a resident word-processing program, four read-only memory sockets, and an IBM-style keyboard. An optional bus can accommodate an external printer and a built-in 1200-baud modem.

Nicolet's 800D Logic Analyzer

Because Some Tools Are Indispensable!



No matter where problems are lurking in your digital system, the development and lebug measurement capabil-



ities of Nicolet's NPC800D Logic Analysis System help you quickly isolate and dispatch them.

This precision instrument combines a comprehensive set of digital tools integrated into one portable, highly affordable measurement system. Examine small

timing skews at 200 MHz. Find three nanosecond glitches. Trace software execution in discontinuous segments. Optimize systemlevel software performance. Examine transient analog signal problems. Follow communications through RS-232, GPIB, Bisync, and HDLC protocols. Use integrated signature analysis, counter and timer functions. Control other instruments via GPIB. Troubleshoot remotely via RS-232. Run standard CPM applications programs. Write specialpurpose testing programs for automatic operation with popular CBASIC.

Count on Nicolet's quality

and reliability based on ten years experience and innovation in creating logic analyzers. Our "firsts" include sixteen-level triggering, integrated analog waveform analysis, state and timing "cross-domain" measurement, built-in mass storage, general computational capabilities and full GPIB controller functions.

To find out the details, arrange a demonstration, or just to tell us about your problem, call 800 NICOLET. In California, 415 490-8300.

CIRCLE NO 27



# UNBELIEWABLE



# FILTERS \$995 IN STOCK



LOW PASS Model PLP		-100	-150	-200	-300	-450	-550	-600	-750	-850	-1000	
Pass Band, MHz (DC-)	48	98	140	190	270	400	520	580	700 1000	780	900	
20dB Stop Band start from	70	135	210	290	410	580	750	800	1000	1100	1340	
HIGH PASS Model PHP -50		-100	-150	-200	-300	-400	-500	-600	-700	-800	-900	-1000
start	41	90	133	185	290	395	500	600	700	780	910	1000
Passband, MHz stop	200	400	600	800	1200	1600	1600	1600	1800	2000	2100	2200
20dB Stop Band, (MHz) from DC to 26		55	95	116	190	290	365	460	520	570	660	720
CIRCLE NO 28 F82-2 REV. ORIG.												

# The concept that shows the way

The SAB 8051 family offers microcontrollers for every application. It's constantly being expanded so that growing functional needs can be implemented with a single device.

Ongoing SAB 8051 development by Siemens gives you

- more peripheral power on one chip
- more memory capacity (RAM/ROM)
- faster processing speed
- greater substitution value
- full upward compatibility with SAB 8051A

Choose the right microcontroller from the SAB 8051 family for your innovative products.

#### **SAB 8051A**

Additionally available with extended temperature range for industrial applications: -40 to +85°C for automotive applications: -40 to +110°C

#### SAB 8051A-15

High-speed version of SAB 8051A with 15 MHz clock frequency. Particularly suitable for applications with critical timing.

#### **SAB 8052A**

An SAB 8051A with dual RAM, ROM plus an extra timer. Extended temperature ranges.

#### **SAB 80515**

5A880F

The latest and most powerful version in the SAB 8051 product family:

with dual RAM, ROM and extra timer, plus A/D converter with programmable reference voltage. six 8-bit ports, watchdog timer and other functions. Extended temperature ranges.


Siemens SAB 8051 family is growing all the time, showing the way to new, cost-attractive solutions for increasingly demanding and complex needs.

If you want to find out more about our single-chip microcontrollers, write to Siemens AG, Infoservice 12/1019, Postbox 23 48, D-8510 Fürth. West Germany, quoting "SAB 8051/8052."

**Single-chip microcontrollers** from Siemens

**CIRCLE NO 30** 





# The new single line Stacks up better You'll appreciate the design freedor we've added to aur line with more

Stacks up better, across the board.

You'll appreciate the design freedor we've added to our line—with mass terminating AMPMODU MTE connectors. Receptacles stack side-by-si or end-to-end, to take 22-30 AWG wanywhere on the board with complemodularity.

Pre-loaded
assemblies simplify
mass termination.
Interlocking carrier
strips accurately
locate insulationdisplacement
contacts in tooling.





# connector.

You can also choose polarized or ching receptacles, or special ribbed ceptacles that gang into single- and uble-row coupling shrouds. Pin ntact types and shrouded headers und out the wire-to-wire and wire-board picture.

MTE connectors are backed by a full range of application tooling, from hand and semi-automatic to fully automatic, to meet any level of production you need.

Call (717) 780-4400 to find out more. Ask for the AMPMODU MTE Connector Desk. AMP Incorporated, Harrisburg, PA 17105-3608.


AMP and AMPMODU are trademarks of AMP Incorporated.

## AMP Interconnecting ideas

Vertical and rightangle headers,
receptacles, and
shrouded housings
provide modular
approach.

CIRCLE NO 34

Do it all in two contact sizes—
22-26 AWG and 26-30 AWG
Dual-beam contacts are overstressprotected, and feature post stops for use on long posts.







In Japan the name JAE is synonymous with connecand quality. The leader. industry's produce nearly every type of electrical connector — for printed circuit boards, ICs, electronic products and of course aircraft. The PICL Series of PCBto-PCB plug-in connectors are the smallest-sized, highest-density connectors in production in the world. The pins have 50-mil center spacing. Gold-plated phosphor bronze pins and two-point contacts guarantee reliable signals. And the various configurations available make it ideal for the tight spaces inside today's compact devices. Another state-of-theart product from JAE.

Japan Aviation Electronics Industry, Limited's manufacturing activities span the full breadth of the electronics industry. Aerospace, Connector, Electro-optics, and Commercial/Industrial Components divisions bring you the most reliable electronic products. Components range from connectors and switches to relays. JAE's aeronautics and aerospace products include sophisticated inertial navigation and automatic flight control systems.

We recently entered the opto-electronics field with an impressive lineup of connectors, optical links, optical sensors and complete fiber optic systems. The first of a full product line of opto-electronics from JAE.

Whether you are looking for selection, reliability, innovation or prompt delivery. JAE. Call us today.

JAE Electronics, Inc. 1901 E. Carnegie Ave. Santa Ana, California 92705 USA Tel. 714-250-8770, 1-800-JAE-PART Telex 681438

Panel, push-button, DIP and keylock switches.



CIRCLE NO 31





Japan Aviation Electronics Industry, Limited

21-6, 1-chome Dogenzaka Shibuya-ku, Tokyo 150 JAPAN Tel. 03-463-3111

# AMERICA'S BEST PROGRAMMERS



#### Z-3000 HIGH VOLUME GANG/SET PROGRAMMER

- 14,000 27256s programmed per day.
- 32 EPROMs simultaneously with 1 to 8 DATA BLOCKS.
- 16 Intel or Motorola MCUs at a time.
- 64K to 256K bytes of DATA RAM.
- Simple one key programming operation.
- Two RS-232 ports with data transfer formats included.



### Z-2500B IN-CIRCUIT MEMORY CARD PROGRAMMER

- Programs up to 32 memory cards with EPROMs or microcomputers at a time.
- Two 1.2 Mbyte DSDD floppy disk drives. Optional 20 Mbyte hard disk.
- Turnkey systems include programmer, terminal, custom interface hardware and software.
- Simple menu driven operation.

#### Z-1000B UNIVERSAL PROGRAMMER

- Over 600 PLDs, EPROMs, EEPROMs, bipolar PROMs and INTEL MCUs.
- Upgradeable PROM based software.
- Stand alone or PC/XT/AT operation.
- Two independent RS-232 ports.
- 64K or 256K bytes of DATA RAM.
- EXATRON handler interface is standard.

### Z-1200B TWELVE SOCKET GANG/SET PROGRAMMER

- 2716-27512, 1 to 4 DATA BLOCKS.
- 64K to 256K bytes of DATA RAM.
- Software personality. No plug-ins.

**ZAP SERIES** low cost programmers for EPROMs and single-chip MCUs.

Z-400 for bipolar PROMs and EPROMs.



#### SUNRISE ELECTRONICS, INC.

524 South Vermont Avenue Glendora, California 91740 (818) 914-1926

# SIGNALS & NOISE

## Phantom-component companies commit fraud

Dear Editor:

Oh boy. "The Phantom Component: A science fiction story" (EDN, November 14, 1985, pg 67) has nothing to do with components. The subject is honesty, cheating, and fraud. Appropriate questions to ask readers would be:

I buy components from a cheating, lying, misrepresenting company.

Circle No 521

I am a sucker for a tantalizing sales pitch.

Circle No 522

I look for honesty in the companies I deal with.

Circle No 523

Sincerely yours, Gus Ositis Ositis Electronics Orinda, CA

## **Engineers need early product information**

Dear Editor:

I read your November 14, 1985, editorial on phantom components (EDN, pg 67) with great interest. Phantom components are a real problem. However, limiting information on a new product until a certain number of days before it's available is not the solution. Because of the rapid rate of technological advancement, engineers need as much information as they can get, as early as they can get it, on new products.

Engineers do need to know the new products' status, however. Your editorial staff can play a major role in both determining the significant items that should get readers' attention and providing candid and realistic assessments of companies' claims regarding product availability.

Sincerely yours, Fan-Chia Tao Senior Engineer Kurzweil Computer Products Cambridge, MA

## HP 3852S features 1-μV sensitivity

Dear Editor:

Thank you for reporting on our new HP 3852S data-acquisition system in EDN's October 31, 1985, issue (pg 306). We're glad you found the product's features of interest to your readers.

A small typo did appear in the writeup, however. We at HP's Loveland Instrument Div are the keepers of the microvolt, and when you stated twice that our 5½-digit digital multimeter has 1-mV sensitivity instead of 1-μV sensitivity, you certainly raised the sensitivity level around here.

Sincerely yours,
William S Porter
MARCOM Manager
Loveland Instrument Div
Hewlett-Packard Co
Loveland, CO

#### Corrections


In EDN's 1985  $\mu$ P/ $\mu$ C Chip Directory (EDN, November 28, 1985, pg 106), the entry for Fairchild's Clipper included the address and phone number for the manufacturer's Microcontroller Div instead of the Advanced Processor Div, which is responsible for the Clipper. For information on the Clipper, please contact:

Fairchild Advanced Processor Div Fairchild Semiconductor Corp 4001 Miranda Ave Palo Alto, CA 94304 Phone (415) 858-4361.

One other item of note regarding the Clipper: EDN stated that the cost "should be at least \$100 per basic 3-chip set." The official price is \$2451.80.

The phone number listed for Metacomp Inc in the November 28, 1985, Product Update on the company's MPA-1000 Multibus Computer (EDN, pg 98) is incorrect. The correct number is (619) 578-9840.


# MUCHNESS & QUICKNESS.



4SZ-4151 R1

# SPRAGUE You can get Sprague Type 592C Monolythic® Multilayer Ceramic Capacitors in a hurry. These conformally-coated units offer you a lot of advantages. They're widely-used for bypass and decoupling applications in computers, and are an excellent replacement for the more expensive molded designs. Stocked for off-the-shelf shipment in both large and small

quantities from Sprague distributors. Popular ratings are available in five formulations including Z5U, Y5U, X5R, X7R, and C0G. Supplied in EIA Standard RS-296 and tape-and-reel packaging for automatic insertion. They're competitively priced. Write for Engineering Bulletin 6248A to Technical Literature Service, Sprague Electric Company, 41 Hampden Road, P.O. Box 9102, Mansfield, MA 02048-9102.



## IT'S BASIC TO ASIC.

- \* Free design manuals, cell manuals, and software libraries for Daisy, Mentor, and FutureNet workstations.
- \* 100 first pre-production pieces free.
- \* Guaranteed prototype delivery dates.
- \* Guaranteed NRE and no additional CPU charges.
- \* Guaranteed production prices for two years.

Announcing the Siliconix 5-Star Service™ Program. Anything else is just basic ASIC.

5-Star Service means the end of excessive up-front charges for gate array designs. So you can buy gate arrays as easily as if they were completely standard products.

Compare us with your current supplier on your next job.

Call (408) 970-4107.

We'll send you a complete fact sheet, free. You'll find that we not only give you better control over the design process, but we also save you a lot of money.

In fact, the only money we can't save you is the money you've already spent with our competitors.

Siliconix

### SMART FORCE™ INVERTERS FOR ECTROLUMINESCENT LAMPS



- Exclusive LPS Series 1 matrix of inverters makes foil-type EL designs easier than ever! Less expensive
- LPS inverters use the original Smart Force compensating circuit to help ensure longer useful EL lamp life.
- · Wide variety of low DC input voltages available.
- LPS...from ERG the leader in EL power technology. More inverters for more EL applications than any other manufacturer in the world.

Call today for complete product information and pricing:




#### Endicott Research Group. Inc.

2601 Wayne Street, P.O. Box 269, Endicott, NY 13760 (607) 754-9187 TWX: 510-252-0155 VISA

**CIRCLE NO 104** 

Dealer Inquiries

Bishop Graphics introduces its unique, new, low-cost CÂD/CÂM System for printed circuit board design, layout and manufacturing applications...QUIK CIRCUIT™ You can master Bishop's Quik Circuit the very first day, and design printed circuit boards up to  $30'' \times 30''$  with a full range of standard or custom pad sizes and shapes; circuit traces of virtually any width; squares, holes, feed throughs, etc. for single, double or multilayer boards.



And, you can get finished boards directly from your design data. Find out how. Call toll-free (800) 222-5808 for the name of your nearest Bishop CAD dealer, (818) 991-2600 in Alaska, Hawaii and California.

Bishop Graphics, Inc.

5388 Sterling Center Drive Westlake Village, CA 91359 U.S.A. Telex: 66-2400 Bishop WKVG

**CIRCLE NO 109** 

Invited

### CALENDAR

iRMX 86 for Users (short course). Madison, WI. Donna Miller, Micro-Managers Inc, 1435 E Main St, Madison, WI 53703. (608) 251-6661. February 10 to 14.

Grounding and Shielding (short course), San Antonio, TX. Penny Caran, Interference Control Technologies, State Rte 625, Box D, Gainesville, VA 22065. (703) 347-0030. February 18 to 21.

IEEE Annual Meeting, San Jose, CA. IEEE, 10th Fl, 345 E 47th St, New York, NY 10017. (212) 705-7647. February 18 to 19.

IEEE ISSCC '86 (International Solid-State Circuits Conference), Anaheim, CA. Lewis Winner, 301 Almeria Ave, Coral Gables, FL 33134. (305) 446-8193. February 19 to 21.

AutoCADCon 86, Rosemont, IL. CAD Design Systems Inc, 1305 Remington Rd, Suite D, Schaumburg, IL 60195. (312) 882-0114. February 20 to 21.

C Programming Workshop, Bellevue, WA. Specialized Systems Consultants Inc, Box 55549, Seattle, WA 98155. (206) 367-8649. February 24 to 28.

Nepcon West '86, Anaheim, CA. Banner and Greif, 110 E 42nd St. New York, NY 10017, (212) 687-7730. February 25 to 27.

Compcon Spring, San Francisco, CA. IEEE Computer Society, 1730 Massachusetts Ave NW, Washington, DC 20036. (203) 371-0101. March 3 to 6.

First International Conference on CD ROM, Seattle, WA. Microsoft Corp, Box 97200, Bellevue, WA 98009. (206) 828-8080. March 3 to 6.

Dexpo Europe 86 (DEC-Compatible Exhibition and Conference), London, UK. Expoconsul International Inc, 3 Independence Way,



Starting today forget about allotting board space to single DACs. Our line of multiple DACs is packaged in narrow 0.3" DIPs.

So, you save board space as well as component count and dollars. Furthermore, since the overhead logic and latches are shared by two to four DACs, you save on power dissipation. And you know what that means for reliability.

Analog Devices gives you the broadest line of space-saving multiple DACs in the industry. Everything from duals to quads and back again. There's a logical reason for this. Our advanced linear CMOS technology enables us to offer outstanding functional density and the reliability you get only in these high performance multiple DACs.

For more information on our multiple DAC family call your local Analog Devices Sales Office for specification sheets on the four DACs included here.

Then you can forget about ever being desperate for board space again.



AD7549 NEW Model AD7549

Description Dual 12-bit Monolithic Multiplying DAC
Output Current

Package 20-pin, 0.3" narrow DIP

AD7225 NEW Model AD7225

**Description** Quad 8-bit CMOS DAC with Output Amplifiers, Separate Reference Inputs for multiplying applications. Double Buffered Latch Structure for Simultaneous Update

Output Voltage Package 24-pin, 0.3" narrow DIP

**AD7528 Model** AD7528

Description Dual 8-bit Monolithic Multiplying DAC Output Current

Package 20-pin, 0.3" narrow DIP

AD7226 Model AD7226

**Description** Quad 8-bit CMOS DAC with Output Amplifiers, common reference input for all four DACs Output Voltage

Output Voltage Package 20-pin, 0.3" narrow DIP

# When you're desperate for board space, try our multiple DACs.

Analog Devices, Inc., Two Technology Way, Norwood, MA 02062-0280; Headquarters: [617] 329-4700; California: [714] 641-9391, [619] 268-4621, [408] 947-0633; Colorado: [303] 590-8906; Illinois: [312] 653-5000; Maryland: [301] 992-1994; New York: [716] 425-4101, [315] 437-5277; Ohio: [614] 764-8795; Pennsylvania: [215] 643-7790; Texas: [214] 231-5094, [713] 664-6704; Washington: [206] 251-9550; Belgium: [3] 237-48-03; Denmark: [2] 845800; France: [1] 687-34-11; Holland: [1620] 81500; Israel: [052] 28995; Italy: [2] 6883831, [2] 6883832, [2] 6883833; Japan: [3] 263-6826; Sweden: [8] 282740; Switzerland: [22] 31-57-60; United Kingdom: [01] 9410466; West Germany: [89] 570050

**CIRCLE NO 79** 

#### NEW precision instrument for voltage measurement of high voltage D-C

Model RD 200 Model RD 100 Model RD 50

power supplies that also measures A-C ripple component

- Three models rated at 50, 100, 200 KVDC max
- Measurements accurate to 0.25% of full scale
- Guarded and equipotentially shielded for minimum leakage
- Temperature coefficient: less than 100 ppm/degree C
- Voltage coefficient: less than 1 ppm/volt

The Glassman RD Series

#### GLASSMAN HIGH VOLTAGE INC.

Route #22 (East), Salem Park, P.O. Box 551, Whitehouse Station, N.J. 08889 (201) 534-9007 • TWX 710-480-2839

CIRCLE NO 114



#### CALENDAR

Princeton, NJ 08540. (609) 987-9400. March 4 to 6.

Power UK '86, London, UK. TCM Expositions Ltd, Exchange House, 33 Station Rd, Liphook, Hampshire, GU30 7DN, UK. (0428) 724660. March 4 to 6.

Design/Drafting with Surface Mount Devices (short course), Milwaukee, WI. Peter Tocups, University of Wisconsin-Milwaukee, 929 N 6th St, Milwaukee, WI 53203. (414) 224-3952. March 5 to 7.

7th Annual Computer Graphics Conference, Hollywood, FL. Frost & Sullivan, 106 Fulton St, New York, NY 10038. (212) 233-1080. March 5 to 7.

CAD/CAM/CAE Winter Workshops, San Diego, CA. Jack Sanders, CAD Report, 841 Turquoise St, Suite D, San Francisco, CA 92109. (619) 488-0533. March 6 to 7.


CIMTECH '86, Boston, MA. Society of Manufacturing Engineers, Box 930, Dearborn, MI 48121. (313) 271-1500. March 10 to 13.

Integrated Services Digital Networks Exposition, Dallas, TX. Information Gatekeepers Inc, 214 Harvard Ave, Boston, MA 02134. (617) 232-3111. March 10 to 14.

Structured 8086/186 Assembler (short course), Madison, WI. Donna Miller, Micro-Managers Inc, 1435 E Main St, Madison, WI 53703. (608) 251-6661. March 10 to 14.

Automated Design and Engineering for Electronics (ADEE) West, Moscone Convention Center, San Francisco, CA. Banner and Greif Ltd, 110 E 42nd St, New York, NY 10017. (212) 687-7730. March 11 to 13.

Southcon, Orlando, FL. Electronic Conventions Management, 8110 Airport Blvd, Los Angeles, CA 90045. (213) 772-2965. March 11 to 13



At CTD, we offer total system integration with our TM6000 Silicon Gate CMOS Analog/Digital Semi-Custom Array, plus CMOS Digital Gate Array and Thick Film Hybrids.

Our Macrocells Library, available on Daisy CAE workstation and in hardware kit parts, include D/A, A/D converters, VCO, switched capacitor filters, and many



more. Call or write today to order our comprehensive TM6000 Design Manual at US\$70.



249 Jalan Boon Lay, Singapore 2261 Tel: (65)-265-1066, Tlx RS 21419 FAX: (65)-261-0766

a member of Singapore Technology Corporation



Representatives/Distributors:

**Hong Kong:** Karin Electronic Supplies Co. Ltd. Tel. No: 3-898252. • **Taiwan:** General Industries (Taiwan) Inc., Tel. No: 02-764-5126.


# Cahners Means Business

# In Readership


When you advertise in a business magazine you want to make sure the magazine is read by the people who receive it. Readership is really what you are after when you advertise. Cahners magazines are very well read. Every year we publish over 33,000 pages of news, articles, and features in our 33 magazines. Virtually every editorial page of every issue of a Cahners magazine is analyzed and tested to ascertain its interest to the readers. Much of this testing is done by the Cahners 270 editors who maintain contact with their readers through focus groups, reader panels, and mail and telephone surveys. Also, Cahners Research conducts over 300 in-depth studies of readership. We put all of this research to work to give our readers more valuable, more readable magazines; and to give our advertisers a better showcase for their products and services. When it comes to readership, Cahners Means Business. That's why we're the first choice of American business in specialized business magazines.

#### Cahners Publishing

33 Specialized Business Magazines for Building & Construction, Electronics & Computers, Foodservice, Manufacturing, and Health Care.



# Software?







Of course Ziatech gives you the highest performance in STD Bus hardware: STD-8088. But we further extend the power of the compact STD Bus by offering the most complete support in the industry. Sophisticated development software. Explicit documentation. Detailed application notes.

And you even get Ziatech's engineering staff oncall to help you with implementation. What's more, every Ziatech board is backed by a comprehensive two-year warranty.

For a free sample of Ziatech support just send in the coupon.

Free System Designer's Guide

I want to find out how the Ziatech Series 8800 can be my high power, low cost system design solution. Please send me my free STD-8088 Designer's Guide and Application Note immediately.

NAME

TITLE

PHONE

APPLICATION

COMPANY

ADDRESS

CITY

STATE

ZIP


STD DOS™ is a trademark of Ziatech Corporation polyFORTH is a trademark of FORTH, Inc.



3433 Roberto Court San Luis Obispo, California 93401 USA 805/541-0488 ITT Telex 4992316

#### EDITORIAL

#### Cooperation—at last



Will wonders never cease! The hardware folks and the software folks are actually talking to each other! And they're not even calling each other names! For once, they're cooperating in a way that will benefit all of us.

Their cooperation has resulted in the Computer Graphics Interface (CGI), an interface between hardware and software in graphics systems. CGI is great for software designers, because it defines a rich set of standard, high-level, hardware-independent graphics instructions. It's great for hardware designers, too, because semiconductor manufacturers such as Texas Instruments and Motorola are now implementing it in silicon in their latest graphics-processor ICs. Some of the new chips' instruction sets are actually CGI instructions in off-chip ROM, and they speed up graphics processing enormously. As Southwestern Editor Steve Leibson reports in our cover story (pg 104), graphics systems implemented with the new chips can perform at speeds previously reached only with bit-slice processors.

Semiconductor companies, recognizing that their expertise lies in implementing designs in silicon, have been turning to outside experts for help in specifying those designs. For CGI, semiconductor giants TI and Motorola turned to the relatively small Graphics Software Systems (Beaverton, OR) and Nova Graphics International (Austin, TX), which specialize in CGI and other graphics software. These software companies helped the IC manufacturers define products that deliver high performance and yet avoid unnecessary difficulty in software development. By providing, in silicon, features desired by software developers, these products obviate the need for special software that converts high-level instructions into low-level command strings.


The high degree of cooperation between hardware and software specialists in developing CGI is commendable, but the benefits of such cooperation needn't be limited to graphics ICs. All digital designs can benefit from such cooperation, and it's high time that regular consultation between hardware and software designers be a part of all projects. Otherwise, we're apt to develop products that do wonderfully what they're designed to do, but don't do what


anyone wants them to do.

Gary Legg Editor


Hary Legg

# THE 68454: THE FIRST TRULY INTELLIGENT DISK CONTROLLER.





# How to prevent failures in communication.





Check your datacomm designs with an HP protocol analyzer. And you can catch problems before they become a problem.

The HP family of protocol analyzers makes testing so quick, so simple, so complete and so accurate, you can get better products to market in a fraction of the time.

Obviously, the most crucial part of your R&D is developing your products to standards. So we offer a full range of high-level decode/simulation software packages, including SNA, X.25 certification, DDCMP, BSC, X.21, and CCITT #7.

And no matter which of our analyzers you choose, they operate from standard interfaces. They'll also communicate with each other and transfer test programs as well as remotely collected data.

On an individual level, the HP 4951B offers you the best performance for the money on data rates up to 19.2 kbps. The HP 4953A takes you to 72 kbps for full simulation, and 256 kbps for monitoring. And the HP 4955A adds a built-in BASIC interpreter for development of proprietary protocols.

Their remote capabilities let you extend your R&D outside the lab to your customer's site when field service engineers need design back-up during troubleshooting.

So if you want to design better, faster write to: Hewlett-Packard, Attn. Marketing Communications, P.O. Box 7050, Colorado Springs, CO 80933. Or contact your local HP office and ask for a field engineer.

We'll help you communicate better in the future.



### Design challenges attend application of monolithic voltage-comparator ICs


Tarlton Fleming, Associate Editor

Most of today's comparators are mature, versatile products. You can buy them in a wide range of speeds, but unwelcome characteristics (low gain, high bias current, etc) are prevalent among the older models. The performance of newer devices is impressive, but their behavior remains temperamental, and designing with voltage comparators is still a difficult task. The comparator function demands high gain and wide bandwidth-properties not easily combined on one IC-and the manufacturer's option to trade one for the other is restricted, because the typical application requires both.

One consequence of this inherent design problem is the limited variety of comparator types available (compared, for example, with the wide variety of op amps). Therefore, the best comparator you can choose for a given application is likely to be a rough fit, forcing you to design around the comparator's limitations. Depending on the part, these limitations can include high input bias currents, low gain, narrow common-mode range, nonstandard supply-voltage requirements, and a tendency to oscillate.

You surmount most of these comparator shortcomings at the cost of increased circuit complexity, and your specific added design tasks depend on the type of comparator you initially choose. Comparators fall into three rough categories determined by speed (assuming you set aside a few maverick devices for separate discussion).

At the top end are devices that are based on bipolar ECL and fea-



Furnishing a 10-nsec propagation delay, the LT1016 bipolar precision comparator from Linear Technology Corp has latched complementary outputs and offers stability in its linear region of operation.


ture propagation delays as short as 2 nsec. With one exception, these comparators come with standard pinouts. Next are the middle-performance comparators, few in number, that attempt to provide as much speed and accuracy as possible in one device. The majority of these are used in A/D converters with 10-bit resolution or better.

In the third category you find most of the comparator population—1-bit A/D converters with response times from 200 nsec to several microseconds. These devices include low supply-voltage versions, low-power versions, FET-input ver-

sions, and dual and quad versions. They suit a wider spectrum of applications than many designers realize. Because comparators have a reputation for unpredictable behavior (they might burst into oscillation, blurring their own switching threshold, or they might create spurious pulses by chattering over a decision they have made), engineers are wary of these components and often choose a circuit approach that avoids comparators altogether. The use of comparators can, however, reduce your cost and component count (Ref 1).

The fastest voltage comparators

# TOPAZ is DMOS And DMOS is...




CDG5341-Monolithic CMOS/DMOS "T" switch

#### ... Video Switching


With the lowest capacitance-R(on) figure of merit, DMOS FETs give you more than 70 db of 'OFF' isolation at 20 MHz (CDG5341). And it's still 55 db at 100 MHz. Combine them with CMOS on the same chip and get an IC that can control ± 10 volts with 5 volt logic. They come as multiplexers... or DPDT switches... or SPDT... or ...

#### ... Sub Nanosecond Analog Switching

If fast switching is your thing, then reach for a DMOS. Its input capacitance is so low that driven from a low impedance source, sub nanosecond turn ons... and offs... are easy. Choices of low 'ON' resistances and voltage ranges handle almost every application. And our choice of packages ranges from plastic TO-92's and DIPs through military and custom arrays.



Sub Nanosecond Buffer



Complementary DMOS. Control 80V with 5V Logic

#### ... High Voltage Analog Switching

Complementary pairs handle up to 85 volts. And we've got FETs that go to 650 volts.

We use low power packages for the best packing density. But, if you need more we can give you a multi chip package, because we specialize in both standard and custom multiple chip arrays.

TOPAZ specializes in low to medium power DMOS in both vertical and lateral types. We make proprietary parts, and most of the industry standards. We've got the SD210-215...SD5000 series...ANO1 series...VN01 series...VP01 series...If you can't find what you need in our catalog, then call us; we'll spec out a special. Want more information? Write, call or check the 'bingo'...We'll send you our catalog and some 'app' notes.

TOPAZ SEMICONDUCTOR

1971 N. Capitol Ave., San Jose, CA 95132 Ph.: 408/942-9100 TWX: 910/338-0025

FREE seminar in Boston March 5, 9 to 11:30 A.M. MARRIOTT Hotel, Burlington. For reservations call (617) 964-6205 and ask for Arletta

you can buy today are the bipolar-ECL types offered by Advanced Micro Devices, Plessey, Honeywell, Analog Devices, and LeCroy. (All are monolithic; comparators based on hybrid construction methods are generally proprietary designs not offered commercially.) Except for LeCroy's Model MVL407 monolithic quad comparator, the models in this group are all plug-compatible with either the single Am685 or dual Am687 types originally introduced by Advanced Micro Devices.

AMD's Am685, for example, specs a 6.5-nsec max propagation delay at 25°C under the standard test conditions: a 100-mV step with 5-mV overdrive. (Overdrive is the input differential voltage in excess of the value required to drive the output voltage to its logic-threshold value.) The voltage gain-approximately 1600-is fine for use in automatic test equipment (ATE) but generally impractical for use in mass-produced A/D converters. The Am685's 6V, -5.2V supply-voltage requirements are a headache for systems designers, but these nonstandard values are necessary to support ECL-compatible output logic levels (approximately -1.75V and -0.85V).

Supply voltages are less of a problem for the single, TTL-compatible Am686 (5V, -6V) and the dual, ECL-compatible Am687 (5V) -5.2V). Fabricated using a Schottky-clamped bipolar process, all three AMD comparators come in 16-pin DIPs; other package options include an 8-pin DIP, a 20-contact LCC, and a 10-lead metal can. These devices furnish complementary logic outputs and a latch-enable input. The Am687 offers a complementary latch enable as well.

#### Racehorse comparators

Plessey Semiconductors' SP9685 and SP9687 ECL-compatible comparators spec faster (2.5-nsec) propagation delays. These models and the similar AD9685 and AD9687 from Analog Devices are pin-com-

patible with the Am685 and Am687, respectively. AMD has answered with the Am6685 and Am6687, comparable to the parts from Plessey, and Honeywell Signal Processing Technologies has recently intro-HCMP96850 the and HCMP96870. All of these secondgeneration ECL-compatible comparators employ a combination of process and circuit enhancements to achieve response times between 2 and 3 nsec. AMD's proprietary IMOX process, for example, provides shallow-junction ion-implanted transistors with a low junction capacitance and short transit


The Honeywell parts' guaranteed differential propagation delay, or skew (±300 psec, input to output; ±200 psec, latch to output), can reduce your system-recalibration requirements, according to product-marketing manager Randel Castelberry. This guarantee applies both to comparators within a package and to comparators in different packages.

All of these very fast comparators require 5V/-5.2V supplies, except the Am6685 (6V/±5.2V). Model MVL407 from LeCroy Research Systems offers similar speed

and ECL-compatible outputs but operates from ±5V supplies. The monolithic MVL407 provides four comparators in a 20-pin DIP. Each comparator has complementary outputs, and an internal 3.5-mV hysteresis stage allows comparison of low-level or slowly changing signals without oscillation. Latches are not included in this model.

#### Speed is key for ATE

The major application for highspeed dual comparators is in ATE systems. Testers of high-pin-count digital ICs in particular use four to eight comparators per pin just to verify digital switching thresholds and to generate timing intervals. Each of these jobs requires two comparators, so the dual units offer convenience, plus the advantage of closely matched electrical parameters that track each other with variations in temperature and supply voltage. You can produce a precise pulse width (time interval), for example, by connecting a NAND gate's inputs to the outputs of two comparators that are fed by the same fast voltage ramp. The pulse width obtained in this way remains unaffected, because each comparator's performance will change by the



Used primarily in ATE systems, the Am6687 high-speed comparator has dual complementary latched outputs that are ECL compatible. Propagation delay is less than 3 nsec.

same amount and in the same direction.

Comparator speed is the main consideration in these ATE applications because it directly affects the tester's throughput rate. Although this speed is obtained at the expense of higher input bias currents, fast comparators can be used as they are in about half of all ATE applications. In the other applications, you must add a FET-input stage or use other means to buffer the comparator's bias current, ac-

cording to Pete Sylvan, a design engineer for Teradyne Inc. In general, ATE systems can tolerate the moderate gain and high power dissipation associated with fast comparators.

#### Stable in the linear region

Also in the fast-comparator class is Linear Technology's 10-nsec model LT1016C, which has complementary TTL-compatible latched outputs. The negative supply current is only 3 mA, yielding about

140 mW for total power dissipation—approximately half that of comparable ECL types. In addition, the low input-offset voltage (3 mV max) suits this device to use in successive-approximation A/D converters. What's more, the LT1016C is stable in its linear region—a feature not available in any other high-speed comparator, according to the company. This stability reduces the problem of oscillation when handling slow-moving input signals. Also, of course, it eliminates the

MANUFACTURER AND MODEL <sup>1</sup>	RESPONSE TIME <sup>2</sup> (nSEC TYP)	VOLTAGE GAIN (V/mV MIN) <sup>3</sup>	INPUT BIAS CURRENT (μΑ MAX) <sup>3</sup>	INPUT OFFSET VOLTAGE (mV MAX) <sup>3</sup>	DIFFERENTIAL INPUT VOLTAGE (V MAX)	SUPPLY VOLTAGE (V TYP)	POWER DISSIPATION (mW TYP) <sup>3</sup>	COMMENTS
ANALOG DEVICES AD9685 AD9687	2.2 2.7	Ė	20 20	±5 ±5	±2.5 ±2.5	+5/-5.2 +5/-5.2	210 430	ECL-COMPATIBLE ECL-COMPATIBLE, DUAL
ADVANCED MICRO DEVICES Am685-L (INDUSTRIAL) Am686C Am687	5.3 9.0 7.0	- - -	10 10 10	±2 ±3 ±3	±3.3 -3.3/+2.7 -3.3/+2.7	+6/-5.2 +5/-6 +5/-5.2	300 MAX 415 MAX 485 MAX	ECL-COMPATIBLE TTL-COMPATIBLE ECL-COMPATIBLE, DUAL
LH2311 Am6685 Am6687	200 2.5 2.5	200,000 TYP — —	0.25 15 TYP 15 TYP	±7.5 ±0.5 TYP ±0.5 TYP	±13 ±3 ±3	±15 +6/-5.2 +5/-5.2	 180 360	STROBED OUTPUT, DUAL ECL-COMPATIBLE ECL-COMPATIBLE, DUAL
FAIRCHILD μΑ711C μΑ734C μΑ760C	40 200 16	700 35,000 7000 TYP	100 0.05 60	±5 ±5 ±6	±5 MIN ±10 MIN ±5 TYP	+12/-6 ±15 ±6.5	130 145 MAX 175	STROBED OUTPUT, DUAL
HARRIS HA-4905	215 MAX	400,000 TYP	150	±7.5	±15	+5, ±15	190	QUAD; SINGLE-SUPPLY OPTK
HONEYWELL HCMP96870	2.0	-	20	±5		+5/-5.2	_	ECL-COMPATIBLE, DUAL
INTERSIL ICL8001C	250	15,000	0.25	±5	±10 MIN	+5/±15	30	LOW POWER; THIN-FILM RESISTORS
LeCROY MVL407	2.5	_	7.0	_	-2/+1.7	±5	420	ECL-COMPATIBLE, QUAD
LINEAR TECHNOLOGY LT1011AC LT1016C LT1017C LT1040C	150 10 1500 80k	200,000 1400 316,000	0.025 10 0.015 0.3	±0.5 ±3 ±1 ±0.5	-14.5/+13 -3.75/+3.5  ±5V	±15 ±5 1.15 TO 40 ±5V	74 140 0.15 0.0025	5V SUPPLY OPTION LATCHED OUTPUT; SINGLE- SUPPLY OPTION LOW-POWER DUAL CMOS SWITCHED-CAPACITOR DUAL
MOTOROLA MC1414	40	1000	25	±5	±5	+12/-6	230	STROBED OUTPUT, DUAL
NATIONAL SEMICONDUCTOR LF311 LM319 LM361 LM393	200 80 14 1300	200,000 TYP 8000 3000 200,000	150 pA 1.0 10 TYP 0.25	±10 ±8 ±5 ±5	-13.5/+14 ±13 ±5 0/+3	±15 ±15 +5/±10 5	138 165 250 2	FET-INPUT DUAL ±15V SUPPLY OPTION LOW-POWER DUAL, ±15V SUPPLY OPTION

Table continues on pg 50

# The Latest Word in Gate Arrays: Microtachyanorexilogopraxis



And a few words of explanation.

Raytheon introduces a family of advanced Oxide-Isolated bipolar gate arrays combining density, high speed, low power consumption, and Integrated Schottky Logic. The 5,040 gate, 150 I/O, CGA 50L15. The 3,584 gate, 124 I/O, CGA 35L12.

□ High performance: 1.2 nS,  $160 \mu\text{W}$  (typical) gate performance for <0.2 pJ speed-power product. Selective enhancement to 1.0 nS. (Runs twice as fast as CMOS, without severe loading degradation. And total chip dissipation <1.5 W at top speed.) Full military

performance, radiation hardness.

☐ Flexible service and support:
complete integration of design and
manufacturing eliminates gate array
anxieties. Fully automated CAD (including conversion from logic simulation to placement and routing, linkage
between logic simulator and tester).
Flexible customer interface points,
program manager support.

You have our words on bipolar gate arrays, redefined. We'd like to get the word on your application.

**CIRCLE NO 42** 

Raytheon Company Semiconductor Division 350 Ellis Street Mountain View, CA 94039-7016 (415) 966-7716

Access to the right technology

Raytheon

			INPUT	INPUT	OMPARATO			
MANUFACTURER AND MODEL <sup>1</sup>	RESPONSE TIME <sup>2</sup> (nSEC TYP)	VOLTAGE GAIN (V/mV MIN) <sup>3</sup>	BIAS CURRENT (µA MAX) <sup>3</sup>	OFFSET VOLTAGE (mV MAX) <sup>3</sup>	DIFFERENTIAL INPUT VOLTAGE (V MAX)	SUPPLY VOLTAGE (V TYP)	POWER DISSIPATION (mW TYP) <sup>3</sup>	COMMENTS
PLESSEY SP9685 SP9687	2.5 2.5	250 250	20 20	±5 ±5	±2.5 ±2.5	+5/-5.2 +5/-5.2	292 MAX 584 MAX	ECL-COMPATIBLE ECL-COMPATIBLE, DUAL
PRECISION MONOLITHICS CMP-01E CMP-02E CMP-04FP CMP-05E	110 190 1300	200,000 200,000 70,000 8000	0.6 0.05 0.2 1.2	±0.8 ±0.8 ±2.0 ±0.25	±12.5 ±12.5 0/+3.5	±15 ±15 +5	103 99 60 105	LOW INPUT CURRENT LOW-POWER QUAD; SINGLE SUPPLY OPTION HIGH SPEED; LATCHED OUTPUT
RAYTHEON RC4805E	30	15,000 TYP	2.5 TYP	±0.8	±2	<u>±</u> 5	140	HIGH SPEED; LATCHED OUTPUT
SIGNETICS NE521	18.001 <b>8</b>	_	40	±10	±3	±5	210	HIGH-SPEED DUAL; STROBE
NE527	16	_	4	±10	±5	+5/±10	250 MAX	OUTPUT COMPLEMENTARY STROBED OUTPUTS
NE529	≥0 <u>0</u> 0 12		50	±10	±5	+5/±10	250 MAX	COMPLEMENTARY STROBEL OUTPUTS
SILICONIX L161C	5000	10,000	0.2	±6	-3/+1.3	±3	1.26	LOW-POWER QUAD; ±15V SUPPLY OPTION
TEXAS INSTRUMENTS TL510C TL331C TL506C	30 1300 28	10,000 200,000 TYP 40,000 TYP	20 0.25 25	±3.5 ±5 ±5	±5 0/+3.5 ±5	+12/-6 +5 +12/-6	90 2.5 186	STROBED OUTPUT ±15V SUPPLY OPTION, LOW POWER DUAL; STROBED OUTPUT
TLC372C TLC374C	650 900	200,000 TYP 200,000 TYP	1 pA TYP	±10 ±10	0/+3.5 0/+3.5	+5 +5	1.0 2.0	CMOS, DUAL, LOW POWER CMOS, QUAD, LOW POWER
(SEE NOTE 4) LM311 LM319 LM339	200 80 1300	40,000 8000 200,000 TYP	0.25 1.0 0.25	±7.5 ±8 ±5	-14.5/+13 ±13 0/+3.5	±15 ±15 +5	138 165 4	DUAL LOW-POWER QUAD

#### NOTES

- 1. COMPARATOR MODELS LISTED ARE COMMERCIAL-TEMPERATURE-RANGE VERSIONS (PARAMETERS SPECIFIED AT 25°C) UNLESS OTHERWISE INDICATED.
- 2. RESPONSE TIMES ARE BASED ON A 100-mV STEP WITH 5-mV OVERDRIVE.

3. UNLESS OTHERWISE SPECIFIED.

4. THESE MODELS ARE MANUFACTURED BY NATIONAL, TI, MOTOROLA, SIGNETICS, AND OTHERS.

need for latch-circuit hysteresis, which is used in some comparators to prevent oscillation in the linear region.

One step down in speed are the comparators whose major application is in successive-approximation A/D converters of hybrid construction. These comparator types do strenuous work; they need both high speed and high gain. Too much speed (bandwidth) or gain, however, will cause the comparator to oscillate as a consequence of the unavoidable parasitic capacitance between output and input. Because of this constraint, comparators limit the achievable resolution and conversion time for many successive-

approximation A/D converters.

Still, a minimum value of gain is required to ensure that the comparator output will switch reliably in response to a small input overdrive. Equally important, the comparator output must complete this output transition in time to respond properly to the converter's next bit decision. In a 12-bit converter, for example, the comparator must perform satisfactorily with an overdrive of ½ LSB, and preferably with less than that. If ½ LSB=1.22 mV and the comparator's output must change by 2V, the necessary gain is  $2 \div 0.00122$ , or about 1640 min. Unfortunately, few of the comparators that offer enough speed for

competitive A/D-converter designs can guarantee this much gain.

In some cases, hybrid converter manufacturers solve the gain problem by adding a discrete voltage amplifier in front of the comparator chip. A voltage amplifier with a gain of 50 to 80 allows the use of LM311 and LM319 comparators that otherwise would be unsuitable for these applications.

#### Suitable for A/D converters

Precision Monolithics' CMP-05E precision comparator is among the few devices suitable for use in 12-bit A/D converters. It guarantees a voltage gain of 8000 and a 55-nsec propagation delay with 5-mV over-

#### STANDARDS UPDATE

#### **FCC TELECOM RULES, PART 68**

Clarification of the 2nd, 3rd and 4th Report and Order (Docket 81-216) was offered by Mr. Bill Von Alven of the FCC to attendees of the EIA/ITG Conference in Washington, DC. The November conference attracted over 150 persons from the telephone and related industries to a series of specialized talks and demonstrations focussed on telephone interconnect issues.

The 2nd Report and Order now allows the connection of digital Network Channel Terminating Equipment to the network, while at the same time requiring testing and registration as with analog devices.

The 3rd Report and Order cleared up a number of rules and most particularly changed the signal power and on-hook resistance limits under Part 68. The 4th Report and Order offered clarification on the standards for alarm dialers.

The premier public demonstration of a specialized Part 68 Workstation™ from Compliance Design Incorporated also highlighted the EIA/ITG. Attendees saw demonstrations of a single rack setup that incorporates all the equipment necessary to test to the electrical specification of Part 68.

The Workstation tests include: (1) hazardous voltages and currents, (2) signal power limitations, (3) balance, (4) impedance limitations, (5) billing protection, and (6) surge. By putting all this technology together in a single unit, Compliance Design has made testing to the Part 68 specification simpler and easier than with jury-rigged collections of equipment now used in many locations. Cost of the Part 68 Workstation is \$49,950 (FOB Boxborough, MA) and includes complete documentation plus one full day of training. Circle the Compliance Design Reader Service Number below for more information.

#### FCC EMISSIONS RULES - COMPUTERS, PERIPHERALS, AND ELECTRONIC EQUIPMENT, PART 15

A complaint from Keytronics to the Federal Communications Commission has caused government action against a foreign manufacturer. Five retail outlets have been cited for handling Model 5151 keyboards made by the Taiwanese firm Behavior Communications. Keytronics complained that the keyboards did not have the proper FCC authorization and that Behavior Communications therefore had an unfair trade advantage.

As budgets are trimmed in Washington, investigation and enforcement rely more and more heavily upon tips and complaints like this. The Commission's resources are better spent in handling actual non-compliance cases than in routine cataloguing and rulemaking.

And attacking a manufacturer's or importer's distribution chain is one of the most effective remedies the Commission has in interdicting illegal equipment. Retailers, distributors, and even lessees and owners are liable for compliance with such regulations as FCC Part 15. Fines and possible imprisonment are effective deterrents to the sale of non-complying devices. There are several recent cases in which the FCC attacked distribution channels in an effort to stop the sale of non-complying devices.

#### **ELECTROSTATIC DISCHARGE**

Static problems sweep across the nation on the heels of cold, dry weather. Tied to this will be innumerable computer crashes resulting from electrostatic discharge (ESD). Though these failures are often misdiagnosed as line transients, the fact is that a variety of common occurrences as simple as a spark jumping from an operator's finger can be at fault.

Before a fatal data loss strikes your equipment, take steps to protect it and your customers from the hazards of ESD, advise the engineers at Dash, Straus & Goodhue, Inc. They can test, modify, and verify equipment as complying with industry and government standards.

An exclusive charge reservoir probe tip gives the Compliance Design ESD simulator a slew rate of up to 20,000 volts per nanosecond. It simulates the actual human-ESD event better than any other instrumentation, and allows engineers to test for ESD protection more accurately. For information on the simulator and ESD standards, contact Compliance Design.

#### COMPLIANCE ENGINEERING 1985-1986 NOW AVAILABLE AT NO CHARGE.

The leading reference book for compliance topics is now available free of charge to engineers, attorneys, and others with compliance responsibility. Topics covered include: FCC Part 15 and Part 68, CS-03 (Canadian, telecom interconnect), VDE (West German, emissions), and ESD. **COMPLIANCE ENGINEERING 1985–1986** is an expanded version of last year's first edition. It includes authoritative articles on design, test procedures, fixes, and legal rules and interpretations. To receive your copy at no charge, circle the Reader Service Number below.

All inquiries are handled in complete confidence.

For information on Dash, Straus & Goodhue, Inc., circle no. 43
For information on Compliance Design Inc., circle no. 133
For a copy of COMPLIANCE ENGINEERING 1985-1986, circle no. 134



Dash, Straus & Goodhue, Inc. 593 Massachusetts Avenue Boxborough, MA 01719 617-263-2662

drive. PMI's zener-zapping trimming method reduces the input-off-set voltage to 0.25 mV max. In addition, an output latch control allows you to make comparison decisions on a sampling basis.

Raytheon's Model RC4805E comparator is plug compatible with the CMP-05E. It specs a 30-nsec propagation delay but no guaranteed minimum gain (typical gain is 15,000). The device includes a latch for the TTL-compatible output. Linear Technology Corp's LT1011 offers 12-bit performance but requires an external latch for A/D-converter ap-


plications. This comparator specs a 250-nsec response time (150 nsec typ) and a gain of 200,000, guaranteed for a single 5V supply as well as bipolar supplies from  $\pm 5$  to  $\pm 15$ V. All specs but gain are guaranteed over the operating temperature range.

#### Speed compromises accuracy

Several other comparators are fast and therefore worthy of mention, but you may find their high bias currents unattractive for use in A/D converters with better than 8-bit resolution. Signetics' 22-nsec

max NE529, for example, specs a 50-μA input bias current; the 26-nsec NE527 reduces bias current to 4 μA by adding input emitter-followers to the input stage. The voltage gain is not specified for either product.

National Semiconductor's 20-nsec max LM361 and Fairchild's 16-nsec typ  $\mu$ A760C also require high bias currents. Their respective gain specs are 3000V/mV and 7000V/mV (the latter figure assumes the maximum allowed supply voltages). Both comparators provide complementary outputs. The LM361 includes an



An Am687 dual comparator senses voltage levels from a remote device under test in this digital option for LTX's LTX'77 linear/digital IC tester.

# RELIABLE FOUNDRY.

Comdial Semiconductor set the standard for guaranteed delivery of reliable CMOS/HMOS prototypes. Now, as Orbit Semiconductor, Inc., we will continue our commitment to guaranteed service.

Orbit's high reliability CMOS processes, N-Well or P-Well, extend to 2 micron feature sizes. The quality of our processing allows us to deliver product to Mil-Std-883C requirements. Mature processes, i.e. Synertek's, are also available.

Orbit guarantees on time delivery for engineering prototype runs.

≤ 10 working days Single Poly and Single Metal CMOS/HMOS

≤15 working days Double Poly or Double Metal CMOS

From prototyping to large volume production orders in wafer form or packaged parts, Orbit delivers on time. That's reliability you can count on.

	No. of days	Typical working days
Customer/Engineering interface	1	
Orbit accepts data base to films	3	234
Customer approval from film to first plate *	3	507
Wafer fab start to completion	10	8 9 10 11 12 13 14 15 16 17
Double poly start to completion	15	B 9 10 11 12 13 14 15 16 17 18 19 20 21 22
Double metal start to completion	15	8 9 10 11 12 13 14 15 16 17 18 19 20 21 22
25 cut and goes		

\*Typical customer approval



What others promise, we guarantee.

For information, please contact Gary Kennedy, President. 1230 Bordeaux Drive, Sunnyvale, California 94089 Telephone (408) 744-1800 TWX 910-339-9307 FAX (408) 747-1263

A subsidiary of Orbit Instruments Corporation.

CIRCLE NO 44

independent strobe for each output.

Not all comparator applications require high speeds. You probably wouldn't mind if a comparator took several microseconds to indicate a low battery voltage after it had monitored the battery for three weeks. The LT1040 from Linear Technology is suited to this and many other tasks requiring low power consumption. Based on a silicon-gate CMOS process and switched-capacitor circuit techniques, this dual sampling comparator draws only 1 nA while in the standby mode.

#### Unique circuit architecture

The LT1040 has little in common with more conventional comparators. Its A and B sections each have two pairs of differential inputs, and each comparator's output logic state follows the arithmetic sum (positive or negative) of voltages applied to its four input terminals. You can choose to sample these input voltages on command or to sample them at a rate set by an internal oscillator, with the frequency (0.1 Hz to 1 kHz) determined by an external resistor and capacitor. The comparator's response is completed 80 µsec after an external command or internal strobe, and it's independent of overdrive voltage.

Three additional outputs augment the LT1040's versatility. The pulsed-power terminal asserts the V<sup>+</sup> supply voltage for the duration of a comparison sample, letting you save power by activating an external circuit (a resistive bridge, for example) only when needed. The  $\overline{(A+B)}$  output connects the comparator outputs in a NOR gate to simplify window-comparator hookups, and the on/off output is derived from on-chip logic that lets you implement bang-bang controller applications with few external compo-

Other comparator types fit a variety of niche applications and offer a range of electrical performance—in part because many devices are simply old and represent a bygone state of the art. In addition to a selection of parameter values, these types offer low power consumption for remote and battery-powered systems, low-voltage (1V) supply operation, FET inputs to provide low bias currents, and output stages that simplify the interface to different logic families. Some types come in dual and quad versions to reduce the package count in a system.

CMOS technology offers the obvious way to achieve low power consumption. Texas Instruments' dual TLC372 and quad TLC374 comparators, based on the company's linear-CMOS process, draw only 0.1 mA per comparator from a 5V supply. However, Linear Technology's LT1017 is a bipolar dual-comparator IC that draws even less supply current-0.15 mA total from a 5V supply. Other low-power bipolar devices include the familiar LM393 dual comparator (0.4 mA) and the LM394 quad device (0.8 mA). Siliconix's L161 quad comparator, the TI TL331, and the Intersil ICL8001 also feature low current draw. (All these supply currents are measured under static conditions and with no output load.)

In addition, you can find comparators that operate with supply voltages as low as 1.15V or ±2V. The demand for these low-voltage comparators should escalate, along with the trend toward finer-geometry ICs that require low supply voltages

#### For more information . . .

For more information on the voltage comparators mentioned in this article, contact the following manufacturers directly or circle the appropriate numbers on the Information Retrieval Service card.

**Advanced Micro Devices Inc** Box 3453

Sunnyvale, CA 94088 (408) 732-2400 Circle No 710

Analog Devices Inc Two Technology Way Norwood, MA 02062 (617) 329-4700 Circle No 711

Fairchild Camera and Instrument Co 3333 Bowers Ave Santa Clara, CA 95051

(408) 987-9530 Circle No 712

Harris Semiconductor Corp Analog Div Box 883 Melbourne, FL 32901

(305) 724-7000 Circle No 713 Honeywell Inc

Signal Processing Technologies 1150 E Cheyenne Mountain Blvd Colorado Springs, CO 80906 (303) 576-3300 Circle No 714

Intersil Inc 10710 N Tantau Ave Cupertino, CA 95014 (408) 996-5000 Circle No 715

LeCroy Research Systems Corp 700 S Main St Spring Valley, NY 10977 (914) 425-2000 Circle No 716

Linear Technology Corp 1630 McCarthy Blvd Milpitas, CA 95035 (408) 942-0810 Circle No 717

Motorola Semiconductor Products Inc

Box 20912 Phoenix, AZ 85036 (602) 244-6900 Circle No 718

National Semiconductor Corp 2900 Semiconductor Dr Santa Clara, CA 05051 (408) 737-5000 Circle No 719

Plessey Semiconductors Inc 3 Whatney Irvine, CA 92718 (714) 951-5212 Circle No 720


Precision Monolithics Inc. 1500 Space Park Dr Santa Clara, CA 95050 (408) 727-9222 Circle No 721

Raytheon Co. Semiconductor Div 350 Ellis St Mountain View, CA 94043 (415) 968-9211 Circle No 722

**Signetics Corp** Box 3409 Sunnyvale, CA 94088 (408) 739-7700 Circle No 723

Siliconix Inc 2201 Laurelwood Rd Santa Clara, CA 95054 (408) 988-8000 Circle No 724

**Texas Instruments** Semiconductor Group Box 225012 Dallas, TX 75265 (214) 995-2011 Circle No 725



## In VMEbus, you can play games or you can get serious.

We're Bicc-Vero. We supply it all. We're serious. Play to win. Call us once.

Wide Selection of boards including...

- CPU's fixed or floating point, single board computers, DRAM, static RAM, disk controllers, SCSI, A/D and D/A, serial and parallel communications, GPIB in both single and double high.
- One of the widest ranges of support products covering backplanes

in many slot sizes, card cages and accessories, power supplies, connectors and enclosures.

- Single and double high systems and software support from operating systems to board drivers.
- Prototyping boards in wirewrap and speedwire. Multilayer extender boards.

Please ask us for a copy of the most comprehensive VMEbus system catalog available today.






#### BICC-VERO ELECTRONICS INC.

40 Lindeman Drive, Trumbull, CT 06611 (203) 372-0038 FAX: (203) 372-6224 / TWX: 510-227-8890

CIRCLE NO 56



The HCMP96850 high-speed comparator from Honeywell is suitable for use in automatic test equipment and high-speed instrumentation. Propagation delay is less than 3 nsec.

(**Ref 2**). Currently available low-voltage comparators include Linear Technology's LT1017 and LT1040C, Siliconix's L161, and the generic LM339 and LM393.

National Semiconductor's LF311 FET-input comparator provides subnanoampere input bias currents that almost eliminate bias-current errors. The device can operate from a single 5V supply or from  $\pm 15$ V supplies. Its  $\pm 10$ -mV max input offset voltage rules out some applications, however.

Commodity-comparator products like the quad LM339 are popular, principally because of their price: You can buy the LM339 for about \$0.35. "At that price they are virtually free," says Phil Perkins, chief engineer, advanced development for LTX Corp. It's also easy to design parts like the LM339 into the applications for which they're best suited.

Still, Perkins would be willing to pay considerably more for an enhanced LM339. The part's output swings to the negative power-supply rail, for example, so with bipolar supplies you often must add a level translator to make the output compatible with the load circuit's logic requirements. A 16-pin package and a logic-level select pin controlling all four of the comparator outputs would address this problem. Also, Perkins suggests, it would be nice to

have a middle-performance comparator that specs a 100-nsec response time and a decent common-mode range but is easy to apply like the LM339. Lower input bias current would be welcome, so the device might profit from FET inputs.

Improvements in voltage comparators need not depend entirely on improved technology. A better dialogue between the makers and users could lead to models with a more useful combination of the features that are already available. One technology development seems certain, however: the use of gallium arsenide to speed the performance of linear ICs. Within the year you may see GaAs voltage comparators that feature 0.5- to 1.0-nsec propagation delays, gains of 200, and input bias currents below 20 nA.

EDN


#### References

Williams, Jim, "Use comparator ICs in new and useful ways," EDN, January 6, 1983, pg 115.
 Mosley, J D, "JEDEC standards

2. Mosley, J D, "JEDEC standards for sub-5V chips to guide future sub-micron VLSI designs," *EDN*, April 18, 1985, pg 71.

Article Interest Quotient (Circle One) High 500 Medium 501 Low 502 SPOTUGHT#19

NOW AVAILABLE-THE ONE-CHIP BELL 212A 1200 BPS MODEM



#### FEATURES:

- One-chip Bell 103/212A compatible modem IC
- Call progress detection and DTMF tone generator on-chip
- Easy to use 8-bit parallel bus (28 Pin DIP, QUAD) or optional serial bus for modem control (22 Pin DIP)
- Interfaces directly with 8051 or 8048 family of microprocessors
- Integrated analog and digital design provides exceptional performance
- Low power CMOS uses a single +10V supply

The SSI K212 is a complete Bell 212A modem on a single chip, and it incorporates all the primary functions needed for a typical intelligent modem. Included on a single chip are full Bell 103 and 212A operating modes, a call progress monitor, and a DTMF dialer. The device also has an 8-bit parallel bus for control of modem functions and will directly interface with the 8048/8051 family of low-cost micro controllers. A complete modem requires only the addition of the phone line interface and a control microprocessor.

The one-chip K212 provides functions on a single chip which were previously only possible using many separate components. The new one-chip modem (C simplifies the design problem for users who are building modems for personal computer applications, and it is ideal for use in any self contained or integral modem system. The K212 provides exceptional performance under poor line conditions, and allows all Bell 212A operating modes.

For more information, contact: Silicon Systems, 14351 Myford Road, Tustin, CA 92680, (714) 731-7110, Ext. 595



**CIRCLE NO 17** 

#### SILICON SYSTEMS OFFERS THE ONE-CHIP MODEM THAT'S READY FOR DELIVERY NOW!



#### More Functions Integrated on a Single Chip

The race to deliver a true single chip
212A modem was won in November, 1985
when Silicon Systems released samples of
its K212. The new SSI K212 is a full-featured,
1200 BPS modem in a single 28-pin DIP.
It incorporates all the primary functions
needed to construct a modem which
exceeds Bell 212A performance
requirements.

Included on the single chip are complete Bell 103 and 212A operating modes, a call progress monitor, and a DTMF dialer. The device also has an 8-bit parallel bus for the control of modem functions and will directly interface with the 8048/8051 family of lowcost micro-controllers. Its high functionality, low-power CMOS operation, and efficient packaging facilitate design usage and increase system reliability.

#### Simplifies Modem Design and Manufacturing

The one-chip K212 represents a new level of integration for modem IC's. It provides functions on a single chip which were previously only possible using many separate components. This new single-chip modem simplifies designs for users who are building intelligent modems, or who wish to incorporate datacommunications capability

into specialized systems. A complete modem requires only the addition of the phone line interface and a control microprocessor. The K212 is ideal for use with any selfcontained or integral modem system that incorporates a dedicated microprocessor for control and command interpretation.

#### **Pricing and Availability**

The Silicon System K212 one-chip modem is available from stock now. For prices or more product information, contact us today.

Silicon Systems, Telecom Products Division, 14351 Myford Road, Tustin, CA 92680 (714) 731-7110, Ext. 595.



# Introducing the 22V10

E for Erasable. 25ns for performance. CMOS for cool, cool, low, low power. A great new high speed PAL® device standard. Our free comparison demo will show you.

### FREE

Cypress Semiconductor CMOS 22V10 Erasable PI Comparison Sample



### FPLD.

#### How to get your FREE comparison part:

22V10 users: We'll duplicate your 22V10 on our new part, for free. You'll have your part and our part with the same logic.
Compare for yourself. Then erase and reprogram our part to your heart's content.

A simple, one-minute toll-free phone call gets you, by instant return mail, your 22V10 COMPARISON OFFER CERTIFICATE with full details of the comparison offer. It's easy.

#### 1-800-952-6300.

In California call, 1-800-423-4440. In Europe call, (32) 2-672-2220. In Canada call, (416) 475-3922. Ask for Dept. C41. Offer expires April 30, 1986. The standard 22V10, we must admit, is a superb part.

High speed, for high performance systems. Macrocell I/O so one part can be programmed to replace up to 10 different PAL devices, plus many additional logic configurations. Inverted or non-inverted, registered or combinatorial operating modes. As many registers as you want—1 to 10. Synchronous Preset and Asynchronous Reset feature. Super flexibility.

#### Now, consider the PAL C 22V10 with Cypress Semiconductor 1.2 micron CMOS technology:

FIRST, THE WINDOW: Reusable parts lower your cost of prototyping, and lower your cost of inventory. You stock fewer parts through Macrocell versatility and erasability. Inventory is flexible should your specs—or demand—change.

SPEED: 35ns parts go as fast as bipolar. Our new 25ns parts will go even faster.

LOW POWER: Cool, cool CMOS draws only 80mA, half the operating power of bipolar, and runs happily in inexpensive plastic packaging.

QUALITY: Greater than 2000V ESD tolerance on every pin; easily tolerates ± 10% power supply fluctuations.

100% CHECKED: Windowed or nonwindowed 22V10 devices are factory tested—every memory cell on every device for AC functionality and programmability. You get *minimum* rejects.

COMPATIBILITY: Fits your existing 22V10 sockets, at very competitive prices. Use the industry standard languages you like, such as CUPL® or ABEL™, and the programmer you probably already use.

and 20G10, the 55mA generic PAL 24 device. Both have parts available at 25ns. Both with optional windowed parts. Both 100% tested. Offering up to 75% power savings over bipolar parts.

We want your programmable logic business, and we've got the devices to earn it!

Now a few words on the rest of our MIPS CHIPS family.

#### **CMOS High Speed Static RAM Family**

Including the *fastest* (15ns) static RAM you can buy. 25ns, 35ns, 45ns parts, too. Nibble-wide, bit-wide, byte-wide, ranging from 64-bit through 16K-bit. Low active power. Low standby power—many parts include auto-power-down when deselected. A superset of separate I/O functions provides a design edge for improving overall system performance.

#### **CMOS High Speed PROM Family**

Surpassing bipolar with the fastest registered PROM at ½ bipolar power, or less. Parts feature speeds to 30ns access, 15ns clock-to-output; all with low CMOS power. Byte-wide family available in 4K, 8K, 16K densities. All available with registered outputs. EPROM memory technology permits 100% testing before packaging, to provide 100% programming yields.

#### **CMOS High Speed Logic Family**

World's fastest 4-bit-slice microprocessor (25% faster using only ¼ power of 2901 bipolar). Plus sequencers, controllers, DSP circuits, more.

Also the world's fastest, cascadeable 4-bit and 5-bit FIFOs (25 MHz performance, 1/3 bipolar power.)

Need PAL 20 or PAL 24 devices?

Our CMOS PAL product line also includes a 45mA PAL 20 family;

CMOS Data Book

This data
book, packed
with high-speed,
low-power parts, is
yours for a phone call.

DATA BOOK HOTLINE: 1-800-952-6300. 1-800-423-4440 (In CA). (32) 2-672-2220 (In Europe). (416) 475-3922 (In Canada).

Ask for Dept. C41.

CYPRESS SEMICONDUCTOR

Cypress Semiconductor, 3901 North First Street, San Jose, CA 95134, Phone: (408) 943-2666, Telex: 821032 CYPRESS, TWX: 910-99740765 @1985 Cypress Semiconductor, PAL is a registered trademark of Monolithic Memories, Inc. CUPL is a registered trademark of Assisted Technology/P-CAD Systems. ABEL is a trademark of Data Space I/O Corporation.

#### Get a calculator that has no equal.

Get an HP-41.

So advanced, it doesn't need an "equals" key. So extremely simple to use, you'll be quickly solving the most difficult electronic design and analysis problems.

The HP-41 has over 2,500 software programs to choose from. More than any other calculator. Also available are plug-in application pacs. They allow you to easily handle things like complex number operations, network analysis and fourier series. And four ports give you the ability to add a variety of enhancements

and peripherals like additional memory, printers and mass storage devices.

The HP-41's quality also has no equal. That's something you can see. Even feel. Right down to the touch of the keys. They're designed to prevent double entry. So you won't enter more than one number at a time.

And there are two HP-41s to choose from The HP-41CV or the extended capabilities of the HP-41CX.

So call (800) FOR-HPPC toll-free. Ask for Dept. 215C. We'll instantly give you the name of a calculator dealer who has no equal.

ON	USER		PRGM	ALPHA	
Σ-	y×	x<	10×	ex	
Σ+	1/x	1x	LOG	LN	
				E	
CLE	%	SIN-1	cos-1	TAN-1	
xxy	R₩	SIN	cos	TAN	
				de	
	ASN	LBL	GTO	BST	
	XEQ	STO	RCL	SST	
I and the second					
	ALOG	CHS		CLX/A	
	ENTER +		EEX	+	
x=y?					
	SF 7		OF O	FS?	
Q	B	8		9	
x ≤ y ?	BEEP			R+P	
+	4	P → R 5		6	
U	V	W		×	
x>y?	FIX	SCI		ENG	
×	1	2		3	
		=		7	
x=0?		LASTX		VIEW	
÷	0			R/S	
	SPACE			11/3	



### Logic analyzers evolve in response to high-level languages

Charles H Small, Associate Editor

In parallel with the design engineer's journey from pencil-and-paper designs and discrete parts to high-level languages and programmable ICs, logic analyzers—in their latest incarnation as software analyzers-have also evolved by becoming high-level-language instruments. Although the software analyzer is a logical and necessary extension of the concept of logic analysis into the realm of high-level software, the instruments are so new that not even their makers, let alone software engineers, fully appreciate all the changes that the instruments will wreak on software-engineering methods.

From their introduction, logic analyzers gave engineers a new way of looking at phenomena—seeing events in parallel instead of serially. Software analyzers, similarly, provide new ways of analyzing software and viewing the phenomena associated with the software under development (see box, "From logic to software analyzers"). In addition, hardware-based software-performance analyzers prove useful earlier in the software-design cycle (Fig 1) than do software-based analyzers (program profilers).

Typically, hardware-based software analyzers make five classes of measurements on program statements and data constructs:

- Intermodule linkage
- Program activity
- Memory activity
- Module duration
- Module usage.

That is, the analyzers can record extended sequences of subroutine or procedure calls, the frequency of




Fig 1—You can use hardware-based software-performance analyzers early in the software-design cycle. Unlike software-based analysis tools, which typically wait until the verification stage, hardware-based tools prove useful as soon as you need to debug multiple modules.

### IS THE NUMBER 2> ONE CHOICE TO READ 13 1



#### You said so yourse

Ask which electronic engineering publication is most useful on the job and your answer is EDN.

Again and again.

In fact, EDN has won 87 out of 125 (or 70%) of the independent readership/reader preference studies conducted since 1978. That includes capturing the 1984 Westcom Study, the most comprehensive readership study ever conducted in the industry. Which tells us EDN captures more attention than any other electronic engineering publication.

Thanks. We couldn't ask for better results.



First in Readership among Design Engineers and Engineering Managers in Electronics

Cahners Publishing Company 

Publishers of 33 specialized business magazines in Building & Construction 

Electronics & Computers ☐ Foodservice ☐ Manufacturing ☐ Medical/Health Care Cahners Building, 275 Washington Street, Newton, MA 02158-1630 617/964-3030

1

X

X

X

X

X

N

X3

\$

N

\*

X

X

X

\*

X

\*

 $\Sigma$ 

X

\*

1

\$

#### From logic to software analyzers

Early logic analyzers served low-level-logic designers by capturing multiple channels of timing data and displaying them in fundamental terms—timing diagrams. Although logic analyzers never lost the capability to display timing waveforms, the instruments gradually acquired additional abilities in response to design engineers' changing needs. Logic analyzers could soon capture, format, and display data in forms increasingly abstracted from the electrical activity in the circuits under test. The first step along the road to handling high-level languages was the state analyzer. State analyzers compress captured data into lists of numbers or characters—usually binary, octal, hexadecimal, or ASCII.

#### Analyzers become abstract

Next, state analyzers became µP analyzers when they acquired µP-specific interfaces and the ability to disassemble captured data into the assemblylanguage mnemonics of the targeted µP. Inferring the assembly-language program from captured data is a relatively simple process because of the one-for-one correspondence between an assemblylanguage instruction and the corresponding µP state that the analyzer sees at the µP's pins. Further, µP analyzers that are integrated into a hardware/software development system can easily consult the assembler's original symbol tables and plug labels back into a disassembled listing in place of raw hexadecimal numbers where appropriate. Thus, although the term "software analyzer" refers to high-level-language instruments and doesn't refer to  $\mu P$  analyzers, the  $\mu P$  analyzers are really a rudimentary kind of software analyzer.

High-level software analyzers are just now be-

ginning to appear. These instruments attempt a much more difficult task than  $\mu P$  analyzers; a software analyzer's job is to trace high-level-language execution and data constructs based on observations of a  $\mu P$ 's address, data, and status lines. Decompiling machine-level activity into high-level code is much more difficult than disassembling because no one-for-one correspondence exists between a high-level-language construct and the code it becomes through compilation—particularly if you invoke the compiler's optimizing option. The degree of abstraction of high-level languages from the  $\mu P$ 's activity is high, and no clear-cut path exists between the two domains.

In fact, software analyzers don't really decompile captured data. Instead, they rely on myriad clues to associate certain kinds of  $\mu P$  activity in specified memory areas with a corresponding section of a high-level program. Therefore, software analyzers cannot function without extensive cross-reference information from the compiler that generated the object code that the instrument is analyzing. The software analyzer must know, for example, not only the absolute locations of all variables and other data constructs of interest, but also the mechanisms the compiler uses to pass variables between modules or subroutines and the locations of all specified program modules' entry and exit points.

Armed with this cross-reference information and understanding the compiler's mechanisms, the software analyzer can correlate your high-level debugging commands with the low-level activity it sees at the  $\mu P$ 's pins. Moreover, after capturing data, the analyzers can condense and display them in ways that help you pinpoint program bugs.

program flow to selected parts of the code, the program's destination in memory, length of run time for selected modules, and frequency of calls for selected modules. You specify all of these program and memory areas using the same terms used in your original source code. The analyzer then correlates those commands with the correponding object-code and memory areas and configures itself to trigger on lowlevel events.

Somewhat confusingly, three types of software analyzers currently exist. Real-time software analyz-

ers (also called software-performance analyzers) have specialized, fast hardware that allows them to obtain one-shot timing data. Nonreal-time analyzers, on the other hand, must occasionally interrupt the software under test to record the state of program constructs or the µP because they lack fast hardware. Finally, some socalled software analyzers mimic conventional software-based program profilers. Like the software tools they mimic, these analyzers measure repeated runs of the same program to gather and reduce statistical data. Consequently, they prove useful only during the final-verification stages of software development.

The key difference between the hardware- and software-based methods of software analysis is that in using the latter method, you must instrument your program; with the former method, you instrument the hardware (see box, "Software- vs hardware-based tools"). Thus, users of software-based software analyzers must edit and recompile their programs each time they change their measurement setups. Hard-

#### Software- vs hardware-based tools

Because the advocates of software-based software analyzers have experience only with program profilers, they consider only module duration and module usage to be software-performance analysis. To them, software analysis is a tool to be applied only during the last phases of a software project for what they loosely term "optimization" ("fine tuning" is in fact a more apt term). By optimization, they mean that after measuring the time consumed by various program modules, they rewrite the slowest and most frequently called ones so that those modules execute faster, thereby speeding the overall program's execution. (They can also, at this juncture, eliminate the phantom modules that are never called. Such phantoms seem to lurk, needlessly occuping memory, in every large program.)

#### Application area expands

But this myopic view of software analysis overlooks the utility of the new hardware-based software analyzers early in a software-design project. Conventional software-based software-analysis tools are too cumbersome to be applied economically anywhere other than during the final phases of a project. In contrast, hardware-based software analyzers are much faster to set up and run. Therefore you can use hardware-based software analyzers to trace module-to-module jumps and to trace variables passed between modules early in the software-design cycle-in fact, as soon as you have just two modules to check. In other words, software analyzers' area of application isn't limited to just conventional software analysis; it also overlaps what conventional wisdom considers debugging.

#### A typical debug session

The software analyzers' abilities begin to make sense when you consider how you might perform a typical high-level-language debugging session with the aid of a hardware-based software analyzer. Recall that the conventional software-based debugging tools generally allow only single-stepping through modules line by line, module by module; you then manually examine the program's state. This debugging scheme is laborious and far from optimal because it begins with the particular instead of the general.

A hardware-based software analyzer, on the other hand, allows you to start at the highest, most abstract level of your program's algorithm: how the program's modules interact. You can use the software analyzers' module-linkage tracing facility to see if the sequence of modules is according to your plan.

#### From general to particular

If the sequence of modules proves correct, you could next trace common (global) or shared data constructs (data passed between modules) in an effort to find data being corrupted. Once you've homed in on the offending module, you could then dip into that module's execution to trace its local variables. When you find a local variable with wrong data, then (and only then) you can revert to conventional software-debugging practice and trace your program line by line.

Proponents of software-based software analyzers might argue that they could duplicate this sequence of descending from module linkages to statements by peppering their programs with Print statements at appropriate locations. They could determine module entry and exit points by inserting commands to print such announcements as "entering module A" and "exiting module A" at the beginning and end of module A's statements. Similarly, they could print the contents of various data constructs at key points in the program.


Although the software-based analyzer proponents *could* thus duplicate some of a hardware-based software analyzer's abilities, experience shows that the software method is too time consuming and its output too difficult to interpret; in addition to making real-time measurements that software methods can't hope to duplicate, the hardware-based software analyzer is easier to use, and its output is easier to interpret.

ware-based software-analyzer users, on the other hand, can run the same program over and over without time-consuming recompilation because they don't depend on in-line code. Each user will have to decide whether his or her time is valuable enough to warrant the \$3000 to \$11,000 (depending on

model) for a hardware-based soft-ware analyzer.

#### Paying the price

Not all hardware-based tools are that easy to use, however, and not all have wide application areas. Of the major logic-analyzer makers, all offer some form of software-performance analysis in their state analyzers. And all complain that users neither appreciate nor understand the feature. However, a software analyzer that has a limited range and that must be programmed manually (each time you change just one routine and recompile and relink, all the absolute addresses change and



# ULA\*. Gives you the edge for custom LSI.

Thinking custom LSI? You should be, to gain the edge over your competition.

To get the full benefits of custom LSI you must include not just the system

logic but also the I/O and analogue functions.

The ULA is designed to do precisely this by combining the logic implementation, an I/O capability for all commonly used technologies and a facility for integrating functions such as Schmitt trigger inputs, precision oscillators, analogue switches, op amps, voltage references, comparators, high current drive transistors and so on.

The ULA provides the economic and performance benefits of full custom

design but with the short time scales of gate arrays.

There are over 50 different ULA's supported by the Ferranti Silicon Design System, the CAD facility covering the complete design cycle from system concept to silicon hardware.

In more ways than one, the ULA gives you the edge.


For further information, contact

IC Marketing, Ferranti Electronics Limited, Fields New Road, Chadderton, Oldham, OL9 8NP, England. Telephone: 061 624 0515 Telex: 668038.

ULA is a registered trademark of Ferranti plc for semiconductor devices.




#### FERRANTI Semiconductors



□ Ferranti GmbH, West Germany, Munich, Tel: 089-2368 040 □ Ferranti Electronics Benelux, Antwerp, Tel: (0) 3/542.62.73

☐ Ferranti Electronics Sweden, Stockholm, Tel: 08-52 07 20 ☐ Ferranti Computer Systems (Australia) Pty Limited, Alexandria, Tel: (02) 698 5544

□ Ferranti Wheelock Microelectronics, Aberdeen, Hong Kong, Tel: 5-538298-9 □ Ferranti Interdesign Inc. USA, California, Tel: 408-438-2900.



Specialized for gathering software data, Northwest Instrument Systems' Softanalyst times program execution, locates possible bottlenecks, and notes which routines are called frequently.

therefore must be updated) is likely to be used only when absolutely necessary. By excluding such limited devices, you're left with software analyzers that can both access a compiler's symbol tables and automatically access program hooks.

#### Real-time analyzer

The Hewlett-Packard HP 64340A software analyzer, for example, solves otherwise intractable problems of tracing the real-time execution of high-level programs. The \$11,000 analyzer is a 3-board set for the company's HP 64000  $\mu$ P development system (processor-specific analysis software costs \$1000). In addition to the 64340A, a reasonably configured 64000 system will cost \$20,000 or more.

Unlike the 64340A, other analyzers are befuddled by certain aspects of such high-level languages as Pascal and C because programs generated by these languages' compilers define certain variables and other data constructs as the programs run. Instead of preallocating to each

data construct its own private memory area at compile time, the programs typically use and reuse a common area of memory—called a stack or heap—for data constructs. Therefore, you don't know where a given data construct will reside. Worse, a given memory location could successively contain several variables during different phases of a program's execution.

Because you must explicitly arm the event recognizers (address, data, and qualifier comparators) of other instruments before a program's test run, those instruments cannot handle dynamically declared data constructs in real time. Instead, they must inject pauses into the program's flow while the instrument takes a snapshot of the target system before resuming execution (that is, it moves a copy of the state of the data construct and the processor into data-capture memory).

The HP 64340A, however, can follow the execution of a program by using a combination of cross-reference data from the manufacturer's

Pascal and C compilers, special hardware, and post-capture data reduction. The company is trying to convince other compiler suppliers to provide the necessary hooks with their compilers so that the HP 64340A will be able to work with compilers other than those supplied by Hewlett-Packard.


#### Family resemblance

Fig 2 shows the 64340A's architecture. The instrument's front end resembles that of a logic analyzer. The analyzer's inputs are in parallel with the inputs of the 64000's incircuit emulator-that is, the analyzer sees the target µP's address, data, and status lines. The analyzer has an onboard 68000 µP and a 4k×96-bit data-acquisition memory. An acquisition-memory location stores not only the state of the µPaddress, data, and status lines-but also a time tag, a computed program-counter value, and flags from the analyzer's state machines. The analyzer needs all this information for post processing.

Information that the analyzer gleans from the compiler allows the analyzer to set up its static and dynamic event recognizers. During a program's test run, the recognizers strobe data into the acquisition memory. After the test run, the 64000 system uses the information stored in the analyzer's acquisition memory to reconstruct the program's activity.

#### Tracing local variables

For example, suppose you want to trace one procedure's reads and writes to a dynamically defined variable that is local to that procedure. From the compiler's cross-reference tables, the analyzer knows the location of the beginning and end of the procedure's instructions and also knows how the compiler handles the procedure-entry overhead of setting up the local variables on the stack (the reserved area on the stack is called a frame). Further, the cross-reference data also gives the



#### Philips' PM 3551 A and PM 3632 Logic Analyzers

Choose the PM3551A, the world's fastest transitional timing analyzer. With simultaneous state and timing analysis. Plus powerful performance analysis with unique features. Measure recursive routines, and obtain undistorted data even if subroutines are interrupted. Up to 16 on-screen timing channels. Unmatched trigger facilities. Pure power!

Pure power, too, with the PM 3632 Personal Logic Analyzer. And at a price that lets you put one on every bench. Handles 32 channels at speeds up to 100 MHz. Adapts to any popular  $\mu$ P. Optional ROM emulator and plug-in Set-up and non-volatile Data Memory.

Both feature a simple, powerful menu system with soft-key entry that puts you in charge from the first day. The choice is yours! Get the details on the PM 3551 A logic timing, state and performance analyzer and the PM 3632 Personal Logic Analyzer. In the final analysis you'll choose Philips. Contact your local Philips Sales organisation or:

Philips I&E, T&M Department, TQ III-4-62 5600 MD EINDHOVEN, The Netherlands. Germany (0561) 5015 18 Great Britain 0223-35 88 66 France 01-830 11 11 Netherlands 040-78 32 38 Italy 039/3635.240 (or 248) Sweden 08-782 18 10.

PM 3632 not available in Australia, Canada, Hong Kong, Japan, Singapore and Taiwan.



Test & Measurement **PHILIPS** 

64340A the position of a given variable—or offset—within the frame.

The analyzer arms its low-level recognizers with the procedure's entry and stack-setup instruction addresses. When it senses that the program has jumped to the procedure of interest and has set up its local variables, the analyzer calculates the absolute address on the stack of the variable by using both the current stack pointer (SP) and the known offset of the variable within the frame. The analyzer also sets up its Boolean-function generator. When the Boolean-function generator recognizes an access to the dynamically defined variable of interest, the analyzer records the

96-bit-wide state of the system under test. When the program's flow exits from the procedure, the analyzer dismantles the dynamic word recognizers' and Boolean-function generator's setup.

Because the analyzer's event recognizers can work in pairs, the analyzer can record activity over a range of addresses as well as at one address. The 64340A has enough event recognizers to monitor four ranges simultaneously. In this way, it can capture as many as 256 copies of a complete stack frame or other data construct as the program executes. You can also set up the pairs of event recognizers to trace your program's flow by procedure or by

groups of procedures if the pairs of recognizers span entire procedures or groups of procedures. (You can trace groups of procedures only if the compiler has loaded the groups contiguously.)

The HP 64340A also traces statements and data constructs in non-real time, as other analyzers do, by cross-triggering the development system's in-circuit emulator and by breaking execution when it sees hardware breakpoints. (A hardware breakpoint comes from an event recognizer; a software breakpoint comes from extra debugging instructions inserted at key points in the program.) The analyzer has nine hardware breakpoints that operate in parallel.

Further, the analyzer's remaining functional blocks allow it to count the number of occurrences of 255 different events. This real-time, nonintrusive ability proves useful—as does the analyzer's ability to measure the time the program spends in various procedures (timestamp data)—in identifying procedures that run often or consume excessive amounts of computer time.

#### Nonreal-time analyzer

If you can forgo real-time measurements, the \$3000 HP 64330 provides a suite of measurements similar to that of the 64340. The low-cost instrument, however, cannot dynamically re-arm its event recognizers. Instead, it interrupts the emulator's processor when it needs to determine what the processor is doing. So although it can handle dynamically defined (as well as statically defined) program constructs, it cannot run in real time.

Hewlett-Packard also has a pair of software-performance analyzers—the \$3440 HP 64310A and the \$4350 to \$9610 (depending on number of channels) HP 64620S—that provide only global measurements of module-execution times. These instruments fulfill classical software-performance roles and are un-




Fig 2—By using details gleaned from a high-level language's cross-reference tables, the \$11,000 HP 64340A real-time software-performance analyzer can trace program activity in real time without injecting wait states into the target system's execution of the program under test.


### Microsoft FORTRAN. The overwhelming favorite.

How did Microsoft FORTRAN get so popular? It could be the mainframe compatibility. Our compiler makes porting applications a cinch with overlays and the ANSI features you need.

It could be our support for arrays and COMMON blocks larger than 64K. So you can

tackle mainframe-size problems.

It might be the shelves and shelves of third party support libraries. No other FORTRAN comes close.



Cut your development time dramatically. The Symbolic Debug utility, part of the Microsoft Macro Assembler, lets you debug your FORTRAN programs using your original source code or the resulting disassembly. For example, you can set breakpoints on line numbers, observe the contents of variables and expressions, and examine the contents of the stack

It could be the extensive math support. Our collection of math libraries is simply the largest available. Tackle real problems with direct 8087 support or emulation. Use IEEE floating point or—for extra speed—the altmath package.

It could be the comprehensive set of utilities. A powerful linker and library manager combination. Plus tools like EXEMOD and

EXEPACK. Standard.

It could be the XENIX® and MS-DOS® source-level compatibility. Or the direct interlanguage calling to Microsoft C, Pascal and Assembler. Or the ability to work with our Macro Assembler's symbolic debugger.

It could be the value. Nobody offers a FORTRAN package this complete at this low

a price.

Why is Microsoft FORTRAN the most popular FORTRAN? All the above.

#### Microsoft FORTRAN Compiler Version 3.3 for MS-DOS and XENIX 286

Microsoft FORTRAN Compiler

- Implements most ANSI 77 standard features, plus
- Easily port mainframe/minicomputer programs with little or no modification.
- Overlay support in the compiler and linker.

Common blocks and arrays greater than 64K.

- Supported by the largest number of third party libraries.
- Includes a full set of math libraries to select from:

\*8087/80287 emulation.

- •8087/80287 coprocessor support.
- Floating Point without 8087/80287.

BCD Floating Point.

- Conditional compilation.
- Link your FORTRAN routines with Microsoft C Compiler (version 3.0 or higher), Microsoft Pascal (version 3.3 or higher), and Microsoft Macro Assembler.
- •MS-DOS 3.1 network support and IBM® local area network
- \*Source code compatible between MS-DOS and XENIX 286.
- \*Do source level debugging with the Symbolic Debug Utility, available separately with Microsoft Macro Assembler.

Object Code Overlay

- Simple overlay linker combines relocatable object modules created using Microsoft languages into a single program.
- Link very large programs (over 1 megabyte) using overlays. Library Manager

 Create, organize and maintain your object module libraries created with Microsoft languages.

Microsoft EXE File Compression Utility (MS-DOS only)

• A utility to pack EXE files for smaller size on disk and faster loading at execution time.

Microsoft EXE File Header Utility (MS-DOS only)

• A utility that allows you to display and modify the fields in EXE file headers.

For the name of your nearest Microsoft dealer call (800) 426-9400. In Washington State and Alaska, (206) 828-8088. In Canada, call (800) 387-6616.

Microsoft, XENIX and MS-DOS are registered trademarks and The High Performance Software is a trademark of Microsoft Corporation. IBM is a registered trademark of International Business Machines Corporation

suitable for the early phases of software development.

In contrast to the HP 64340, the front end of Northwest Instrument Systems' Softanalyst (Fig 3) looks nothing like that of a logic-state analyzer. Logic-state analyzers typically have no more than four highspeed comparators (or word recognizers). These comparators look for a match between your preprogrammed trigger event and the state of the system; they can't wait for more than four events at one time. However, you'd need far more than four word recognizers to cover all the branches, accesses, and events you'd be concerned with when analyzing a large structured program.

Softanalyst employs a 256-event-deep RAM array as an event recognizer. You can program the instrument to look for either 250 single events (such as the access of a variable) or 125 pairs of events (such as the entry to and exit from a software module or subroutine), or you can program it to monitor 83 address ranges (to investigate, for instance, access to an array or other data structure). When the instrument sees a trigger event, it records not only the event, but also a time tag for that event.

#### Real-time data reduction

Fig 3 also shows a key feature of the Softanalyst's architecture: the event recognizer's output goes into a FIFO buffer; the output of the FIFO buffer goes to a TMS32010 μP. Unlike analyzers that capture data until their capture memory is full and then reduce the data, the Softanalyst's TMS32010 continually reduces and compresses incoming data. This continual reduction means that (as long as the FIFO buffer doesn't overflow) the Softanalyst can capture data over longer periods than its 1k-event capture memory might at first suggest.

Unlike HP's software analyzers, the Softanalyst isn't integrated with the manufacturer's compilers.





Fig 3—A TMS32010 digital signal-processing  $\mu P$  reduces and compresses data, thereby allowing the Northwest Instrument Systems' Softanalyst to monitor long program runs without overrunning its captured-data buffer.

At present, Northwest Instrument's software analyzer accepts compilers' symbol tables in Intel object-module format (OMF) and in Unix-defined common object-file format (COFF). Once you've downloaded a symbol-table file to the software analyzer, you use a built-in windowing editor to select trigger events corresponding to lines of code, procedure entry and exit points, and data structures. Unfor-

tunately, you'll have to repeat this downloading step each time you modify and recompile your program.

Besides simply recording the execution history of a module, the software analyzer can correlate the module's execution to the state of a system variable or the value of passed parameters at the time the module executes. In addition to collecting data on program activity,

# OP-07 HAS MET



#### OP-77 obsoletes OP-07.

mW Max

120

60

 $P_{D}$ 

Who but PMI, the inventor of the industrystandard precision op amp, could deliver the next generation — with significantly improved gain linearity.

The OP-77 is a direct replacement for OP-07. Competitively priced, the OP-77 sets new industry standards.

For information on the OP-77, gain linearity, and PMI's free 1986 data book, circle the inquiry number below.

Precision Monolithics Inc. A Bourns Company 1500 Space Park Drive Santa Clara, CA 95054-3499 (408) 727-9222


1-800-843-1515 or, in California 1-800-826-9664

FRANCE: 01-42 03 96 33, GERMANY: 0711-22 93 0, NETHERLANDS: 070 87 54 04, SWITZERLAND: 042-33 33 33, UNITED KINGDOM: 01-572 65 31, HONG KONG: 5-702171, JAPAN: (03) 234-1411, AUSTRALIA: (02) 570-8122, AUSTRIA: 0222-43 26 39, DENMARK: 02-98 63 33, FINLAND: 90-75 06 00, GREECE: 01-821 58 25, ISRAEL: 03-49 44 50, ITALY: 02-569 57 46, NORWAY: 02-83 02 20, PORTUGAL: 19-68 60 72, SOUTH AFRICA: 52 86 61 OR 011-839 18 24, SPAIN: 01-405 42 13, SWEDEN: 08-768 05 60, TURKEY: 041-30 15 10, YUGOSLAVIA: 041-42 37 46, EASTERN EUROPE: 0222-24 71 37.



The precision solution.

#### Your CUSTOM HYBRID Source



- We produce custom, design-disclosed high density active hybrid circuits—chip-and-wire or surface mount technology
- Over 17 years of hybrid circuit manufacturing experience
- All manufacturing processes automated from printing through final test
- Manufacturing statistical process control
- A recognized ship-to-stock supplier

We provide custom hybrid quotes in 2-weeks, prototypes in 8 to 10 weeks. Call the Hybrid Hotline—612-443-2500, ext. 274, for clear answers to your custom hybrid questions.



HYBRID ELECTRONICS DIVISION Box 5000, Victoria, MN 55386

CIRCLE NO 55

#### **UPDATE**

the software analyzer can let you see the range of values that your program's variables assume during the program's run.

#### Measure variable's range

Softanalyst's minimum acquisition interval is 100 nsec, and its front end handles 24 address lines. 16 data lines, and eight status lines. At the fastest acquisition rate, the time-tag counter overflows in approximately four minutes; at the slowest rate, it runs for more than seven hours. The instrument works with predefined software constructs, so it can't trace dynamically defined variables. And because it sees only the µP's activity, it can't follow the activity of such independent hardware devices as memorymanagement circuits or satellite processors.

The Softanalyst requires an IBM PC or PC/AT for control. Including a mainframe, pc boards, an IBM PC interface board, and IBM PC software, the system costs \$9200. A required µP-specific interface pod costs an additional \$765 for the 68000 version and \$1995 for the 8086/186 versions.

#### For more information . . .

For more information on the software analyzers described in this article, circle the appropriate numbers on the Information Retrieval Service card or contact the following manufacturers directly.

Hewlett-Packard 1501 Page Mill Rd Palo Alto, CA 94304 Phone local office Circle No 744

Northwest Instrument Systems Inc 19545 NW Von Neumann Dr Bldg D-4 Beaverton, OR 97006 (503) 690-1300 Circle No 745

Article Interest Quotient (Circle One) High 503 Medium 504 Low 505

### IDT CMOS. When performance counts.






















#### Innovative bit-slice architectures



Last year we ran only six ads...but introduced 62 new high-speed CEMOS™ products. Products at the very forefront of CMOS technology. Faster. Larger. And packed with advanced new features.

As always, we continued to sharpen our technology. Reducing geometries to a 1.2 micron CEMOS IIC production

And we improved the speed of everything we make. Including every CEMOS Static RAM, Subsystem, Digital Signal **Processing Circuit, Memory Support** 

Logic, and MICROSLICE™ bit-slice microprocessor product.

All of which are now available nationwide from Hamilton/Avnet and Diplomat.

Not a bad year's work!

#### May we be of assistance?

For more information on the CMOS products that are shaping the course of future systems, call IDT. We're the innovators in high-speed CMOS. Last year. This year. And into the future.


Leading the CMOS Future

## Integrated Device Technology

3236 Scott Blvd. Santa Clara, CA 95054-3090 (408) 727-6116 TWX 910-338-2070

CEMOS and MICROSLICE are trademarks of Integrated Device Technology, Inc.

# HOW TO KEEP YOUR SOFTWARE FROM DANCING IN THE DARK.



# INTRODUCING THE SOFTANALYST" FROM NORTHWEST INSTRUMENT SYSTEMS.

#### The dark side.

When you finally execute your code on a target micro-computer system, you're often left completely in the dark.

Which procedure is calling which? Which modules are consuming the most CPU time? Is the stack overflowing? Are interrupts serviced fast enough? Is all the code being tested?

#### The bright side.

A new class of measurement tool, the SoftAnalyst from Northwest Instrument Systems, gives you the first complete solution to real-time analysis of high-level programs. It's a non-intrusive, non-statistical system that works with high level languages (e.g. C, Pascal, PL/M and FORTRAN) and assembly.

#### High-level trace of program and data flow.

The SoftAnalyst's Sym-Trace™ gives you real-time trace capability at the module and procedure level, where it's easiest to spot bugs.

See your program as it executes. Discover the actual sequence of procedure calls. Find out how much time is taken to execute a series of procedures. Watch variable values change.

SymTrace shows you all this and more.

Performance analysis pinpoints execution bottlenecks.

Performance analysis shows you where you'll get the best results for your optimization efforts.

Track down modules and procedures that are heavy CPU users. Determine if a procedure's execution time is due to its code, or to the code of its sub-procedures. See the frequency of interrupts.

And that's just the start. With the SoftAnalyst you can zero in on the behavior of a specific procedure to get a distribution of its execution times or to see which routine calls it most frequently.

#### Now, test your program's tests.

For the first time, you can know how thoroughly your test cases have covered your program. Use CodeMap™ to determine if your program has read or written to all array elements. You can even use CodeMap to see how deep your stack goes.

### Choose your own software development environment.

The SoftAnalyst is compatible with a wide spectrum of languages and development environments. It supports multiple microprocessors. So you can use it now and in the future, as your design environment changes.

### Make sure your software sees the light. Call us today.


For technical literature, applications assistance, or a demo on what the SoftAnalyst can do for you, contact us!



NORTHWEST INSTRUMENT SYSTEMS, EUROPE

Am Eichenhag 12 8160 Miesbach West Germany Phone (49) 8025-3260 Telex 526938

#### FORCEFUL.



#### Sprague has led the way in power interface since 1970. After originating its line of Power ICs (PICs), Sprague has increased emphasis on circuits for stepper, servo, and brushless d-c motors. Output drive capabilities have been extended to ±4 A per channel and to sustaining voltages exceeding 60 V. Motor driver types include half-bridge, full-bridge, dual fullbridge, three-phase, translator/driver, and power driver sink or source arrays. All devices include diode transient

protection. Many feature current limiting (PWM), thermal shutdown, over-voltage and/or short-circuit protection. Sprague Electric Company, a Penn Central unit, World Hdqtrs., Lexington, MA. For Brochure WR-202, write to Technical Literature Service, Sprague Electric Company, P.O. Box 9102, Mansfield, MA 02048-9102. For applications assistance, call Mark Heisig or Tom Truax at (617) 853-5000.

# ISSCC '86 speakers predict future developments in solid-state technology

Robert H Cushman, Special Features Editor

Designers who want authoritative forecasts of future trends in solid-state technology won't want to miss this year's International Solid State Circuits Conference (ISSCC), which will take place in Anaheim, CA (see box, "ISSCC registration details"). The conference will provide a forum for industry experts to speculate about technological developments that you can expect to see in the near future.

For example, the informal panel discussion "Microprocessors in the year 2001" will bring together such experts as John Slager of Intel (Santa Clara, CA), who heads the logic-design group for his company's 80386 (which is now engendering the 80486), and Frederico Faggin, who participated in such key historical projects as the initial 4040, 8008, and 8080 µPs at Intel, and then went on to create the Z80 at Zilog (Campbell, CA).

Slager, the panel organizer, believes that although current \$\mu P\$ families such as the 80386 and 80486 will continue to develop, a radically new approach to microprocessors will emerge between now and 2001. He predicts that this new approach will make programming so easy that the industry will abandon established, software-entrenched \$\mu P\$ families like the 8086/80386.

Faggin agrees, saying that it's unlikely that present μP families like the Z80, 8086, and 68000 will face much competition before 2001. Both Slager and Faggin are convinced that ease of use will be as important in new computer systems as raw performance is. Slager expects to see implementations of artificial intelli-


gence in these systems, and Faggin predicts that these systems will begin to emulate the human brain.

Speakers and panelists at the conference will describe at least two relatively new types of  $\mu P$  architectures: the reduced-instruction-set computer (RISC) and the massively parallel architecture. This year, a number of actual examples of these architectures are appearing; they're no longer simply industrial and academic research projects.

According to Randy Katz, organizer and moderator of the Thursday evening panel discussion "Reduced instruction set computers: A new microprocessor era," serious debate over the merits of RISC vs CISC (complex-instruction-set computers)

must take place, because a number of real RISC machines now exist. He cites the IBM 801 ROMP, HP's Spectrum, the MIPS from MIPS Inc, Inmos's Transputer, and the Fairchild Clipper as examples of real RISC machines. Panelists at this discussion will include both advocates and critics of RISC machines.

The other new architecture that ISSCC participants will consider, the massively parallel architecture, will provide a way to achieve higher  $\mu P$  performance: A massively parallel machine need not be especially fast to achieve high computation rates. The paper "A dynamically reconfigurable processor array chip" (session 18) suggests one practical way to achieve such an architecture. As one



The personal workstation of the future will be so user friendly that the human operator won't need a keyboard, say panelists at the ISSCC '86 informal discussion session "Microprocessors in 2001." The user will simply speak to the computer, which will interpret the commands via artificial-intelligence software. The personal workstation will provide as much power as mainframe computers currently do. In addition, the workstation's massively parallel array processor and cryogenically cooled accelerators will let it execute artificial intelligence software in real time. The ISDN telephone will have features like user-selected routing, including broadcast, and optional encryption. The system would give the user economical, effortless access to vast amounts of information, both locally (through devices like CD-ROMs) and globally (through the ISDN).

#### TECHNOLOGY UPDATE

of the authors, Steven G Morton of ITT, explains, you use the reconfigurability of the processor array to select good 1-bit slice processors on very large (500×600-mil) chips. Despite the chip size, Morton claims, you obtain acceptable yields (25%), because you put down more 1-bitwide ALU slices on the die than you need; that is, where you need 16 bit-wide ALU slices, you put down 20.

At run time, the software selects 16 good ALU slices; any remaining good slices are reserves. The 16 slices make up a 16-bit-wide ALU. To make the massively parallel arrays, you wire large numbers of these 16-bit-wide chips into networks of rows and columns.

In a typical application, one program-control unit would send the same instruction to all the chips, which would then execute the instruction simultaneously. For algorithms that can be paralleled, the computation rate would increase accordingly. According to Morton, 200 of these chips could achieve a speed of 2 billion instructions per second (BIPS), despite the modest 10- to 12-MHz clock rates.

#### Cooled CMOS

A more direct way of obtaining increased performance for all CMOS architectures is to cool them cryogenically to very low temperatures (-196°C), as panelists at the Thursday evening discussion "Liquid-nitrogen-cooled CMOS" will suggest. According to one of the panelists, ETA Systems (St Paul, MN) will introduce a cooled-CMOS computer in 1986. This machine is a supercomputer that runs at 5M flops when cooled by air and 10M flops when cooled by liquid nitrogen. The machine uses semicustom CMOS circuits. Only the multiple CPUs are cooled.

The cooled-CMOS technique does involve some tradeoffs, however. Although it makes circuits faster by decreasing some of the resistivities, the technique may cause some circuits to lose speed when hot electrons become trapped in the oxide and shift the device thresholds. In addition, the cooled-CMOS technique will be less useful in devices with smaller geometries.

#### **Future workstations**

A topic of concern to engineers as well as to their employers—the future of the engineering workstation —will be the subject of the keynote address in session 5. In his speech. "Computer-based design for tomorrow's super chip," James Solomon of SDA Systems (Santa Clara, CA) will predict that by 1990, the workstation will be the accepted approach to electronic engineering. By that year, engineers will find at least \$20,000 worth of computing power on their desks when they report to work, Solomon contends. Each engineer will share other equipment (worth \$10,000 per engineer) over a localarea network, he predicts.

In his address, Solomon will also touch upon CAE software. He believes that these CAE tools will be so advanced in the next five years that even engineers fresh out of school will be able to tackle the ULSI (ultra-large-scale integration) chips of 1990. The CAE tools will not only make available large libraries of IC building blocks (such as PLAs, ROMs, RAMs, and data paths)and have block compilers and macrocell place-and-route tools for assembling these building blocksbut they'll also have expert-system overlays, which will guide engineers through the complex design steps. helping them avoid known pitfalls.

Solomon will also predict a new division of labor between the IC experts at the semiconductor houses and OEM engineers. Semiconductor experts, he says, will provide the basic workstation tools and build up the libraries of IC building blocks, while OEM designers define the overall architecture of circuits on chips.

Speakers in session 10 will offer an example of this structured-custom

approach to CAE in the paper "A 32-bit digital-signal processor for motor control." The paper, a joint project by J B Costello and J T Santos of SDA Systems with some authors from National Semiconductor, will propose a universal 1-chip implementation of the electronic portion of dc-motor-position servos. The 28-pin, NMOS LM628/629 accepts position commands from a host μP and generates the trapezoidal motion profile needed to accelerate the motor to the maximum allowed speed and then decelerate it so it stops in the desired position. The LM628's internal, dedicated µP and firmware computes the motion profile and the servostability equalization in DSP fashion. To maintain the accuracy required for large and small position increments, the µP has a 16×16-bit multiplier and a 32-bit ALU.

According to the National designers, the SDA workstation approach allowed them to size the computing and memory functions to the task, keeping chip size—and cost—down. The CAE tools also allowed the designers to develop special variations of the LM628/629 quickly. For example, the designers could incorporate the commutation electronics for a brushless, Hall-effect dc motor on the chip.

A less costly implementation of CAE will be presented in the paper "Reconfigurable logic arrays" in session 18. This CAE implementation will allow engineers to do all design and device programming at their desks on an IBM PC. The software resides on four floppy disks; a board that plugs into one of the PC's expansion slots does the device programming. These user-alterable logic devices are becoming popular because they suit both short production runs and breadboarding, thus sparing the designer the chore of wiring TTL.

Another paper in the session, "CMOS erasable programmed logic with zero standby power," will explain how to keep chips turned off.

#### ISSCC '86 schedule details

The 1986 International Solid State Circuits Conference will take place from February 18 to 21, 1986, at the Anaheim Hilton Towers Hotel, Anaheim, CA. Consult the **schedule** for the times and locations of the technical sessions and informal discussions. You can register for the conference sessions on Tuesday from 4 to 8 PM or on Wednesday through Friday from 8 AM to 4 PM at the hotel's second-floor promenade.

Advance registration fees (before February 7) are \$90 for IEEE members, \$110 for nonmembers. After February 7, those registration fees will be \$100 and \$120, respectively. Each registrant will receive a copy of the *Digest of Technical Papers*; additional copies cost \$60 for members, \$70 for nonmembers, and \$20 for students who attend the conference.

ISSCC'86 AT ANAHEIM HILTON HOTEL/ANAHEIM, CA

	г		OO AI AIVA					HUNTINGTON
		A-B	LIFORNIA PAVILIO	ON D	A-B	PACIFIC BALLROOI	V D	HUNTINGTON
	9:00 AM 11:45 AM	-	SESSION I ANALOG TECHNIQUES	SESSION II PROCESSORS/ COPROCES- SORS	TV THEATER TV THEATER	SESSION III NONVOLATILE AND APPLICATION- SPECIFIC MEMORIES	_	_
.6	12:00 PM 1:30 PM LUNCH		_	_	_	_	_	_
RUARY 1	1:30 PM 2:05 PM	F */**	SESSION IV ORMAL OPENING	G	TV THEATER	-	_	_
DAY, FEBI	2:10 PM 2:50 PM	*/**	SESSION V EYNOTE ADDRES	SS,	TV THEATER	<u> </u>		
WEDNESDAY, FEBRUARY 19	3:20 PM 6:00 PM	-	SESSION VI OPTICAL LINKS	SESSION VII SEMICUSTOM ARRAYS	-	SESSION VIII SIGNAL PROCESSING	SESSION IX SENSOR INTERFACE	_
	6:15 PM 7:15 PM	- The state of the		-	-	Section 250 may 1898/00	TO THE SECOND STREET, SECOND STREET, SECOND STREET, SECOND STREET, SECOND STREET, SECOND STREET, SECOND STREET	AUTHOR INTERVIEWS
				INFORMAL DISC	USSION SESSION			
	8:00 PM	WE 1 DSP ARCHITECTURE	WE 2 TESTING	WE 3 4M- TO 16M-BIT DYNAMIC RAMS	-	WE 4 HIGH- PERFORMANCE STATIC RAMS	WE 5 μPs IN 2001	_
	9:00 AM		SESSION X SPECIAL- PURPOSE	SESSION XI DATA	TV THEATER	SESSION XII IMAGE	SESSION XIII VLSI MODELING	
	12:15 PM PF		PROCESSORS AND CONTROLLERS	ACQUISITION	TV THEATER	PROCESSING	AND PACKAGING	
RY 20	12:15 PM 1:30 PM LUNCH	-	-	-	_	-	_	
THURSDAY, FEBRUARY 20	1:30 PM		SESSION XIV	SESSION XV HIGH-SPEED DIGITAL	TV THEATER	SESSION XVI STATIC		
URSDAY,	5:00 PM	<del>-</del>	VOICEBAND TELECOMM ICs	CIRCUITS AND TECHNOLOGY	TV THEATER	RAMs		
王	5:15 PM 7:00 PM				\$ 200 Sec. 2			AUTHOR INTERVIEWS
				INFORMAL DISC	CUSSION SESSIO			
	8:00 PM	THE 6 RISC	THE 7	THE 8 ASIC MEMORIES	_	THE 9 POWER SUPPLIES	THE 10 LIQUID- NITROGEN CMOS	_
AY ARY 21	9:00 AM 12:15 PM	45 DAA		SESSION XVIII RECON- FIGURABLE	TV THEATER	DYNAMIC		_
FRIDAY	12:15 PM		PROCESSORS —	LOGIC ARRAYS	TV THEATER	-		AUTHOR INTERVIEWS

# Qualidyne means Modular Design Flexibility



#### **ML Series**

Modular switching power supplies that provide custom configuration capability to 300 Watts

- 115/230VAC-100 to 300 Watts
- 24 or 48VDC-50 to 150 Watts
- Up to 6 outputs
- International Safety Standards
- No Main Channel Load required
- Switching, Linear and Semi-regulated outputs
- 75 KHZ switching frequency
- Mosfet Technology

For additional information on this or other Qualidyne products, please call or write:

#### QUALIDYNE SYSTEMS, INC.

3055 Del Sol Boulevard San Diego, California 92154 619/575-1100 TELEX: ESL227140



**CIRCLE NO 59** 

#### TECHNOLOGY UPDATE

until an input transition is detected. Although the part the paper describes is fabricated in CMOS, the programmable array itself is in NMOS (UV-EPROM) technology, and it has sense amplifiers, which also consume power. The paper will examine a method of keeping these power-consuming elements turned off except when logic transitions are detected at the inputs.

#### The future ISDN

Future computers and workstations may well be linked to the rest of the electronic world via the integrated services digital network (ISDN). This proposed system would effect a complete end-to-end digitization of the world's telephone network, as panelists in Thursday evening's discussion "ISDN: The future for telecomm VLSI" will explain.

However, according to moderator Michael Foster of Mitel Corp (Kanata, Ontario, Canada), a few problems are delaying the implementation of the ISDN at present. First, in order to be a cost-effective replacement for the present analog channels, the ISDN will require single-chip (or few-chip) VLSI circuits. IC manufacturers, however, are hesitant to design these complex ICs until the various ISDN standard committees agree upon all the ISDN standards. At present, the North American standards committees are trying to balance sophistication and economy in the coding of the signals that go on the 2-wire U link between a telephone company's central station and a subscriber's line.

Despite the problems with ISDN standards, Foster says, progress with the network is being made. A number of telephone companies are working with various suppliers to set up ISDN trials. In addition, a number of PBX makers are already introducing ISDN concepts in their own equipment, for which they set the standards.

The potential of the ISDN market, for both semiconductor manufactur-

ers and OEMs, will be very great, says panelist Thomas Ladshaw of Lear Siegler (Anaheim, CA). "There are over 100 million phones out there in the US alone, and if just a small percentage of those convert initially to ISDN—say, just the business users—it's still an extremely big market," Ladshaw says.

Foster and Ladshaw agree that when the problems with defining the ISDN standards are resolved, telephone companies will make steady progress in converting the existing telephone networks to ISDN. For one thing, the companies won't have to install any new copper wires: ISDN can use the existing 2-wire loops that go to all phones. And then, the telephone companies will be able to convert their networks to ISDN gradually. They can start by setting up a few ISDN racks in their central stations and connecting only those users who want ISDN services.

Further, Foster says, although the average homeowner might not need to have two 64k-bps ISDN voice and data channels coming into his or her home, third parties that could benefit from such channels might underwrite some of the cost. Utility companies, for instance, could save money by reading meters over ISDN's D control channel. The D channel could also provide a homeowner with communication links to firefighters and police.

These informal discussion sessions—along with the technical sessions on such topics as analog techniques, nonvolatile and application-specific memories, semicustom arrays, DSP architecture, data acquisition, image processing, high-speed digital circuits, high-performance static RAMs, and dynamic RAMs—will inform attendees of ISSCC '86 about recent innovations in technological research and give them a foretaste of future developments.

Article Interest Quotient (Circle One) High 506 Medium 507 Low 508

# INTRODUCING OUR 1986 COMPACTS.

# 0-50,000 IN 0.7 NSEC.

Open one up.

And feel your pulse accelerate. 50,000 logic gates on a single chip. Room enough to implement large macrofunctions and build an entire digital system.

All with our new LCA 10000 Compacted Array™ Series.

In theory, somewhere between a gate array and a cellbased custom IC.

In practice, it's a flat-out acceleration of our ASIC technology. With advanced 1.5 micron, dual-layer HCMOS technology. And our innovative variable routing tracks.

For performance no mere gate array

can touch, 0.7 nanosecond propagation delay for a 2-input NAND gate. ECL-like speeds. Random Routing. VHSIC performance compatibility. And more.

You'll get there fast, too, using our proprietary LDS Design System. Working at any of our 12 worldwide design centers.

And you'll get there safely. Thanks to our proven 97%

first-time hit rate.


With manufacturing in our facilities. The best equipped in the country. Geared to pump out all you need. From hundreds. To hundreds of thousands. All thoroughly tested on our 256pin system.

Start yours today. Call one of our sales offices listed below.

Because with our new Compacted Array Series driving your next design

there's no telling how far you'll go.

Or how fast.



Our new 50,000-gate

LCA 10000 Compacted Array Series makes "System Scale Integration" a reality.

Now, you can fit an entire

system on a chip.

Even the packaging is advanced, with up to 256 I/O signal pins.

LSI LOGIC CORPORATION

San Jose, CA 408/248-5100, Irvine, CA 714/261-0124, Sherman Oaks, CA 818/906-0333, Denver, CO 303/756-8800, Westport, CT 203/222-9336, Altamonte Springs, FL 305/339-2242, Boca Raton, FL 305/395-6200, Schaumburg, IL 312/397-0155, Waltham, MA 617/890-0161, Ann Arbor, MI 313/769-0175, Minneapolis, MN 612/835-6161, Raleigh, NC 919/872-8400, Trevose, PA 215/638-3010, Austin, TX 512/343-4513, Dallas, TX 214/788-2966, Bellevue, WA 206/455-5055, Nepean, Ontario 613/726-1585, England 44-344-426544, Israel 972-3-421146/7, Japan 81-3-589-2711, West Germany 49-89-926903-0 LCA 10000 Compacted Array Series is a registered trademark of LSI Logic Corporation. © 1985 LSI Logic Corporation.

# What do IBM, computers have



# DEC, and Apollo in common?

Take the engineering computer of your choice. Add one fully integrated electronic development system. That's Tektronix Aided Engineering.

The Tektronix WorkSystem™ design family is equally at home in the AEGIS\*, UNIX\* or VMS\* environment. So you get total development support—from design capture and verification through test—on the enhanced IBM Personal Computer AT\*; Digital Equipment Corporation's VAX\* computers, VAXstation II\* and MicroVAX II\* workstations, and Apollo workstations.

The WorkSystem family supports design, layout and simulation of standard cells, gate arrays, structured custom and full custom circuits, even PC boards. There's even a WorkSystem for test and measurement, and another for software development.

Together, they make up the most by the kind of service and support capable design tools you can have today. programs that you've come to expect regardless of your hardfrom Tektronix. Test and If you have an IBM ware! All from Tektronix. Measurement WorkSystem Every WorkSystem Designer's WorkSystem AT, Apollo, DEC Microshares our unique VAX II, VAX station II, VAX Designer's Database 11/750, 11/780 or that lets you partition 8600 computer your de-Gate Array system, let us VorkSystem sians. turn it into a Tekmaking tronix Aided team engi-Engineering DATA neering a tool, right BASE reality. The now. Or. if open architecyou haven't Cell WorkSystem ture design of the selected database also your allows you to CAE tools System interface vet, let us provide vou Structured your existing tools to our with a complete system, WorkSystems, So your built around the com-WorkSystem prior investments in puter that's best for all hardware and software your needs. are protected. Call us at 800/547-1512 (in Oregon, For all their power, Tektronix Work-800/542-1877). Or write Tektronix, System solutions are surprisingly easy CAE Systems Division, 5302 Betsy

Tektronix Aided Engineering.



Ross Drive, Santa Clara, CA 95054.

to learn, and easy to use. They're backed

# 

from two new mass storage solutions from Bering Industries. The Series 8000-EP and TopSecret Removable Hard Disk Subsystems. Designed for HP computers using CS/80 and SS/80 command sets, like HP1000, HP3000, and HP9000 Series 200/300/500 systems.

#### **Enhanced Performance** 8000-EP

Bering's Series 8000-EP enhanced performance hard disk subsystems offer an alternative HP mass storage solution. From 65MB to 190MB, the EPs are worth a close look.

Cost Savings. At \$60 per MB, EPs are price/performance leaders. Savings can be up to 45% the cost of a comparable HP drive. And Bering's standard one-year warranty applies to all EP models.

Capability. Designed for HP users' critical performance needs in real-time and multi-user environments, the EPs are the best choice. An advanced disk controller and fast head seek mechanism match average transfer rates of HP7912/7914 drives.

Compatibility with HP-IB. The EPs are designed for any HP computer using CS/80 and SS/80 command sets. Compatibility is guaranteed. No hardware or software changes are needed for installation.

Bering Series 8000-EPs and TopSecret Removable Hard Disk Subsystems are HP-IB compatible and designed for any HP computer using CS/80 and SS/80 command sets.

Compact. EPs save prime office or lab real estate. At one-third the size of an HP7912/7914, EPs are compact and ideal for stacking or rack mounting.

#### **Topsecret Removables**

Data Security. Securing classified data is easy with 5.25" Top-Secret removable hard disks. Sensitive information can be locked away in a safe, 10MB at a time. Personal data storage and selective file back-up is convenient and fast.

Unlimited Storage. With a TopSecret, storage is virtually unlimited simply by inserting another cartridge. No need to buy another drive to increase capacity. A two-sided built-in 3.5" floppy is optional.

Bering has set the pace for innovative mass storage solutions in the HP world since 1981. Bering is an official HP Independent Hardware Vendor with authorized service and support by DATAGATE in the USA, and by DATATECH in Canada. For complete specifications on the EPs, the TopSecret, and 100 other disk configurations, call or write us today!

Note: HP, CS/80, SS/80, and HP-IB are tradenames of Hewlett-Packard Company.

### BERING

Official Hewlett-Packard Independent Hardware Vendor

#### Bering Industries, Inc.

1400 Fulton Place Fremont, CA 94539 Telex: 325606 415/651-3300

# PC/AT-compatible data-acquisition board has 12-bit analog I/O, 130-kHz throughput


The DT2821 12-bit data-acquisition board, which plugs into a card slot in the IBM PC/AT and clones, performs conversions at rates as high as 130 kHz. This conversion rate represents a quantum leap over that of earlier cards, which provide 50-kHz max throughput. Model DT2821-F-16SE accepts 16 single-ended inputs, and the DT2821-F-8DI has eight differential-input channels.

The key to the speed of the system's analog-to-digital conversion is the manufacturer's DT5725 analog-input module (see "Modular analog-input and -output units provide high speed and resolution," EDN, August 8, 1985, pg 97). This 150-kHz module contains the multiplexer, instrumentation amplifier, track/hold amplifier, A/D converter, and control logic needed to perform the DT2821's data-acquisition function.

You use a 2-bit code to program the instrumentation amplifier's gain to 1, 2, 4, or 8. Input range is jumper selectable to  $\pm 10$ V or 0 to 10V; division by the selected gain value yields the effective input range. A 4-bit word selects the channel to convert.

#### Unit has RAM channel/gain list

A convenient feature in the DT2821 is a RAM channel/gain list. This block is a 16-location RAM that you can use to specify the sequence of channels and the gain at which the system will sample each channel. When an A/D-conversion scan begins, the board sequences through the RAM, sampling each channel entry at the specified gain. The RAM allows you to predefine virtually any desired sampling sequence: sequential sampling (0 to n or n to m channels, for example), random channel sampling (eg, chan-



Boasting the highest speed in the industry, the DT2821 data-acquisition board brings analog-I/O capabilities to the IBM PC/AT and clones. Its 130-kHz throughput rate stems from the manufacturer's high-speed analog-input module. The unit accommodates 16 channels of data in the single-ended version and eight channels in the differential-input version. You can use the system in programmed-I/O or DMA mode.

nels 0, 3, 2, 5), or successive samples on a single channel at the same or different gain.

In addition to the A/D converter, the DT2821 contains two independent 12-bit D/A converters. You can control the D/A section in either programmed-I/O or DMA mode. The A/D and D/A converters have sufficient differential linearity to guarantee no missing codes and monotonicity (respectively) over 0 to 70°C. The D/A converters are low-glitch types: Glitch area is typically 3 mV·µsec. You use jumpers to select unipolar output ranges of 0 to 5V or 0 to 10V; bipolar ranges are ±2.5, ±5, or ±10V.

#### Card has five interrupt levels

The data-acquisition card accommodates interrupts to the PC/AT's processor upon the completion of significant events. The board's interrupt source, selected under pro-

gram control, includes A/D done (programmed I/O transfers); A/D DMA done (DMA transfers); A/D scan done; A/D error; D/A ready (programmed I/O transfers); D/A DMA done; and D/A error. The DT2821 can interrupt the processor on any of five levels (from highest to lowest): 10, 15, 3, 5, or 7. You use a jumper to select the interrupt level.

Continuous-performance DMA operation allows the DT2821 to perform gap-free DMA transfers of large amounts of data. Data is transferred through a pair of buffers, each associated with a separate DMA channel. The transfers require both buffers: Upon reaching the end of the first buffer, the system shifts automatically to the second buffer without pausing or missing any samples.

You can use the onboard pacer clock to initiate A/D, D/A, or concurrent A/D and D/A conversions.

# AC POWER ...FOR EVERY APPLICATION





From computer controlled AC Power Sources for test labs through back-up power in the computer room, Behlman Engineering covers the entire spectrum of AC power requirements.

#### INSTRUMENT QUALITY AC POWER SOURCES

Behlman Engineering's instrument quality AC power sources greatly enhance your testing capabilities and effectiveness for complex computer controlled, or simple manual tests. These efficient linear sources are widely used in ATE systems, laboratories, production lines, test facilities, quality control and many other applications.

- · Manual or computer control
- 45 Hz to 10,000 Hz
- 100 VA to 54 KVA power ratings
- 1, 2, and 3 phase outputs
- Up to 300% overload transient capability
- Measurements of outputs independent of programmed values, including diagnostics.
- IEEE-488 (Talker/Listener) interface
- Smaller, lighter saves rack space
- ATE applications
- Military test systems including MATE and CASS
- · Avionics testing
- DC power supply testing

#### UNINTERRUPTIBLE POWER SYSTEMS

Behlman UPS' continuously guard against power failure while also protecting sensitive electronic equipment from line anomalies. The range of applications spans from the office to advanced space and military programs. The Behlman UPS Series provides the finest in AC power for sensitive applications such as: Tempest systems, instrumentation, security, communications, Automatic Test Equipment and computer systems.

- Low EMI/RFI
- · Input and output transformer isolation
- · Purest sine wave power available
- 100 VA to 20 KVA, 1 and 3 phase
- Up to 300% transient overload capability
- High noise rejection/suppression
- · Rugged design and high reliability
- Low distortion, under 1.0%

Call or write today for more detailed information.



Electronic Energy Conversion Sources & Systems

(805) 684-8311

1142 Mark Avenue Carpinteria, CA 93013

#### UPDATE

The clock comprises three elements: a 6-MHz pulse generator, a clock prescaler that serves as a programmable divider, and a counter divisor. You can set the prescaler in powers of 2 from 0 to 31. The counter divisor is an 8-bit programmable counter that divides the prescaler's output by a number from 1 to 256.

ATLAB, a real-time software package from the DT2821's maker, accommodates Call commands from Fortran, C, and Pascal. The software provides library routines for control of all the system's analogand digital-I/O functions. An error-processing system checks for argument errors and generates error reports. The system reports—and refuses to obey—attempts to operate the board in illegal modes of operation.

Several screw-terminal and signal-conditioning panels are available from the manufacturer. The 130-kHz DT2821 costs \$1595, and ATLAB is priced at \$449. A 50-kHz version of the DT2821 has all the features of the higher-speed units and costs \$1195.—*Bill Travis* 

Data Translation Inc, 100 Locke Dr, Marlboro, MA 01752. Phone (617) 481-3700.

Circle No 729

## LOW-COST SOLUTIONS IN GRAPHICS

GET A PRICE BREAK ON THE GRAPHIC DISPLAY CONTROLLER AND A PERFORMANCE EDGE WITH THE DUAL-PORT VIDEO RAM.

Introducing the first integrated graphics processing team: NEC's dual-port video RAM and graphic display controller. Together they break through the screen-memory-CPU bottleneck. And give you better graphics at a bargain price.

Two Ports are better than One

Our 256K dual-port RAM uses up to 95% of the RAM port bandwidth. Versus 30% with standard RAMs. You can drive the RAM port continuously while video data exits asynchronously through the serial port. Two ports open two big benefits: greater throughput and higher speed.

Four-to-One Price Advantage

Maximize that performance edge with our 7220A high-speed GDC, the industry standard. At one-fourth the cost of the competition, the 7220A meshes smoothly with the video RAM. You can spend more. But you can't buy a better team.

NEC's graphics processing team does more than lower chip count, increase drawing speed, boost memory efficiency, and simplify design. It also gives you the most cost-effective solution on the market.

#### **Graphics Processing Team**

O. up	0
Dual Port Video RAM	μPD41264
Graphic Display Controller	μPD7220A

#### Call Toll Free

To get the full picture, call NEC today at 1-800-632-3531. In California: 1-800-632-3532. For technical information, pricing, or delivery, ask for the number of your local NEC office or distributor.

©Copyright 1985 by NEC Electronics Inc.

WE'RE TAKING ON THE FUTURE



401 Ellis Street P.O. Box 7241 Mountain View, CA 94039

CIRCLE NO 62



# Wireless modem and portable computer provide secure, encrypted network

Using packet radio-transmission technology to eliminate the cables commonly associated with local-area networks (LANs), the Esteem Model 85 wireless modem and Quest wireless portable computer team up to create a mobile, encrypted LAN with a communication range as great as 50 miles.

The Model 85 modem offers you 50 channels and a 1k-byte data spooler, yet consumes only 1W. The device's effective baud rate is 2817 bps—a slow rate compared to those of cable-based LANs like Ethernet, which boast data rates of 9600 bps and greater. The 2817-bps rate is, however, much faster than the ubiquitous 300- and 1200-bps modems that operate via telephone lines. Furthermore, this radio modem eliminates the considerable expense of laying cables or wires.

The Z80-based modem uses packet radio techniques to transmit rapid bursts of tightly grouped data. Prior to transmission, the modem compresses and encodes the data, via the High Level Data Link (HDLC) format, into compact frequency-modulated packets of 504 bytes each. The modem then runs the HDLC format through a Manchester coder and transmits the data. The receiving radio modem uses 16-bit error-correction algorithms to screen the incoming packets for bad data. If it detects an error, the receiving unit sends a retransmission signal to the sending unit, and the sequence begins again.

Each modem has a unique address, and each provides network management for as many as 254 terminals. DIP switches on the Model 85's back panel allow you to set the baud rate and radio frequency. You can adjust the baud rate to allow the modem to communicate



You can develop a LAN without telephone connections or costly cabling by using the wireless Model 85 modem. You can rearrange the communications network just by moving your RS-232C-compatible equipment to a new location.

with other devices via an RS-232C port at 19k bps in full-duplex mode. You can also select a radio communication frequency between 72.04 and 72.96 MHz at 40-kHz intervals.

The Model 85 offers an impressive level of data security. Each modem transmits on one of 50 frequencies and has one of 254 addresses, so each unit offers 12,700 possible frequency-address combinations. A person couldn't eavesdrop on your data transmission simply by buying a radio modem and determining your particular frequency and address—the individual would still have to synchronize his system with the random bursts of data from your

packet radio transmission. For even greater data security, you can order an encryption board that meets the National Bureau of Standards' information-processing data-encryption standard No 46.

The Quest radio computer is a logical companion to the Model 85 modem. The 7-lb computer has a 1-in. base that contains a battery pack and radio modem. It comes with 16k bytes of RAM that's expandable to 96k bytes, an 8-line×40-character LCD, a full-size keyboard, ROM-based text editing, Basic, a scheduler, and telecommunications software.

Together, the modem and computer form a network that's completely free of the limitations of power cords and communication cables. Further, the radio-based network lets you mix hardware from a variety of manufacturers without worrying about software incompatibility. Model 85, \$1200; Quest, \$2295.—J D Mosley

Electronic Systems Technology, 1031 Kellogg St, Kennewick, WA 99336. Phone (509) 735-9092. TLX 152514.


Circle No 727



Suitable for mobile data communications, the Quest portable computer needs no power outlets, telephone wires, or network cabling to establish a computer link with other equipment.


### Thank You, Telecom Designers

We just delivered our millionth SLIC...



1,000,000

and helped you shrink 100,000 boards!



Thank you for making Harris the largest world-wide supplier of solid-state Subscriber Line Interface Circuits. You've discovered our Dielectric Isolation process is the perfect solution for high-voltage line interface problems. You've seen how DI offers you the performance, reliability, and space savings you need, all at lower cost and proven out by volume production. You've continued to look to Harris for the "solid-state of the art" in telecom designs — because while others talk SLICs, Harris delivers.

Harris wrote the book on DI. For a free copy of our white paper on the advantages of Dielectric Isolation for telecom applications, write Harris/MHS
Semiconductor Sales Ltd., Eskdale Road,
Winnersh, Wokingham, Berks, RG11 5TR,
England.

DI
Advantages
for
Telecom

Harris Semiconductor: Analog - Bipolar Digital CMOS Digital - Gallium Arsenide - Semicustom - Custom - Hybrids




For your information, our name is Harris.

## 18V linear/digital CMOS arrays implement automotive- and industrial-control circuits

Series MH silicon-gate CMOS arrays operate with supply-voltage levels as high as 18V, suiting them for automotive- and industrial-control applications. The center of each array contains transistors organized to implement digital gates. Around the periphery are larger transistors suitable for implementing output drivers and linear circuits. In addition, digital cells by the output pads can implement I/O circuits or logic gates, increasing the capability of the array.

#### I/O cells implement logic

The series consists of eight arrays that vary in complexity from 70 to 1600 equivalent 2-input gates and 18 to 84 I/O pads (**Table 1**). An I/O cell at each pad contains diodes that protect against voltage extremes and an npn transistor that can supply 10 mA. In addition, the I/O cells contain digital circuitry that can implement input, output, and bidirectional buffers. Peripheral circuitry not used for I/O can implement logic functions; for example, you can build four NAND gates or a D-type



Analog components surround digital gates on MH Series arrays. Built to operate with 18V supply levels, the arrays are suitable for automotive- and industrial-control applications.

flip-flop in an I/O cell if the cell is serving as an input buffer. The peripheral circuitry makes the logic complexity of the arrays higher than their listed number of equivalent gates.

You can create analog circuits from the I/O circuitry as well. Although the vendor includes no ana-

log cells in its function library, you can build such linear circuits as current mirrors, op amps, and D/A converters from the transistors on the periphery of the arrays. The vendor plans to develop and offer analog cells this year.

The vendor currently supplies a library of digital macro functions (cells) for Mentor and FutureNet workstations for logic and circuit design. Alternatively, the company can supply you with its CAE software, or it can perform the design for you. The library contains 50 functions that the company modeled after standard Series 4000 CMOS parts. Once you've settled on your logic design, the company performs all layout tasks and submits final performance estimates for your approval. Turnaround time for prototypes, including layout, is six to 16 weeks, depending on design complexity and on how much of the design the company performs.

#### Many package types available

The vendor packages the arrays in DIPs, small-outline packages, surface-mount carriers, chip carriers, and pin-grid arrays. Plastic and ceramic versions are available for many packages. The DIPs have pin counts as high as 48, and chip carriers and pin-grid arrays can supply as many as 84 pins. The manufacturer can perform all processing, packaging, and screening in accordance with MIL-STD-883C requirements.

Nonrecurring engineering (NRE) charges start at \$5000, and unit prices start at \$1 (for 10,000 MHA arrays in 14-pin plastic DIPs).

#### -David Smith

Ferranti Interdesign Inc, 1500 Green Hills Rd, Scotts Valley, CA 95066. Phone (408) 438-2900.

Circle No 726

#### **TABLE 1—MH SERIES CMOS ARRAYS**

	to the state of th		a significant and the significant
ARRAY	I/O PADS	EQUIVALENT GATES	SMALLEST PACKAGE (PINS)
MHA	18	70	8
МНВ	24	140	8
MHC	30	200	14
MHD	40	330	14
MHE	48	500	.14
MHF	56	660	22
MHG	68	1000	22
мнн	84	1600	22

# No "boomerang effect" at Trend Circuits. Less than 1% of our prototype boards ever come back.

ast turnarounds in prototype circuit boards are great—but not when the boards circle back again and again because of poor quality.



That "boomerang effect" costs precious time in proving your concepts and can end your chances to meet critical market windows.

types don't work. At Trend Circuits, we're specialists in rapid production of prototype boards that work first time out. That's because we're people who understand your language, your objectives and your pressures.

Further, fully one-third of our people are involved in inspection. We begin with incoming artwork, where we can quickly identify common design errors. And we continue with double-and triple-checking right through to completion. As a result, less than a scant 1% ever come back. And that's good for both of us.



Now for speed. On a regular basis, we deliver double-sided boards within 24 hours, and multi-layer boards within five days. In fact, we're completing no less than 82% of all our work within five days.

Check our references.

You can verify our facts easily enough by talking to our customers. Simply phone and we'll put you in touch with people who've decided they won't accept compromise in quickly moving from design to finished prototype. They'll tell you why we're their logical choice for "noboomerang" boards. And why we should be yours.

#### TREND CIRCUITS

44358 Old Warm Springs Road Fremont, CA 94538-6148

415/651-1150 800/448-0550 (nationally) 800/448-0440 (in California)

We deliver speed and quality.

Speedy turnarounds don't count for much if proto-

### SAVE BIG ON HEWLETT-PACKARD Lower Prices on 4 Hewlett-Packard "Best Seller" Calculators

• HP11C	\$ 43
• HP15C	75
HP41CV	134
• HP41CX	189

Above Prices Effective 2/1/86

#### SLIMLINE Shirtpocket Styled Power Packed Programmable LCD PROBLEM SOLVERS

<b>HP-11C</b>	Scientific \$43
HP-15C	Scientific 75
HP-12C	Financial90
HP-16C	Programmer90

## SPECIAL PURCHASE! Hewlett-Packard QUAD MEMORY MODULE

Upgrades the HP41C to the power of the HP41CV

HP-41CV\$134	1
HP-41CX189	Ŀ
Optical Wand 95	123
Card Reader 145	13
Printer 283	-
Quad R.A.M.(for HP41C) 60	
Ext. Memory Module 60	
Ext. Function Module 60	-
Time Module60	W



#### HEWLETT-PACKARD HP-71B COMPUTER \$399



HP-82400A Series 70 card reader 125
HP-82401A HP-IL interface95
HP-82402A 4K memory module60
HP-82700A 8K memory module 150
HP-82441A Assembly/Forth 120
HP-82480A HP-71 math pac 75
HP-82482A HP-71 finance pac 60
HP-82483A Serveying Pac 120
HP-82484A Curve Fitting
HP-82485A Text Editor 60
HP-82488A Data Com. Pac 120
TII OZTOCK Data COIII. Fac 120

HP-IL Loop Module	Mfr Sugg 125	95
Digital Cassette Drive Printer/Plotter(HP-IL)	450 450	400 335
HP-2225B ThinkJet Printer	430	350
HP-9114A Disk Drive	_	600



#### CALL TOLL FREE 800-621-1269 EXCEPT Illinois, Alaska CANADIAN TOLL FREE 800-458-9133

Corp. Accts. Invited. Min. Ord. \$15.00. Visa or MasterCard by Mail or Phone. Mail Cashier's Check, Mon. Ord., Personal Check (2 wks. to clear) Add \$4.00 1stitem. (AK, HI, P.R., Canada add \$10.00 first Item) \$1.00 ea. add



**CIRCLE NO 65** 

#### PRODUCT UPDATE


# Motion-control subsystem is STD Bus compatible

Model 450/451/452 2-card servo-I/O subsystem includes a general-purpose motion controller and a pulse-width-modulated (PWM) servo amplifier. You can use the system as a complete single-axis drive controller for dc motors. The controller is compatible with the STD Bus; it accepts commands from either the bus, an RS-232C serial input, or local switches.

The 450 Series controller is a microprocessor-based system that can control motor position, velocity, and torque. The system generates a trapezoidal velocity profile that has programmable acceleration and slew rates. The system, which needs no analog feedback, owes its stability to digital filtering. You can vary the filter's coefficients to suit particular robotics and automation applications.

Residing on a second card, the PWM output amplifier is available in three ratings. Model 450 contains an amplifier that can drive motor loads requiring 5A peak and 2A continuous current at voltages from 15 to 45V. Models 451 and 452 both accommodate voltages of 15 to 75V; the 451 provides currents of 10A peak, 4A continuous; the 452 controls 20A peak, 7A continuous current.

To avoid generating acoustical switching noise, the PWM amplifiers use a 22-kHz switching frequency. This high switching frequency also allows you to dispense with a series choke in applications using low-inductance motors. A power-MOSFET bridge in the amplifier's output circuit provides high-efficiency switching—for example, Model 452 dissipates only 12W while providing 500W output power. An internal dc/dc converter generates



High-power motor control in a small package and STD Bus compatibility are the hall-marks of Series 450 motion-control subsystems. The 2-card set can control loads demanding power as high as 500W, yet the output amplifier dissipates only 12W, because the switching elements are power MOSFETs.

all bias voltages needed on the amplifier card.

All Series 450 controllers operate over 0 to 70°C without derating. Required power supplies are 5V and ±12V for the controller card and 15 to 45V (Model 450) or 15 to 75V (Models 451 and 452) for the PWM servo-amplifier card. Prices for the 450, 451, and 452 2-card systems are \$995, \$1085, and \$1175, respectively.—*Bill Travis* 

Copley Controls Corp, 375 Elliot St, Newton, MA 02164. Phone (617) 965-2410.

Circle No 728

# THE FIRST SINGLE-CHIP MODEM SOLUTION JUST FELL INTO YOUR LAP.



For truly portable, batterypowered data processing applications, you really need a full-featured single-chip modem. Especially if you're designing laptop computers.

And the fact is, you don't have many choices.

So go with the first choice: Fairchild's new μA212A.

It's perfect for laptop PCs because it's the first single-chip, Bell 212Acompatible modem IC with 1200/300 bps full duplex transmission. And power consumption? The μA212A, made with our highperformance, double-poly silicon-gate CMOS process, features a typical power consumption of only 45 mW. And it performs all the signal processing functions singularly, compared to the competition's solutions requiring up to five chips.

Now designing with modems is easier and faster than ever before. Particularly in applications such as desktop PCs and workstations, voice/ data terminals, hand-held terminals, remote diagnostics, instrumentation, and stand-alone modems. And we back the µA212A with Fairchild's comprehensive design and customer support.

For more details on the new uA212A, simply contact The Fairchild **Customer Information Center at** 1-800-554-4443.

The Fairchild single-chip modem. It'll put all vour modem designs in the lap of

luxury.

We're taking the high ground.

FAIRCHILD

A Schlumberger Company

©1986 Fairchild Semiconductor Corporation

#### LEADTIME INDEX

Percentage of respondents

	700	. 7		٦		6	MONIN'S W			V	N N		A		6		
					_	97	30								2	MONINS	
9		6	1	2	Over		ONIS.		9		6	1	2	Over		ONIN.	
	180 1	54 0	204	304	004	12.5	2/20	2		130	5 0	20	00	30	48	120	2
ITEM	Ine shell	Sweets weets	17.20 W	27.30 W.	Over 30 W	weeks	Metage 1	verage	ITEM	time shell	Sweets	17.20 W	T.30 W.	Over 30 W	weeks	We lade	6,30
		U'	υ,	G,	U,	O.	7 0	2-8		7	· Sr	'U'	·U	.v	·u	200	-,-6
TRANSFORMERS	551 <b>e</b> A	10	67		. 0	0		0.7	RELAYS	00	00	- 00	10	1911 . <b>*</b> 12			
Toroidal Pot-Core	5	19	67 73	9 20	0	0	7.2 9.2		General purpose PC board	26	26 50	32	16	0	0	5.5	4.
Laminate (power)	6	18	47	29	0	0	8.8		Dry reed	0	37	25 63	25	0	0	7.0	6.
		10	- 41	23	U	0	0.0	0.0	Mercury	0	25	75	0	٥,	0	6.5	6.
CONNECTORS Military panel	0	33	67	0	0	0	60	10.6	Solid state	0	40	33	27	0	0	7.7	
Flat/Cable	6	55	39	0	0	0	4.2		DISCRETE SEMICO	MDUC					-	, , , ,	0.
Multipin circular	11	33	28	28	0	0	7.3		Diode	30	27	34	9	0	9	4.6	5.
PC	0	55	36	9	0	0	5.4		Zener	21	18	54	7	0	0	5.7	4.
RF/Coaxial	21	29	29	14	7	0	7.0		Thyristor	6	35	47	12	0	0	6.3	4.
Socket	26	37	37	0	. 0	0	3.6	A-	Small signal transistor	20	20	48	12	0	0	6.3	4.:
Terminal blocks	16	47	37	0	0	0	3.8	4.3	FET, MOS	14	36	36	7	7	0	6.7	5.0
Edge card	17	39	44	0	0	0	4.3	6.2	Power, bipolar	29	14	29	21	7	0	7.8	5.9
Subminiature	15	21	43	14	7	0	8.0	6.7	INTEGRATED CIRC	PILITS	DIGIT						
Rack & panel	0	63	37	0	0	0	4.2	6.0	CMOS	18	21	32	21	4	4	8.4	5.
Power	0	78	22	0	0	0	3.3	6.6	TTL	32	12	24	32	0	0	7.2	5.8
PRINTED CIRCUIT	BOAR	DS							LS	25	20	30	25	0	0	6.8	6.0
Single-sided	0	64	36	0	0	0	4.1	3.7	INTEGRATED CIRC		-	-					5.0
Double-sided	0	50	43	7	0	0	5.5	5.3	Communication/Circuit	0	33	50	17	0	0	7.3	6.0
Multilayer	6	0	69	25	0	. 0	9.5	7.2	OP amplifier	25	25	30	15	5	0	6.6	5.8
Prototype	4	80	8	4	4	0	3.9	2.7	Voltage regulator	23	23	45	5	4	0	6.0	5.0
RESISTORS Carbon film	36	36	19	9	0	0	3.6	2.7	MEMORY CIRCUITS	s	*****						
Carbon composition	31	31	23	15	0	0	4.9	3.8	RAM 16k RAM 64k	39	22	22	17	0	0	4.9	5.1
Metal film	10	38	31	21	0	0	6.5	3.9	RAM 256k	38	31	15	16	0	0	4.3	4.4
Metal oxide	8	50	42	0	0	0	4.3	3.2	ROM/PROM	18	45	18	19	. 0	0	5.3	5.7
Wirewound	9	27	35	9	0	0	6.3	8.1	EPROM	18	18	45	19	0	0	6.9	7.2
Potentiometers	14	32	41	9	4	0	6.5	3.9	EEPROM	34	0	23	23	0	0	6.2	6.0
Networks	17	35	35	9	0	4	6.2	-		34	U	33	33	U	0	8.0	5.7
FUSES									DISPLAYS			Name and Address of the Owner, where the		Minaro			
TOOLS	32	54	14	0	0	0	2.1	2.6	Panel meters	27	27	27	19	0	0	5.6	5.0
SWITCHES		0.1		-			2.1	2.0	Fluorescent	0	50	25	25	0	0	7.0	6.1
Pushbutton	27	27	41	5		0	A E	2.5	Incandescent LED	14	57	29	0	0	0	3.4	5.3
Rotary	11	22	56	11	0	0	4.5 6.6	3.5 4.2		30	25	40	5	0	0	4.5	5.3
Rocker	9	36	36	19	0	0	6.5	5.3	Liquid crystal		19	64	9	0	0	6.7	8.2
Thumbwheel	10	30	30	30	0	0	7.8	7.1	MICROPROCESSOR		45			** * * * * * *		15 X Y 1	
Snap action	25	25	33	17	0	0	5.8	4.9	8-bit	23	6	53	18	0	0	7.2	6.9
Momentary	23	39	23	15	0	0	5.0	6.1	16-bit	21	14	36	22	7	0	8.4	7.9
Dual-in-line	15	50	21	14	0	0	5.0		FUNCTION PACKA					2-0-71 - 2-0-10			
WIRE AND CABLE									Amplifier	44	0	45	11	0	0	5.3	6.8
Coaxial	22	50	21	7	0	0	3.8	2.5	Converter, analog to digital		42	33	17	0	0	6.2	6.7
Flat ribbon	25	60	15	0	0	0	2.4	3.1	Converter, digital to analog	g 8	42	33	17	0	0	6.2	6.7
Multiconductor	18	47	23	0	0	0	4.7	4.1	LINE FILTERS								
Hookup	52	33	15	0	0	0	1.8	1.3		25	0	50	25	0	0	8.0	5.4
Wire wrap	15	70	15	0	0	0	2.6	1.7	CAPACITORS								
Power cords	16	58	21	5	0	0	3.6	3.8	Ceramic	21	29	46	4	0	0	4.9	5.2
Other	11	44	33	0	12	0	6.4	6.6	Ceramic monolithic	28	24	43	5	0	0	4.7	5.2
POWER SUPPLIES									Ceramic disc	19	28	48	0	5	0	5.6	3.5
Switching	0	25	58	8	9	0	8.6	8.4	Film	23	27	36	9	0	5	6.3	4.8
Linear	0	25	75	13	0	0	6.5	6.1	Electrolytic	15	26	48	11	0	0	6.1	5.5
CIRCUIT BREAKER	***************************************								Tantalum	12	12	63	13	0	0	7.3	5.3
OHOUH BREAKER	<b>5</b>	54	31	15	0	0	6.0	5.8	INDUCTORS	22	17	50	5	6	0	6.7	4.0
HEAT SINKS																U.I	7.0

# ABBOTT DELIVERS ITS FIRST PAIR OF TRIPLES.



## ABBOTT'S NEW TRIPLE OUTPUT, 200 kHz 100-WATT SWITCHING POWER SUPPLY SERIES.

In response to the critical need for low profile, triple output, high switching frequency power supplies for use in airborne, shipboard or ground support installations, Abbott has created two new 100-watt switchers that live up to our reputation—"When reliability is imperative."

Triple output, low ripple and noise specs combined with hermetic seal construction make both WMI00T and MBI00T perfect for powering digital integrated circuitry, logic circuits, data processing and retrieval, sonar, radar, communications and electronic countermeasures equipment.

Designed for the military environment, model WM100T, optimized for an airborne environment, accepts a 400 Hz input. For naval applications model MB100T accepts a 60 Hz input, while both deliver 100 watts in a high-density package of  $1.875'' \times 4'' \times 7.5''$ .

Standard features include short circuit protection and remote error sensing. Options which add extra versatility include 3-phase/wye configuration, wider input voltage range, TTL turn-on/turn-off and military connector.

And that's just the beginning. Soon Abbott will offer several additional power supply families which range from 60 to 500 watts, with single, triple and quadruple outputs to choose from. Call or write for complete specs and our new Abbott Military Power Supply Catalog today. Abbott Transistor® Laboratories, Inc., Power Supply Division, 5200 West Jefferson Blvd., Los Angeles, CA 90016 (213) 936-8185. Eastern Office: (201) 461-4411. Southwest Office: (214) 437-0697.

WMI00T Input frequency Input voltage Outputs Switching frequency Efficiency Ripple/noise Line regulation Load regulation **FMI** Environment Input protection Operating temperature range Storage temperature range MTBF\* (ground benign) MTBF\* (ER Option) MTBF\* (Naval sheltered) Standard ER option MTBF\* (Air inhabited) Standard ER obtion \*MIL-STD-217D (50° C Baseplate)

47-65 Hz 320-480 Hz 115V ac ± 10%  $(5 \text{ V}, \pm 12 \text{ V}; \text{ or } \pm 15 \text{ V})$ 200 kHz 65% minimum 100 mV peak-to-peak max 10 mV (103.5-126.5 V ac) 10 mV main (.5% aux outputs) meets MIL-STD-461B MIL-STD-810C, MIL-S-901C MIL-STD-1399 MIL-STD-704 -55°C to 100°C -20°C to 71°C -55°C to 85°C -65°C to 125°C 99,408 hours 97,935 hours 220,434 hours 375,248 hours 17.632 hours 34,307 hours 14,985 hours 27,012 hours


MBI00T

WHEN RELIABILITY IS IMPERATIVE:

MILITARY POWER SUPPLIES

# EASY AS IBC


Advanced VME industrial I/O capability



VME-Industrial I/O signal interfacing is now a simple matter of "putting it on the bus." Thanks to Acromag's analog and digital cards and termination products for interfacing real world I/O signals.

Field inputs such as thermocouple, RTD, voltage, frequency, strain gauge, pneumatic and many others are directly interfaced via screw type termination products and I/O cards to the VMEbus—as easy as IBC.

The Analog Intelligent Base Card (IBC) simplifies the problem by forming an intelligent base for the analog subsystem collecting and conditioning up to 256 analog signals and



storing all in dual port RAM memory. The IBC and analog I/O cards provide for 14-bit A/D conversion, amplification, isolation, scaling, linearization and limit checking. The IBC card also has a local serial port for calibration, diagnostics and configuration.

And digital I/O? Of course... provided for by a 64 channel 30 volt bi-directional I/O card with or without relay field interfaces using a variety of screw type termination panels.

Acromag's VME cards and termination products provide the broadest industrial I/O capability available. All to make solutions to your industrial I/O needs as easy as IBC.









Acromag, Inc. • 30765 Wixom Rd. • Wixom, MI 48096


To find out more about Acromag's VME Industrial I/O capability and commitment write for Bulletin 20-000.0. Or for immediate help call our telemarketing department at 1-800-ACROMAG or (313) 624-1541.






New superfast signal processor from Texas Instruments keeps transactions strictly private...


# strengthens signals, enhances squelches echoes, and gets you Meet TI's new TMS32020



Echo cancellation can be greatly improved by using new TMS32020 processor, allowing telephone messages to come through loud and clear from anywhere.



**Graphics systems** could be economically implemented with TI's TMS32020 supplying throughput capability required for realtime rotation, scaling, and translation.



**High-speed modems** (4.8K bps to 19.2K bps) can be built with fewer chips and in shorter development time using TI's new TMS32020 processor.

It can handle all your digital signal processing (DSP) better than ever before. And as you will read, TI's new, single-chip TMS32020 can also be an efficient, economical processor for many high-speed, numeric-intensive applications.

And because it is available now, fully supported, the TMS32020 can speed your system development.

Up to three times faster throughput

TI's new TMS32020 processor delivers two to three times the throughput of the industry standard, TI's own TMS32010.

Behind this dramatic increase are (1) an expanded instruction set with repeat feature, (2) an expanded memory capability both on chip and off, and (3) much faster I/O.

Like the TMS32010, the TMS32020 utilizes a modified Harvard architecture emphasizing overall system throughput, communication, and flexibility in processor configuration.

Increased capability and flexibility

Having greater throughput, TI's TMS32020 makes fast work of filtering, correlation, windowing, transforms, wave-form generation, and all your other DSP tasks. 544 words of on-chip RAM, 32-bit arithmetic, single-cycle multiply/accumulate instructions, and an independent auxiliary register arithmetic unit further equip the TMS32020 for realtime DSP systems.

However, the capabilities of the TMS32020 should challenge your imagination. Its 64K word program and 64K data-memory spaces, timer, serial port, multiple-interrupt structure, provision for external wait states, and multiprocessor interface capability make the TMS32020 a natural choice for wide use.

And the TMS32020 is economical. Through VLSI implemen-

tation, the TMS32020 incorporates all these features into a single, 68-pin grid-array package.

Full support shortens development time

A wide range of development hardware and software tools is available to shorten your design cycle. Included are full-speed emulators, software simulators and assemblers/linkers, and application reports, plus other documentation (see box).

Three-day DSP workshops are conducted periodically at TI's Regional Technology Centers, and TI application engineers are also ready to provide help. Extensive third-party support is available.


A TMS32020 applications handbook and additional documentation are only 11 quick keystrokes away, 1-800-232-3200, ext. 3502, or use the coupon on page 4.

Where economy is a prime design consideration and system requirements are less demanding, use TI's industry-standard TMS32010 DSP. An extended temperature range military version is also available.

Top secrets stay top secret when secure-telephony systems (on cover) are designed using Tl's new TMS32020 signal processor. Its vastly improved throughput allows it to perform all critical subroutines so rapidly that deciphering the code is made virtually impossible.

# graphics, to market faster. digital signal processor chip.

TMS32020 provides all ecure-telephony features



Because it can perform several funcions by simply executing a variety of subroutines, Tl's TMS32020 processor is a prime candidate for ecure-telephony applications.


For example, multiple FMS32020s can compress the voice, encrypt the digital signals, and act is a modem.

The fast cycle time of the TMS32020 is not only essential to he encryption/decryption routine out can also allow the routine to be constantly varied so that cracking the code would be difficult.

The large program memory, serial port, and single-cycle multiply/accumulate facilitate the coding, lecoding, and modem routines.

Thus, the TMS32020 is an effective alternative to the costly fully custom circuits you would have to use to gain equivalent processing power.

#### TMS32020 cancels echoes more accurately



For more effective echo cancellation, the 544-word on-chip data memory of TI's TMS32020 enables it to provide larger, more accurate adaptive filters. Because of this memory and the single-cycle multiply/accumulate/data move, the TMS32020 can execute and update a 128-tap adaptive filter needed by the echo-cancellation-model routine. And the extraordinary speed of the TMS32020 allows the adaption routine to execute in real time.

The TMS32020 completes a multiply/accumulate/data move in a single cycle. Its "repeat instruction" allows the next instruction to be repeated "N" times, which saves program memory space and effectively pipelines the instruction.

In addition, the 544 words of on-chip data RAM allow quick updates of taps for faster adaptation, and the serial I/O port allows direct interface to a codec with little or no "glue" logic.

#### TMS32020 excels at fast matrix manipulations



In graphics applications, TI's TMS32020 processor can be used for both numeric and pixel processing. Its 200-ns multiply/accumulate allows the TMS32020 to execute realtime graphics scaling, rotation, and translation. All depend upon memory-intensive matrix manipulations that require rapid execution.


The block-move feature of TI's TMS32020 — up to 80 Mbits per second — allows the large data blocks involved to be accessed in real time to manipulate the screen. The TMS32020 is capable of addressing up to 64K 16-bit words of data used to store the pixel information. Among other features that give the TMS32020 an edge in graphics systems are the scaling shifter used in pixel or bit alignment and the wait states that allow communication with slower DRAMs/VRAMs.

Because a graphics system must interface to a host processor, the host-interface logic on the TMS32020 eases your design task.

#### TMS32020 simplifies high-speed modem design

Using multiple TMS32020 processors in high-speed modems is a logical choice over costly fully custom chips. The TMS32020 com-

bines easy programming with large data memory, multiprocessor and



serial interfaces, overflow mode, large program memory, and table access of program memory.

Since many high-speed modems require more than one programmable DSP chip, the built-in multiprocessing interface of the TMS32020 minimizes component count and simplifies design.

Adaptive FIR filters require the single-cycle multiply/accumulate/ data move and the large data memory of the TMS32020 for high-speed computations and realtime implementation.

The overflow-saturation mode minimizes errors caused by an overflowing accumulator and produces a "clean filter."

Program memory of up to 64K words permits multiple bit rates and standards to be supported simply in software rather than hardware.

For more applications data, call 1-800-232-3200, ext. 3502, or check the coupon on page 4.

Samples of TI's new 32020 are available now through authorized TI distributors, at \$250.\* Volume production is slated for early 1986. Development-support tools are also available off the shelf.

#### TMS32020 Software and Hardware Support

Host Operating Part Computer System Number

Macro Assembler/Linkers
DEC VAX VMS TMDS3241210-08
TI/IBM PC MS-DOS TMDS3241810-02


DEC VAX VMS TMDS3241211-08 TI/IBM PC MS-DOS TMDS3241811-02

Hardware Emulator TMDS3262220

\*Suggested retail, quantity 1, U.S.A.

Turn the page for more information.





High system performance and low-power operation result when four of TI's new 74AS888 8-bit-slice processors are cascaded to form a 32-bit CPU with TI's new, low-power THCT1010 speeding multiplier/accumulator operations.

# TI redefines your idea of speed/power ratios with its new bit-slice/multiplier team.

For many applications requiring exceptional system execution speeds, TI's new 74AS888 8-bit-slice processor can prove the effective alternative to the TMS32020 DSP.

Usually, when you increase system performance significantly, power consumption follows right behind — just as night follows day.

Not so with TI's IMPACT™
74AS888 and new THCT1010
multiplier/accumulator. This team
sends power and performance on
their separate ways. One up . . . the
other down.

Texas Instruments Incorporated

P.O. Box 809066

ADDRESS

AREA CODE

CITY

Dallas Tayas 75380 0066

The innovative 74AS888 has an instruction-to-Y output of 46 ns maximum, or a 51% improvement over the 4-bit competition. Power dissipation is only 1.5 W maximum during operation.

Multiplies and divides are about as fast as additions. Flexible microinstructions let you tailor an application-precise instruction set. You can use any software. Any word length in 8-bit increments. Emulate any known  $\mu P$  instruction set while achieving improvements in execution speeds.

<sup>™</sup> Trademark of Texas Instruments Incorporated 27-5287

Expires June 30, 1986

MAIL STATION

ZIP

EXT.

SPR103ED500C

The 74AS888 is fully supported and readily available through TI distributors so you can get your system design finalized in minimum time.

TI's new THCT1010 is pin-forpin compatible with the industrystandard multiplier (TDC1010J) but consumes 30 times less power. In conjunction with the 74AS888, it can significantly cut the power requirements of bit-slice systems.

Fabricated in silicon-gate CMOS, the THCT1010 is a 16- × 16-bit multiplier with 35-bit accumulator. How fast is it? For the -100 suffix, 100 ns maximum with a worst-case power consumption of only 150 mW.

If you want more details on the 74AS888 and THCT1010, just dial the 800 number below or clip and mail the coupon.

For quick response to your information needs, call Texas Instruments today at 1-800-232-3200.

Dallas, Texas (3300-7000
YES, please send me the information checked below.
PR22 ☐ TMS32020 Applications Handbook PR25 ☐ TMS32020 User's Guide PR12 ☐ TMS32020 Third-party Support PR30 ☐ Digital Signal Processing Newsletter DB01 ☐ IMPACT 74AS888 8-bit-slice Processor Data Sheet and User's Guide CL04 ☐ THCT1010 CMOS Multiplier/Accumulator Data Sheet
NAME
TITLE
COMPANY

STATE

**TELEPHONE** 



Creating useful products and services for you.



## Cutler-Hammer switches deliver 5 amp performance at a 3 amp price.

Conservatively rated at 5 amps, Cutler-Hammer® illuminated pushbuttons deliver long-life dependability—even longer in a 2 or 3 amp load application. Switches can be PC board-mounted or panel mounted with unique clips which snap snugly into a wide range of panel thicknesses.

Plus, each switch is UL recognized, CSA certified and most meet VDE requirements. What's more, every switch is backed by extensive R&D and supported by a solid, service-oriented sales and distributor network.

For more information, contact your Cutler-Hammer Sales Office or Distributor. Or send for our complete catalog. Eaton Corporation, Aerospace & Commercial Controls Division,

4201 N. 27th St., Milwaukee, WI 53216. Or call 414-449-7487.

FAT.N

Aerospace, Commercial, Miniature, Illuminated Switches and Relays.

# Graphicscontroller

Recently introduced graphicscontroller ICs offer faster drawing rates and better screen-refresh capabilities than do earlier models.

The ICs range from simple screen-refresh controllers to highly specialized 32-bit graphics microprocessors.

Steven H Leibson, Southwestern Editor

Recent graphics-controller ICs let you build rastergraphics subsystems that include surprisingly few chips, yet deliver fast drawing speeds previously reached only with bit-slice processors. The ICs also make medium- and low-performance graphics systems easier and less expensive to design and build.

Further, many of these new controllers come with software support for the proposed ANSI Computer Graphics Interface (CGI) standard, which promises standardization at the graphics-driver level for display, hard-copy, and input devices.


Graphics controllers fall roughly into three categories: screen-refresh controllers; fixed-instruction controllers; and application-specific, programmable graphics microprocessors. (High-conversion-rate video D/A converters that work with these different types of controller ICs are listed on pg 116.) Screen-refresh controllers manage CPU access to the screen-buffer RAM, extract display information from the buffer, and direct that information to the CRT-monitor electronics. These controllers also generate CRT

Graphics-controller ICs offer a variety of approaches to graphics-system design. One chip set, for instance, allows you to approach the construction of a graphics  $\mu P$  in a modular fashion. The set—to be available this spring—includes a raster-graphics processor (which acts as the set's master chip), a BitBlt processing unit, a video clock generator, and a video shift register. For maximum performance, a separate BitBlt processor would manage each memory plane. (Photo courtesy National Semiconductor)





Any graphics controller that performs screen refresh without the aid of a video RAM cannot draw and refresh at the same time.



Results of several PixBlt operations combining the letter A and X appear in this screen photo from Texas Instruments' MS-DOS TMS34010 simulator. The results of the operations are, from left to right (top), replacement with transparency off, replacement with transparency on, and maximum. From left to right (bottom), the results are minimum, AND, and Exclusive OR.

control signals: horizontal and vertical or composite sync and blanking. In designs using screen-refresh controllers, the CPU places the information into the screen buffer (in other words, it draws the picture). Designs using screen-refresh controllers can be inexpensive, but they won't offer very high performance levels because of the great burden they place on the CPU.

An example of a simple screen-refresh controller is the 6845 NMOS CRT controller from Motorola. IBM uses the device in both the monochrome display and color graphics adapters for the IBM PC family of computers. The 6845 is a character-oriented controller that supports programmable screen formats, including the number of characters displayed both horizontally and vertically, the length of the vertical-retrace period, the width and position of the horizontal sync pulse, and interlace mode. The controller has no onboard character generator.


Although the 6845 is character oriented, you can use it as a screen-timing generator for both character and bit-mapped graphics displays. You can use the 6845's timing signals to drive any screen-buffer architecture. Motorola, Hitachi, VLSI Technology, and Gould AMI

offer several NMOS and CMOS versions of the 6845. Both Gould AMI and VLSI Technology offer 6845 macrocells for incorporation into custom IC designs. Fujitsu recently introduced enhanced 6845 designs in CMOS. The company's MB89321 is pin compatible with the 6845; its MB89322 has the same internal architecture, but it has an Intel-type bus interface instead of the 6845's Motorola-type interface. Both parts feature an enhanced, smooth scroll with as many as four independently scrollable screen partitions.

#### IBM PC-compatible controllers

Specialized screen-refresh controllers for the IBM PC and compatible computers are available from two companies, Chips and Technologies and Tseng Laboratories. The chip sets are compatible with IBM's enhanced graphics adapter card. Chips and Technologies' enhanced graphics chip set comprises the 82C431 graphics controller, the 82C432 sequencer, the 82C433 attributes controller, and the 82C434 CRT controller. These four ICs reduce the chip count of a design compatible with IBM's enhanced graphics adapter from 76 to 32 devices. The chip set supports the IBM PC monochrome display adapter, and it can emulate the Hercules monochrome graphics adapter card.

Tseng Laboratories' ET2000 CRT controller, ET2001 attribute controller, and ET2002 graphics data controller make up a 3-chip set that supports the three screen resolutions ( $320\times200$ ,  $640\times200$ , and  $640\times350$  pixels) available with the enhanced graphics adapter. It also supports the additional  $640\times480$ -pixel screen format




A video-RAM-compatible graphics controller and video RAMs can reduce board real estate tremendously while increasing maximum screen resolution, as you can see from this comparison of an older, 2-board graphics-board set for Texas Instruments' TI PC bus with the video-system-controller evaluation module.

available with the IBM Professional graphics controller and the 80-character×25-line screen format of the IBM PC monochrome display adapter. You can build a higher-resolution (1280×1024-pixel) design with one ET2000, one ET2002, and four ET2001s. The company is planning to add a fourth chip to the series: The ET2003 bit-slice controller, for higher-performance subsystems, will be compatible with IBM's Professional graphics controller.

#### Screen-refresh controllers for bit maps

A screen-refresh controller that specifically addresses bit-mapped graphics is Motorola's raster-memory system, which comprises the MC68486 raster memory interface and the MC68487 raster memory controller. The MC68486 supports from 16k to 1M bytes of screen-buffer RAM. It contains the  $\mu P$ -bus interface, generates system clocks and  $\overline{RAS}$  and  $\overline{CAS}$  signals for dynamic RAMs, and works in both interlaced and noninterlaced modes.

The MC68487 takes information from the screen buffer and converts it to the video signals needed to drive a display. It supports displays whose resolution is as high as 640×400 pixels for NTSC signals and 640×500 pixels for pal (the French equivalent of NTSC) signals. In character mode, the MC68487 can display as many as 50 rows of 80 characters. The device contains ASCII and block graphics characters in ROM and supports as many as 32,000 user-definable characters. An internal color map allows 32 colors (from a palette of 4096) to appear on the red, green, and blue analog



Suitable for high-performance applications, this 32-bit, programmable graphics microprocessor, the TMS34010 from Texas Instruments, features a highly parallel architecture, an on-chip instruction cache, and a pixel-block-transfer (PixBlt) raster engine.

outputs. The video outputs have  $100-k\Omega$  output impedance, so you must buffer them externally to drive low-impedance displays.

Texas Instruments' TMS34061 video-system controller directly supports 64k-bit video RAMs and display resolutions as high as 4096×4096 pixels. The TMS34061 acts as both a dynamic-RAM controller and a screen-refresh controller: It generates multiplexed addresses, RAS and CAS signals, the shift-register transfer-

MANUFACTURER	MODEL	NUMBER OF ADDRESS BITS MANAGED (OR ADDRESS SPACE)	NUMBER OF ON-CHIP CHARACTERS	PRICE (QUANTITY)	ALTERNATE SOURCES/NOTES
FUJITSU	MB89321 MB89322	14 14	0	\$4.03 (10,000) \$4.03 (10,000)	PIN COMPATIBLE WITH 6845 REGISTER COMPATIBLE WITH 6845, INTEL- STYLE BUS INTERFACE
MOTOROLA	6845	14	0	\$6.21 (100)	HITACHI, GOULD AMI, VLSI TECHNOLOGY
SIGNETICS	SAA5350	128k BYTES	512	\$31.59 (100)	CEPT VIDEOTEX A4 TERMINAL CONTROLLER
SMC	CRT9028 CRT9128	2k BYTES 2k BYTES	128 PLUS TWO GRAPHIC SETS	\$22.20 (100) \$22.20 (100)	GENERAL INSTRUMENT, INTEL-STYLE BUS INTERFACE GENERAL INSTRUMENT, MOTOROLA-STYLE BUS INTERFACE
TEXAS INSTRUMENTS	TMS9118A/ TMS9128A/ TMS9129A	16k BYTES	0	\$20.15 (100)	USED IN MSX COMPUTERS
THOMSON-CSF	EF9345	16k	256	\$4 (10,000)	>1000 USER-DEFINABLE CHARACTERS

#### Video RAMs suit high-performance displays

When they're used as screen buffers for character-oriented displays, where screen manipulation involves only a few thousand bytes, conventional (singleported) RAMs don't present much of a limitation to system performance. However, bitmapped displays with resolutions exceeding 1024×1024 pixels have screen buffers of several hundred thousand or millions of bytes, and the limited bandwidth of single-ported RAMs severely degrades the performance of these systems. For high-performance displays, which have large bandwidth requirements for both screen manipulation and screen refresh, you need to use video RAMs.

A video RAM is a 2-port memory device with an internal RAM array and a shift register. One port looks like a conventional dynamic RAM, with multiplexed addresses and RAS and

CAS signals. The other port is serial, coupled to the internal shift register. In one clock, 256 bits (for a 64k-bit video RAM) or 1024 bits (for a 256k-bit video RAM) of data are transferred from the RAM array to the shifter. The serial port then doesn't need the array until the screen-refresh process has used all of the data from the shifter.

Since their introduction a little over a year ago, when Texas Instruments produced the 64k-bit TMS4161, video RAMs have had significant impact on high-performance graphics design. At present, AMD, NEC, and Fujitsu are making 256k-bit video RAMs; TI will soon introduce a 256k-bit device as well. Because the video RAMs have serial ports, they're also finding application in disk, tape, and LAN controllers.

AT&T Technologies' 64k-bit video RAM, the M51064PX, is

pin compatible with the TMS4161, although AT&T is not an official alternate source for the TI part. Further, all the 256k-bit video RAMs are pincompatible, 64k×4-bit designs; however, the NEC µPD41264 offers fewer features than do the other parts listed.

The 256k-bit video RAMs feature bidirectional transfer between the video RAM's shift. register and RAM array: you can use this bidirectional transfer for rapid screen clearing and for patterns. In addition, the parts offer maskable write. which lets you use each of a video RAM's four data-signal lines as a separate bit plane, as well as for individual pixel manipulation. You can use the shiftregister input for register loading, and you can start shifting at any point in the 256-bit shift register.

#### **VIDEO RAMS**

MANUFACTURER	MODEL	RAM-ARRAY CONFIGURATION (BITS)	SHIFTER CONFIGURATION (BITS)	ACCESS TIME (nSEC)	SHIFT RATE (MHz)	PACKAGE	PRICE (QUANTITY)
64k-BIT VIDEO RA	Ms						
AT&T TECHNOLOGIES	M51064PX-20 M51064PX-15	64k×1 64k×1	256×1 256×1	200 150	16.7 20	20-PIN DIP 20-PIN DIP	\$5 (1000)
TEXAS INSTRUMENTS	TMS4161-20 TMS4161-15	64k×1 64k×1	256×1 256×1	200 150	20 22	20-PIN DIP AND 22-LEAD PLCC	\$3.20 (100)
256k-BIT VIDEO RA	AMs						
AMD	Am90C644	64k×4	256×4	100	25	24-PIN, 400-MIL DIP	\$10 (1000)
FUJITSU	MB81461-15P MB81461-12P	64k×4 64k×4	256×4 256×4	150 120	16.7 25	24-PIN, 400-MIL DIP AND 24-PIN SIP	\$10.75 (10,000) \$13 (10,000)
NEC	μPD41264-15 μPD41264-12	64k×4 64k×4	256×4 256×4	150 120	16.7 25	24-PIN, 400-MIL DIP 24-PIN, 400-MIL DIP	\$6.90 (100)
TEXAS INSTRUMENTS	TMX4461	64k×4	256×4	120	30	24-PIN, 400-MIL DIP	
HYBRID SIP VIDEO	RAMs						
TEXAS INSTRUMENTS	TMS4161EV4 TMS4161EP5 TMS4161GW4 TMS4161GY4	64k×4 64k×5 64k×4 64k×4	256 × 4 256 × 5 256 × 4 256 × 4	200/150 200/150	20/22 20/22 20/22 20/22	31-LEAD SIP 35-LEAD SIP 30-PAD LEADLESS SIP 30-LEAD SIP	\$24 (100) \$27.20 (100) \$24 (100) \$24 (100)

\*SAMPLES AVAILABLE

An instruction cache accelerates graphicsalgorithm execution by capturing loops of instructions.

control signals needed by the video RAMs, and video sync and blank signals. Because screen refresh from video RAMs does not require much RAM bandwidth—and because the TMS34061 performs this screen refresh automatically—you can use one TMS34061 to control both screen-buffer video RAMs and main-system dynamic RAMs. The TMS34061 accepts an 18-bit address from the host CPU and directly drives 64 RAMs. Because the RAM data bus doesn't pass through the TMS34061, the data path between the CPU and memory can be of any width.


The video-system controller supports both linear and XY-indirect addressing. In the linear-addressing mode, the address presented to the TMS34061 selects a RAM location. This mode is useful primarily in 16- and 32-bit  $\mu P$  systems, which can support the large memory space that a high-resolution screen buffer requires. The XY-indirect addressing mode is useful in systems with 8-bit  $\mu Ps$ , which can't support large screen buffers directly. When it operates in the XY-indirect addressing mode, the TMS34061 uses an internally generated 20-bit address to select a RAM location. A programmable automatic increment of the XY-addressing registers supports line-drawing algorithms, so the XY-indirect addressing feature is useful with all CPU types.

An evaluation module for the TMS34061 (the TMDX3471800000) is bus compatible with the IBM PC and the TI PC; it costs \$995. The board, which can display a 1024×512-pixel screen, includes a TMS34061 configured with three planes of video RAM. Sockets on the board allow you to add a fourth plane by plugging in eight additional video RAMs.

Another bit-mapped screen-refresh controller is the 82716 video storage and display device from Intel and Matra-Harris, which developed the product jointly. The 82716 has a 512k-byte address space and supports displays that have resolutions as high as  $640 \times 512$  pixels. You can represent each pixel with two, four, or eight bits (the 8-bit mode is available only for 320-pixel-wide screens). A 16-word color map drives three onboard 4-bit D/A converters, allowing you to display 16 colors from a palette of 4096.

The 82716 directly drives RAM arrays and generates multiplexed addresses and RAS and CAS signals. Standard dynamic RAMs are used for the bit map; the controller generates no transfer or shift control signals for video RAMs. The screen buffer is configured as a 16-bit wide array, and the 82716 offers an 8- or 16-bit interface to the host processor.

A key feature of the 82716 is its window-management




Graphics, screen-refresh, and RAM-refresh controllers are combined on the Hitachi HD63484 Advanced CRT controller IC.

scheme. The controller treats windows as objects; it can manage as many as 16 of them. The size and position of each window are determined by two tables: one 512-word access table for all objects and one 8-byte, object-descriptor table for each object displayed. You can program each window to be either bit mapped or character oriented. You control window movement and manipulate window size by altering entries in the relevant tables, a relatively quick operation.

#### Fixed-instruction controllers

For applications that require higher performance graphics or that must relieve the CPU of graphics tasks, you'll need to use a graphics controller that can manipulate the bit map without CPU intervention. One kind of controller that can perform this task is a fixed-instruction graphics controller, whose fixed instruction sets comprise commands for line and arc drawing.

NEC introduced the first single-chip, fixed-instruction graphics controller, the μPD7220 graphics-display controller. The μPD7220, which is now also offered by Standard Microsystems Corp, Zilog, and Intel, includes screen-refresh, dynamic-RAM refresh, and graphics-



This 4-chip graphics controller from Chips and Technologies forms the core of a board design that's compatible with the IBM enhanced graphics adapter.

drawing controllers, as well as a light-pen interface.

The  $\mu$ PD7220's commands include line, arc, rectangle, and graphics-character drawing, which transfers an  $8\times8$ -pixel character to designated screen areas and can be used for area fill. Zoom and pan are also supported. NEC's fastest graphics-display controller, the 7220AD-2, clocks at 8 MHz and can draw at 500 nsec/pixel.

A problem with the 7220, as with any graphics controller that refreshes the screen without the aid of a video RAM, is that it can't draw and refresh at the same time. If you allow the graphics controller to draw while the controller is refreshing the screen, snow will appear on the screen when a memory-write cycle (part of the drawing operation) takes the place of the normally scheduled screen-refresh read cycle. One way to prevent snow would be to program the 7220 to draw only during the horizontal and vertical blanking intervals, but the penalty is a severe reduction in drawing speed.

To avoid both snow and slow drawing speed, you could use a screen-refresh controller like the 6845 to relieve the 7220 of its screen-refresh duties. To implement this scheme, you'd use the 7220's external-sync input to synchronize the 7220 with the 6845. This arrangement would require you to use fast RAMs, so you could interleave the drawing cycles and the screen-refresh cycles without extending the overall access time for screen refresh.

However, the main difficulty with this technique is that it requires you to build complex circuitry to detect the 7220's uninterruptible, read-modify-write drawing cycle (which can occur at any time) and postpone the 6845's read cycle until the 7220's cycle is complete.

To overcome this draw-vs-display conflict, Hitachi uses an interleaved memory-access mode in its HD63484-8 advanced CRT controller. A 1000-nsec (at 8 MHz) display/drawing cycle in the interleaved mode provides separate memory cycles for the screen-refresh and drawing tasks. A disadvantage of the interleaved mode is that, for a given screen configuration, the memory-access speed must be twice the speed required by the noninterleaved, single-access mode.

The HD63484-8 controller lets you use 38 drawing commands, including line, rectangle, polyline, polygon, circle, ellipse, arc, ellipse arc, filled rectangle, paint, and pattern. It supports as many as 2M bytes of screen memory with one, two, four, eight, or 16 bits per pixel. The controller also supports a separate 128k-byte character memory space, three split screens, and one window. Signetics will act as an alternate source for the part.

AMD's Am95C60 quad pixel data-flow manager is a

MANUFACTURER	MODEL	NUMBER OF ADDRESS BITS MANAGED (OR ADDRESS SPACE)	MAXIMUM SCREEN RESOLUTION (PIXELS)	NUMBER OF BITS OR PLANES PER PIXEL	PRICE (QUANTITY)	ALTERNATE SOURCES/NOTES
AMD	Am8150	18 BITS	N/A	N/A	\$46 (100)	
CHIPS AND TECHNOLOGIES	EGA CHIPSET	256k BYTES	720×350	4	\$85.40/SET (100)	IBM EGA-COMPATIBLE, 4-CHIP SET
NTEL	82716	512k BYTES	640×512	2, 4, OR 8	\$19.95 (10,000)	MATRA-HARRIS
MOTOROLA	MC68486/ MC68487	1M BYTE	640×500 (PAL) 640×400 (NTSC)	1, 2, OR 4	\$20.45 (10,000)	
TEXAS NSTRUMENTS	TMS34061	18 BITS	4096×4096	N/A	\$35.50 (100)	
TSENG LABORATORIES	ET2000 SERIES	256k BYTES/PLANE	1280×1024	8	\$75 PER SET (10,000)	IBM EGA-COMPATIBLE, 3-CHIP SET

Screen-refresh controllers manage CPU access to the screen-buffer RAM, extract display information from the buffer, and direct the information to the CRT.

fixed-instruction graphics controller that takes advantage of video RAMs. One QPDM controls as many as four planes, accessed 16 bits at a time, and supports screen resolutions as high as 4096×4096 pixels. The Am95C60 generates multiplexed addresses and the RAS and CAS signals needed for dynamic-RAM support, as well as the transfer signal needed for video-RAM control.

By controlling four planes with one chip, AMD implemented an antialiasing algorithm in the Am95C60. The controller performs line smoothing through two or four levels of shading. The Am95C60's 60-instruction command set includes line draw, block move, and area fill. Internally, the Am95C60 is a 16-bit machine, but it supports both 8- and 16-bit interfaces to the host CPU.

The X1001/1002 graphics microprocessor chip set from XTAR Electronics has a display-list architecture. Instead of passing individual drawing instructions to the chip, the CPU interacts with the X1001/1002 by sharing a 128k-byte display-list buffer that's separate from the screen buffer. Using the X1001/1002's display-list-descriptor instruction set, the CPU builds a description (in the buffer) of the picture to be drawn. It then activates the X1001/1002, which runs through the description, executing the instructions, and drawing the picture in a separate frame buffer. The display-list buffer can hold several display lists; if you use an interleaved-access buffer, the host CPU can create a new display list while the X1001/1002 draws from a different, completed list.

The X1001/1002 has no screen-refresh capabilities; you can use either dynamic RAMs or video RAMs as

the screen buffer and design your own screen-refresh circuitry. The company incorporates a 6845 screen-refresh controller in its \$2195 EVA 1000S evaluation module, however. An IBM PC-compatible video-display board, the PG1000E, costs \$3500 and includes a display-list editor; polygon, dither/transparency, and color-palette editors; an assembler; a disassembler; a debugger; and DOS-compatible text drivers.

You can expect several companies to introduce other dedicated graphics microprocessors in 1986. Unlike the X1001/1002, which has a specialized instruction set for drawing, these newer graphics  $\mu$ Ps will have general-purpose instruction sets with graphics enhancements in both instruction sets and hardware support.

These high-end machines will employ bit-block transfers (BitBlts) as an efficient means of manipulating the bit map. A BitBlt, which is also called a raster operation (rasterOp), is a primitive graphics operation that takes two rectangular regions of pixels (source and destination), performs a pixel-by-pixel Boolean operation on these blocks, and then writes the resulting block back to the destination.

Because of the BitBlt's Boolean nature, it's mainly suitable for monochrome (one bit per pixel) displays. Texas Instruments has extended the BitBlt operation for multiplane color and gray-scale designs in its TMS34010 graphics system processor by adding arithmetic operations. The company calls the extended function the pixel block transfer (PixBlt).

The TMS34010 (samples of which will be available this month) is based on a 6-MIPS, 32-bit microprocessor core that's like a reduced-instruction-set computer. The

A DESCRIPTION AND STATE OF THE											
MANUFACTURER	MODEL	NUMBER OF ADDRESS BITS MANAGED (OR ADDRESS SPACE)	MAXIMUM SCREEN RESOLUTION (PIXELS)	NUMBER OF BITS OR PLANES PER PIXEL	NUMBER OF COMMANDS	PRICE (QUANTITY)	ALTERNATE SOURCES/ NOTES				
AMD	Am95C60	2M BYTES/PLANE	4096×4096	4/95C60	60	· Comment					
HITACHI	HD63484-8	2M BYTES BIT MAP PLUS 128k BYTES TEXT	4096 × 4096 (AT 1 BIT/PIXEL)	1, 2, 4, 8, OR 16	38	\$38.50 (1000)	SIGNETICS				
NCR	7300/7301	1M BYTE	1024×1024	2/7301, 8 MAX	25	<\$80 (10,000) FOR ONE 7300 AND TWO 7301s					
NEC	7220	512k BYTES	2048×2048 (AT 1 BIT/PIXEL)	1 TO 16	18	\$37.50 (100)	INTEL, SMC, ZILOG				
THOMSON-CSF	EF9367	64k BYTES/PLANE	1024×512	DETERMINED EXTERNALLY	18	\$12 (10,000)					
	EF68483	4M BYTES	2048×2048	4 OR 8	18	**					

For applications that require higher performance graphics, you'll need a graphics controller that can manipulate the bit map without CPU intervention.

#### Manufacturers of graphics ICs

For more information on graphics-controller ICs such as the products discussed in this article, circle the appropriate numbers on the Information Retrieval Service card or contact the following manufacturers directly.

Advanced Micro Devices 901 Thompson Pl Sunnyvale, CA 94088 (408) 732-2400 Circle No 678

Analog Devices Inc Computer Labs Div Box 280 Norwood, MA 02062 (617) 329-4700 Circle No 679

Analogic Corp Audubon Rd Wakefield, MA 01880 (617) 246-0300 Circle No 680

AT&T Technologies Inc 1 Oak Way, Room 2WC-106 Berkeley Heights, NJ 07922 (800) 372-2447 Circle No 681

Brooktree Corp 11175 Flintkote Ave, Bldg F San Diego, CA 92121 (619) 452-7580 Circle No 682

Chips and Technologies Inc 521 Cottonwood Dr Milpitas, CA 95035 (408) 434-0600 Circle No 683

Ferranti Electric Inc 87 Modular Ave Commack, NY 11725 (516) 543-0200 Circle No 684

Fujitsu Microelectronics Inc Integrated Circuits Div 3320 Scott Blvd Santa Clara, CA 95054 (408) 727-1700 Circle No 685 General Instrument Corp Microelectronics Div 600 W John St Hicksville, NY 11802 (516) 733-3120 Circle No 686

Gould AMI Semiconductors 3800 Homestead Rd Santa Clara, CA 95051 (408) 246-0330 Circle No 687

Hitachi America Ltd 2210 O'Toole Ave San Jose, CA 95131 (408) 942-1500 Circle No 688

Honeywell Inc Signal Processing Technologies 1150 E Cheyenne Mountain Blvd Colorado Springs, CO 80906 (303) 577-1000 Circle No 689

Inmos Corp Box 16000 Colorado Springs, CO 80935 (303) 630-4000 Circle No 690

Intech Microcircuits Div 2270 Martin Ave Santa Clara, CA 95050 (408) 988-4930 Circle No 691

Intel Corp 3065 Bowers Ave Santa Clara, CA 95051 (408) 987-8080 Circle No 692

Matra-Harris Semiconducteurs BP 942 La Chantrerie, Route de Gachet 44075 Nantes Cedex France (40) 303030 Circle No 693 Motorola Semiconductor Products Inc Box 20912 Phoenix AZ 85036

Phoenix, AZ 85036 (602) 962-2252 Circle No 694

National Semiconductor 2900 Semiconductor Dr M/S 16-197 Santa Clara, CA 95051 (408) 721-5943 Circle No 695

NCR Corp Microelectronics Div 1635 Aeroplaza Dr Colorado Springs, CO 80916 (303) 596-5612 Circle No 696

NEC Electronics Inc Box 7241 Mountain View, CA 94039 (415) 960-6000 Circle No 697

Pacific Mountain Research Inc 8026 35th Ave NE Seattle, WA 98115 (206) 524-0910 Circle No 698

Signetics Corp Box 3409 Sunnyvale, CA 94088 (408) 739-7700 Circle No 699

Silicon Compilers Inc 2045 Hamilton Ave San Jose, CA 95125 (408) 371-2900 Circle No 700

Standard Microsystems Corp 35 Marcus Blvd Hauppauge, NY 11788 (516) 273-3100 Circle No 701 Telmos Inc 740 Kifer Rd Sunnyvale, CA 94086 (408) 732-4882 Circle No 702

Texas Instruments Inc Box 1443 Houston, TX 77001 (713) 490-2000 Circle No 703

Thomson-CSF Components Corp 301 Rte 17 N Rutherford, NJ 07070 (201) 438-2300 Circle No 704

Tseng Laboratories Inc 205 Pheasant Run Newtown Commons, PA 18940 (215) 968-0502 Circle No 705

TRW Electronic Components Group LSI Products Div Box 2472 La Jolla, CA 92038 (619) 457-1000 Circle No 706

VLSI Technology Inc 1109 McKay Dr San Jose, CA 95131 (408) 434-3000 Circle No 707

XTAR Electronics Inc 2262 Landmeier Rd Elk Grove, IL 60007 (312) 364-4111 Circle No 708

Zilog 1315 Dell Ave Campbell, CA 95008 (408) 370-8000 Circle No 709

1-chip TMS34010 incorporates a barrel shifter for high-speed bit rotations, and it includes a rasterOp engine, a CRT timing controller, and a video-RAM controller. Local memory can be any combination of video RAM, dynamic RAM, other RAM, and ROM.

A 256-byte instruction cache is also on chip. The cache accelerates graphics-algorithm execution by capturing loops of instructions. Once a particular instruc-

tion loop is captured, memory cycles for instruction fetches within the loop cease, and loop execution is faster, because the TMS34010 can access instruction cache, internal register file, and external memory simultaneously, instead of sequentially. The 256 bytes can hold 128 instructions—an ample capacity for most algorithms.

You can use multiple TMS34010s in your applications

# 11-Bit Flash Converter

### MPS Single Chip ... vs. ... Other's Hybrids



# Compare power, price, reliability, space, LCC packaging, and specs.

Stop spending hundreds of dollars on large, complex 10-and 12-bit hybrid flash converters. Now you can benefit from the world's only, one-chip 11-bit flash. Not only does the MP7685 out perform the hybrids, but it's available to full mil specs and with LCC packaging. Two devices in series provide 12-bit resolution and 2 devices in parallel double the throughput rate to 4MHz.

Micro Power's line of flashes can satisfy all of your design requirements. Check these out: 11-bit MP7685 (2MHz speed,  $\pm 1/2$  bit accuracy), 8-bit MP7684 (20MHz speed,  $\pm 1/2$  bit accuracy), 8-bit MP7683 (10MHz speed,  $\pm 1/2$  bit accuracy), 6-bit MP7682 (30MHz speed,  $\pm 1/4$  bit accuracy).

Micro Power's proprietary bulk silicon molybdenum gate CMOS converters provide high performance and powerful solutions for flash applications. These devices meet commercial, industrial, and military temperature ranges. All are available with MIL-STD-883 processing, and are CMOS microprocessor compatible.



Samples, data sheets, applications boards and applications support are immediately available. Send the coupon or phone your local representative or distributor. MPS is the leader in data acquisition ICs, refractory gate MOS technology, and now flash converters.



3100 Alfred Street Santa Ctara, CA 9505/ (408) 727-5350

To: <b>Micro Power Systems,</b> 3100 Alfred St., Santa Clara.  Send Flash Converter data Have Applications Er	
Application:	
Estimated Yearly Usage:	<u> </u>
Name/Title	
Company	rike.
Address	
City State	Zip
Phone	EDN 2•6•86

A fixed-instruction graphics controller can manipulate the bit map without intervention from the CPU.

(for instance, by running several slave TMS34010s from one master). Multiple TMS34010s would suit an application like gun processing, in which each of the three CRT color guns has its own graphics processor.

The TMS34010 supports both linear and XY addressing modes. Linear addressing (the type of addressing available in most general-purpose  $\mu Ps$ ) is useful for program execution and management of data structures; XY addressing is better for screen and window clipping and other screen-management functions. The TMS34010's 32-bit address architecture can access 4G bits, because the architecture of the part supports bit addressing. The TMS34010 package doesn't bring out the two high-order bits, so the address range is limited to 1G bit.

Fabricated in 1.8-µm CMOS, the TMS34010 graphics microprocessor incorporates 160,000 to 180,000 transistors and dissipates 250 mW at its full rated speed (6 MIPS). Samples cost approximately \$500; the company expects to have the part in full production late this year. TI is also planning a line of software-development and -support products for the TMS34010: The products will include low-level, assembly-language tools, a C compiler with a run-time support package, a function library, and support of the CGI standard. You'll be able to select MS-DOS, VMS, Berkeley 4.2 Unix, or Unix System V as the operating system. A software simulator for computers running MS-DOS, as well as a hardware emulator, will also be available.

Motorola plans to introduce a 32-bit graphics microprocessor in the second half of this year. The 68490 raster-graphics display processor is based on a 68000  $\mu$ P core, but it doesn't support the full 68000 instruction set. Coupled to the processor is a raster engine capable of performing all 16 Boolean operations of a 2-operand rasterOp (source, destination) and all 256 operations of a 3-operand rasterOp (source, mask, destination). The company has not yet determined pricing for the part.

The 68490 supports video RAMs and screen sizes of as much as 1280×1024 pixels with a 16M-bit/plane address space. Without extra hardware, the 68490 can control as many as eight planes. The 68490 doesn't have a built-in screen-refresh controller, so you'll have to include one (such as the 6845) in your subsystem design.

The processor's local memory can comprise any mixture of video RAM, conventional RAM, and ROM. The 68490 has a dual-bus architecture; a host bus interfaces a CPU or DMA controller to the processor. Commands

and instructions pass over this bus and through the 68490 into local graphics memory. A program executing in the 68490's local memory then interprets the instructions. You can use the 68490 processor to implement the proposed CGI standard.

This spring, National Semiconductor will introduce its advanced graphics chip set. Comprising the DP8500 raster-graphics processor, DP8510 BitBlt processing unit, DP8512 video clock generator, and DP8515 video shift register, the chip set will allow you to approach the construction of a graphics  $\mu P$  in a modular fashion. The DP8500 and DP8510 are both fabricated in 2- $\mu m$  CMOS and clock at 20 MHz max. The DP8515, which is fabricated in National's recently announced bipolar/CMOS process, runs as fast as 200 MHz.

The DP8500 is the master chip in the set; it processes instructions from local memory and controls multiple DP8510s. The DP8500 has a 32-bit internal address bus, but, because of pin limitations, it has an external 28-bit address and supports a maximum screen resolution of  $16k \times 16k$  pixels. The DP8500 has a general-purpose microprocessor core with a full complement of arithmetic and Boolean instructions, and it supports both dynamic RAMs and video RAMs. The DP8500 and its host CPU communicate through shared RAM.

In a maximum-performance configuration of the chip set, each bit plane would be managed by its own DP8510, which contains a rasterOp engine and a barrel shifter. This configuration would support both pixel architecture (manipulation of one bit/plane to the full pixel depth) and plane architecture (manipulation of several adjacent bits in a single plane simultaneously), and you could switch from one orientation to the other from within your program. You could design an architecture that multiplexes one DP8510 over all bit planes, and you could also use the DP8510 as a graphics accelerator for a general-purpose  $\mu P$  even if you had no DP8500 in the system.

The DP8500 is the system address generator; the DP8510s manipulate bit plane data. Allocating a rasterOp processor and barrel shifter to each plane gives the chip set a performance edge over competing single-chip architectures, the company claims.

The DP8512 generates system timing. Although you can use any number of DP8510s in the advanced graphics chip set architecture, the company specifies that both the DP8512 and DP8500 can drive a maximum of eight DP8510s directly. To drive more DP8510s, you would need buffers. An 8-plane system would include one DP8500, one DP8512, and eight DP8510s; these 10

## OMIBYTE

#### Multibus\* Products

(IEEE 796)

Here's how our 8 plus years of experience saves you time and money: time because we have already designed and built these state-of-the-art boards for your high performance needs; money because we spread design/debug/testing costs over thousands of units. Call Peter Czuchra, Marketing Manager, to discuss how our high quality, high reliability boards will save you time and money on your next application.




OMNIBYTE CORPORATION 245 W. Roosevelt Rd. West Chicago, IL 60185-3790

(312) 231-6880 Intl. Telex: 210070 MAGEX UR

A Look at Today... A Vision of Tomorrow \*Multibus is a trademark of Intel Corp.

Circle no. 1 on reader service card.



#### OB68K1A™ MULTIBUS SINGLE BOARD COMPUTER

- 10MHz 68000 16/32 bit CPU 32K/128K/512K of zero-wait-state dual-ported RAM
- Up to 192K bytes of EPROM
- (2) RS-232C serial ports (2) 16-bit parallel ports A triple 16-bit timer/counter
- (7) prioritized-vectored interrupts
- Omnibyte two year limited warranty

Circle no. 2 on reader service card




#### OB68K/MSBC1™ MULTIBUS SINGLE BOARD COMPUTER

- 12.5MHz 68000 16/32 bit CPU (other speeds and 68010 optional) 256K/512K/1M/2M bytes dual-
- ported; zero-wait-state RAM w/parity (4) RS-232C serial Synchronous/
- Asynchronous multiprotocol I/O ports
- (1) iSBX\* expansion connector (4) 28 Pin ROM sockets (up to
- Optional memory management
- Omnibyte two year limited warranty

\*iSBX is a trademark of Intel Corp.


Circle no. 3 on reader service card



#### OB68K/MMU™ MULTIBUS CPU BOARD WITH OPTIONAL MEMORY MANAGEMENT

- 10MHz 68010 16/32 bit CPU
- Up to (4) 68451 Memory Management Units (optional)
- High speed iLBX\* memory port 8 channel DMA port
- (2) RS-232C serial ports
- 4K/16K bytes of RAM (2) 28-pin ROM sockets
- Omnibyte two year limited warranty
- \*iLBX is a trademark of Intel Corp.


Circle no. 4 on reader service card.



### OB68K/OCTAL™ MULTIBUS SERIAL I/O BOARD

- (8) RS-232C or RS-422 serial I/O ports
- Individually programmable baud rates between 50 and 38.4K baud
- (4) 68681 DUART chips
- (4) Multi-function programmable 16-bit counter/timers
- Omnibyte two year limited warranty


Circle no. 5 on reader service card.



#### OB68K230™ **MULTIBUS 96-BIT PARALLEL** I/O TIMER BOARD


- 96 bits of software definable parallel I/O
- (4) 68230 PI/T chips
- (4) 24 bit timers 35 sq. in. of prototyping area
- Omnibyte two year limited warranty

Circle no. 6 on reader service card.



#### OB68K/INT(P)™ MULTIBUS HOST ADAPTER/ PARALLEL I/O BOARD


- 48 bits of software definable parallel, I/O
- Real time calendar clock w/battery back up
- (4) 68230 PI/T chips 15 sq. in. of prototyping area
- Parallel printer port
- SASI\* interface to disk controller
- Omnibyte two year limited warranty



#### OB68K/INT(S)™ MULTIBUS HOST ADAPTER/ SERIAL I/O BOARD

- 68230 PI/T chips 68681 DUART chips
- (4) RS-232C or RS-422 serial I/O
- ports SASI interface to disk controller
- Parallel printer port
- Real time calendar clock with battery back up
- Omnibyte two year limited warranty

Circle no. 8 on reader service card.



### OB68K/SYSII™ TARGET DEVELOPMENT SYSTEM

- 10/12.5MHz 68000/68010 w/512KB RAM
  - 6-8 serial I/O ports

  - 2-4 16-bit parallel ports
    12 slot Multibus card cage
    32/53/85/90/234/378/500 MB Winchester hard disk drive
  - 100 MB streaming tape
- Diagnostic front panel
- 1.6 Mb floppy disk drive
   Software available includes ldris\*, polyFORTH/32\*\* and more
   \*Idris is a trademark of Whitesmiths, Ltd.
   \*\*polyFORTH/32 is a trademark of Forth, Inc.
- Circle no. 9 on reader service card

\*SASI is a trademark of Shugart Associates. Circle no. 7 on reader service card. A fixed-instruction graphics controller can manipulate the bit map without intervention from the CPU.

chips would cost about \$500. The DP8500 alone costs approximately \$200.

The maximum specified pixel clock rate for the DP8512 is 200 MHz. Because that rate outstrips all video-RAM shift rates, National adds a video shift register (the DP8515) to the chip set. A 4-word×16-bit FIFO buffer in the shift register allows for some delay

in the video-RAM shifter outputs. This FIFO buffer would be useful in designs that route bit-plane outputs over a backplane to an analog card, the company speculates.

Article Interest Quotient (Circle One) High 470 Medium 471 Low 472

MANUFACTURER	MODEL	RESOLUTION (BITS)	THROUGHPUT (MHz)	COMPATIBILITY	PRICE (QUANTITY)	COMPOSITE INPUTS
ANALOG DEVICES	AD9700	8	125	ECL	\$42.50-\$74.50 (1)	SYNC, BLANK, REF WHITE, 10% BRIGHT
DEVIOLS	AD9768 HDG-0405	8	100 150	ECL ECL	\$29.25 (100) \$39-\$55 (1)	NONE SYNC, BLANK, SETUP, REF
	HDG-0605	6	150	ECL	\$44-\$64 (1)	WHITE, 10% BRIGHT SYNC, BLANK, SETUP, REF
	HDG-0805	8	150	ECL	\$52-\$67 (1)	WHITE, 10% BRIGHT SYNC, BLANK, SETUP, REF WHITE, 10% BRIGHT
	HDG-0407	4	50	TTL	\$45-\$48 (1)	SYNC, BLANK, SETUP, REF WHITE, 10% BRIGHT
	HDG-0807	8	50	TTL	\$55-\$61 (1)	SYNC, BLANK, SETUP, REF WHITE, 10% BRIGHT
ANALOGIC	AH8308E	8 5577 344	150	ECL (children)	\$45 (100)	SYNC, BLANK, SETUP, 10% BRIGHT
	AH8308T	8 5.2%	65	TTL 105 (2019)	\$49 (100)	SYNC, BLANK, SETUP, 10% BRIGHT
	MP8308	8 19 19 19 19 19	100 (ECL) 40 (TTL)	ECL OR TTL	\$80 (100)	SYNC, BLANK, SETUP, REF
	MP8318	8. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2. 2.	100 (ECL) 40 (TTL)	ECL OR TTL	\$77 (100)	NONE
BROOKTREE	Bt102	8	75	TTL/CMOS	\$31 (1000)	SYNC, BLANK, SETUP, REF WHITE, 10% BRIGHT
FUJITSU	MB40788 MB40748-8 MB40748-9 MB40776	10 10 (8-BIT ACC) 10 (9-BIT ACC) 6	125 20 20 20 20.	ECL ECL ECL TTL	\$63 (10,000) \$19.80 (10,000) \$24.39 (10,000) \$7.31 (10,000)	NONE NONE NONE NONE
HONEYWELL SPT	HDAC97000	8	200	ECL	\$23 (1000)	SYNC, BLANK, SETUP, REF WHITE, 10% BRIGHT
NTECH	VDAC 0405	4	100	ECL	\$44 (100)	SYNC, BLANK, SETUP, REF WHITE, 10% BRIGHT
	VDAC 0605	6	100	ECL	\$67 (100)	SYNC, BLANK, SETUP, REF WHITE, 10% BRIGHT
	VDAC 0805	8	100	ECL	\$61 (100)	SYNC, BLANK, SETUP, REF WHITE, 10% BRIGHT
	VDAC 1840	8	40	TTL/CMOS	\$24 (100)	SYNC, BLANK, REF WHITE, 10% BRIGHT
	VDAC 8308THC	8	65	TTL/CMOS	\$52 (100)	SYNC, BLANK, SETUP, REF WHITE, 10% BRIGHT
	RGB DAC 3400S	4	40	TTL/CMOS	\$40 (100)	SYNC, BLANK, REF RGB
EKTRONIX	TEK 8120 TEK 8121 TEK 8130/8131	8 6 8	200 200 300	ECL ECL ECL	\$150 (1) \$100 (1) \$300 (1)	NONE NONE NONE
ELMOS	TML1840 TML1842 TML1850 TML1852	8 8 8 8	25 25 75–85 75–85	TTL TTL TTL TTL	\$40-\$51 (100) \$14-\$27 (100)	SYNC, BLANK, 10% BRIGHT SYNC, BLANK, 10% BRIGHT SYNC, BLANK, 10% BRIGHT SYNC, BLANK, 10% BRIGHT
RW	TDC1012 TDC1112 TDC1018	12 12 8	20 20 125	TTL ECL ECL	\$70 (1000) * \$26 (1000)	NONE NONE SYNC, BLANK, REF WHITE,
	TDC1034	4	125	ECL	\$18 (1000)	10% BRIGHT SYNC, BLANK, 10% BRIGHT



Eleven new VMEbus modules from Dual can make your 32-bit designs take off. Today.

Dual's full line of VMEbus modules is setting new performance and packaging standards in the 32-bit world. Especially among applications that demand high system throughput, fast I/O processing and heavy disk usage. For performance, start with our multiprocessor engine, the VMPU-32, based on Motorola's advanced MC68020. Optimized for virtual memory UNIX environments, it features extensive interprocessor communication capabilities, a full megabyte of dual-ported local memory, and up to 32 Kbytes of EPROM.

Next, add the industry's fastest, most versatile disk controllers, for both SMD and ESDI formats, using Dual's patented architecture. The SMD controller handles 3 drives with 2.4 Mbyte-persecond data rates; the ESDI controller handles 4 at 1.25 Mbytes per second. Then add our powerful VME universal storage controller, which handles hard disk, cassette tape and floppy disk drives, using both ST-506 and SCSI interfaces. And, for high-performance input/output handling, there's a multi-purpose I/O processor with 512 Kbytes of dual-port memory, supporting the industry-standard Motorola I/O bus protocol. Plus our compact, 8-port serial I/O module, which minimizes the space taken by I/O ports.

These modules are all fully ruggedized, housed in a standard VME backplane, and run under a system controller featuring fast 96ns arbitration. For software support, our implementation of UNIX System V, Release 2.0, Version 2 is available.

So why waste time developing your own 32-bit VMEbus solutions when ours are ready to go? For full details, contact: Dual Systems Corporation, 2530 San Pablo Ave., Berkeley, CA 94702. (415) 549-3854. Telex 230199 SWIFT.

THERE'S ONLY ONE

Unix is a trademark of AT&T Bell Laboratories.

CIRCLE NO 70

TDIDI		V COM	/EDTEDC
INIFL		A CUIT	<b>VERTERS</b>

MANUFACTURER	MODEL	RESOLUTION (BITS/ CHANNEL)	THROUGHPUT (MHz)	COMPATIBILITY	PRICE (QUANTITY)	COMPOSITE INPUTS
ANALOG DEVICES	AD9702	4	125 (ECL) 75 (TTL)	ECL OR TTL	\$50 TO \$63 (1)	SYNC, BLANK, REF WHITE
ANALOGIC	AH8304TC AH8308TC AH8308EC AH8404TC	4 8 8 4	100 100 150 25	TTL TTL ECL TTL	\$49 (100) \$93 (100) \$86 (100) \$52 (100)	SYNC, BLANK SYNC, BLANK SYNC, BLANK
BROOKTREE	Bt101 Bt103 Bt444	8 4 4	50 75 40	TTL/CMOS TTL/CMOS TTL/CMOS	\$69 (1000) \$36 (1000) \$59 (1000)	SYNC, BLANK, REF WHITE SYNC, BLANK SYNC, BLANK
FERRANTI	ZN454CJ	4	100	TTL	\$29.76 (100)	RGB SYNC, BLANK
HONEYWELL SPT	HDAC34010 HDAC34020	* <b>4</b> ***********************************	100	ECL STATE	\$39 (1000) \$39 (1000)	SYNC, BLANK, REF WHITE 10% BRIGHT SYNC, BLANK, REF WHITE 10% BRIGHT
INTECH	VDAC 888E RGB DAC 3400 RGB DAC 3800 RGB DAC 5151	8 4 8	100 40 40 150	ECL TTL/CMOS TTL/CMOS	\$149 (100) \$58 (100) \$90 (100) \$45 (100)	SYNC, BLANK SYNC, BLANK, REF RGB SYNC, BLANK, REF AND 10% BRIGHT RGB SYNC, BLANK, REF WHITE 10% BRIGHT
SIGNETICS	NE5151	4	150	TTL OR ECL	\$43 (100)	SYNC, BLANK, REF WHITE 10% BRIGHT
TRW	TDC1334	4	100	ECL	\$35 (1000)	SYNC, BLANK, 10% BRIGH

ANALOGIC AHB: ANALOGIC AHB: AHB: BROOKTREE Bt45.	-3805 8 -3806 8	8	200 (ECL) 83.3 (TTL) 100 100-115	ECL OR TTL  ECL  ECL	256×8 256×8	\$40 (100) \$430 (1) \$463-\$512 (1)	HSYNC, VSYNC, BLANK, OVERLAY  RGB SYNC, BLANK, REF WHITE, 10% BRIGHT
TRIPLE CONVERTERS  ANALOG DEVICES  HDL- HDL- HDL- HDL- HARALOGIC  ANALOGIC  BROOKTREE  B145	-3805 8 -3806 8	8	100 100–115	ECL	256×8	\$430 (1)	RGB SYNC, BLANK, REF WHITE, 10% BRIGHT
ANALOGIC AHB: ANALOGIC AHB: BROOKTREE B145	-3806 8	8	100-115				WHITE, 10% BRIGHT
ANALOGIC AHB: ANALOGIC AHB: AHB: BROOKTREE B145	-3806 8	8	100-115				WHITE, 10% BRIGHT
BROOKTREE Bt45						11.10 40.12 (1)	RGB SYNC, BLANK, REF WHITE, 10% BRIGHT
		4	20 20	TTL TTL	32×4 32×4	\$76 (100) \$80 (100)	SYNC, BLANK SYNC, BLANK
Bt45 Bt45	50 4	4	40 50 125	TTL/CMOS TTL/CMOS TTL/CMOS	16×4 19×4 260×4	\$65 (1000) \$32 (1000) \$105 (1000)	SYNC, BLANK SYNC, BLANK SYNC, BLANK
NMOS IMSO	G170 6	6	35, 50	TTL	256×6	\$62 (100) (35-MHz VERSION)	SYNC, BLANK
RGB RGB RGB RGB	3 DAC 3404 3 DAC 3405 3 DAC 3408 3 DAC 3808 4 3 DAC 34055 4	4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	100 40 40 40 40 40 40 40	ECL TTL/CMOS TTL/CMOS TTL/CMOS TTL/CMOS TTL/CMOS TTL/CMOS TTL/CMOS	256×8 16×4 32×4 256×4 256×8 32×4 16×4	\$434 (100) \$79 (100) \$121 (100) \$195 (100) \$184 (100) \$53 (100) \$52 (100)	RGB SYNC AND BLANK SYNC, BLANK, REF RGB BLANK SYNC, BLANK, REF RGB SYNC, BLANK, REF AND 10% BRIGHT RGB SYNC, BLANK SYNC, BLANK, REF WHIT 10% BRIGHT
SIGNETICS NE51	150 4	4 ( ) ( ) ( ) ( ) ( ) ( )	110	TTL OR ECL	16×4	\$43 (100)	SYNC, BLANK, REF WHIT 10% BRIGHT
TEXAS TMS:	34070 4	4	36	TTL	16×4	\$24 (100)	BLANK

Attend The World's Largest Design **Engineering Event...** 



McCormick Place • Chicago, Ill. • March 24-27,

#### The Show:

See, test and compare thousands of OEM products and design tools, at

- Find new sources of materials and components from more than 600 leading supplies. newest and most advanced CAD/CAM systems • Examine new state-of-the-art manufacturing technologies
- Acquire new design ideas Discover new applications Learn new solutions to design problems

SPECIAL SHOW FEATURE — Industry's Tribute to the Design Engineer

The Show will acknowledge and pay tribute to the tremendous contributions that you and other design engineers have made in improving the quality of life throughout the world. Be there and be recognized.

#### The Conference:

Sessions and in-depth Short Courses to keep you up to date with the latest design techniques, tools, technologies, materials, and applications available to you today including:

• CAD/CAM selection, usage and applications • Computer-aided engineering • Plastics design and processing • Finite elements • Microprocessor and personal-computer design applications • Robotics • Designing for automated assembly

Use this coupon to pre-register for free show admission

Save Time, Save Money: Fill out this coupon and mail it to arrive before March 10, 1986. Otherwise, registration at the Show will cost \$15. Use the coupon to request a complete Conference Program and Conference registration details.

#### **Bonus:**

All Conference and Show registrants receive free admission to two concurrent shows: Spring National Plant Engineering & Maintenance Show and DEPO '86, The National Warehousing and Distribution Facilities Exposition.

#### Pre-Register Now For Free Admission To

The World's Largest Design Engineering Event...



Spring National Design **Engineering** Show & Conference 1M

McCormick Place • Chicago, Ill. • March 24-27, 1986

Name												لــا
Title	Ш			Ш								
Company		1 1										
Street				Ш		Ш						
City										J	State	
Zip			Te	lepi	hone	No			<b>_</b> 1-L		<u> </u>	Ш
Sorry, no o	one ur may b	der 1 e dup	8 ad	mitt ed f	ed. or ac	dditio	nal	regi	strar	ıts.		

For more information contact Customer Services at (203) 964-8287

Send coupon to arrive before March 10, 1986, to: Spring National Design Engineering Show Registration Dept. P.O. Box 3833 Stamford, CT 06905-0833

1.	Industry	Group	(please	check	one	onl	y)	١
----	----------	-------	---------	-------	-----	-----	----	---

- ☐ Metal Products G 
  Food, Beverages Engineering Services Non-Electrical Machinery Electrical Machinery Industrial Distribution ☐ Transportation Equipment
  - K Construction Chemicals, Petroleum Instruments, Controls M 

    Other (specify) ☐ Plastics, Rubber
- 2. Product Categories (check all you are interested in seeing)
- A 

  CAD/CAM H 

  Metals B 

  Computers J □ Plastics K □ Power Transmission □ Electrical Components ☐ Electronic Components
- ☐ Shapes & Forms M 

  Engineering Svcs./Equip. E 

  Finishes, Coatings ☐ Fluid Power Components N Other (specify) G 

  Mechanical Components
- ☐ YES, please send me a complete Conference ☐ YES, my company is interested in exhibiting. Send me

details.

#### EDN Multibus I I/O-Board Directory

# Intelligence, local buses preserve viability of Multibus I

Pacing recent developments in computer architecture, systems based on the 9-year-old Multibus I spec are using subsidiary buses and intelligent I/O boards to offer improved throughput.

Ed Teja, Western Editor

Multibus I—a capable, proven architecture for medium-performance computing applications—is known for its flexibility when compared with Q Bus systems and for its power when compared with the STD Bus. But time has its way with all things, including bus architectures: The advent of increasingly powerful microprocessors and the growth of increasingly demanding applications have conspired to force designers to use buses with more power and more capability than the venerable Multibus I can offer. Still, a number of available subsidiary buses and intelligent I/O cards are helping to maintain the viability of the Multibus.


For designers who wish to take advantage of recent developments in computer architecture, but who still intend to base their systems on Multibus I, two inherent limitations cause problems: bus width and bus bandwidth. The 9-year-old Multibus specification won't handle a full 32-bit design. Its 16 data lines and 24 address lines are intended for 8- and 16-bit systems, and it can't directly address the memory required by many of today's system designs. These systems are dominated by the VME Bus and, more recently, Multibus II.

Some CPU board manufacturers, such as Matrox, have seemingly gotten around this limitation of the Multibus I specification by producing 32-bit CPU cards with 16-bit I/O. This strategy is fine if your rationale for moving to 32-bit designs is to take advantage of a particular 32-bit processor's computing power; these boards will provide a solution without requiring a complete system redesign. If you're like most designers, however, you're employing a 32-bit processor to improve overall system performance. The restriction to 16-bit I/O won't render the desired throughput improvement.

#### Multiprocessing meets bandwidth limits

Another trend in computer architectures is multiprocessing: the division of computational chores among multiple processors. Today, the state of the art in multiprocessing is parallel architecture. Here is where the second limitation of Multibus-based systems comes to bear: Multibus I systems don't have the bandwidth to support sophisticated multiprocessing.

Multiprocessor systems typically place a number of processors on the bus, an arrangement that would overload the Multibus. One approach to resolving these problems has been to resort to multicomputing strate-



On-board intelligence lets sophisticated communications boards, such as the COM-4 from SBE Inc, relieve the CPU and the Multibus of many communications tasks.

gies rather than multiprocessing. In a multicomputer environment, the processing chores are shared among multiple computers—transparently to the user.

#### Subsidiary buses offload CPU

To accommodate multiple computers on the Multibus, you can begin by adding subsidiary I/O buses. Without subsidiary buses, the only path for data, instructions, and addresses is the Multibus itself (Fig 1a). The addition of local buses (Fig 1b) gives intelligent controllers direct access to dual-ported memory without bothering the CPU. A variety of board products take advantage of these buses to provide system functions, such as data transfers to mass-storage devices, without overloading the Multibus.

Such buses include the iSBX, a low-cost local bus; the iLBX, a high-speed memory bus; and the Multichannel, a high-speed path for block data transfers. These buses provide paths that allow specialized processors to gain access to data stored in the host computer's memory. Intel Corp's iSBX 586 board, for example, implements Ethernet connections. Priced at \$600 (100), the board plugs into any host that has an iSBX connector, giving the host an intelligent (82586-based) interface to high-speed communications via a local-area network (LAN)

without using Multibus slots. Multiuser operating systems make the system's interaction with the LAN a chore that the CPU doesn't have to deal with.

The next logical step in developing more computer power around the Multibus is to two allow stand-alone computers to share information via other channels. Companies like Mesa Technology Corp (Gaithersburg, MD) provide bus couplers that connect Multibus-based systems to DEC Q Bus or Unibus systems, or even to other Multibus systems.

These boards support DMA transfers between the systems, allowing them to share data without affecting the host system's performance noticeably. The result is the same as having a specialized processor in the same system accessing data via a local bus.

#### Adding intelligence

The main ingredient in maintaining Multibus I systems' viability, however, is the addition of increasingly powerful Multibus I cards. Sophisticated, intelligent I/O boards, even if they gain access to data through the bus, offload the main processor by reducing the amount of communication required between the CPU and its peripherals. Reducing the necessary communications in turn lowers the bandwidth requirements of the system.

To accommodate multiple computers on the Multibus, you can begin by adding subsidiary I/O buses.




Fig 1—Multibus I provides a narrow pathway for contemporary system designs (a). Local buses provide paths that allow intelligent I/O modules to share data without loading down the main bus (b).

In the graphics field, for example, companies such as Datacube provide video acquisition, storage, processing, and display capabilities on Multibus cards. Datacube's VG-124 displays 640×256 pixels in 64 gray levels, and it features scroll, zoom, and high/low resolution. Boards like these let you add graphics capability without bogging down system performance.

Certainly, these I/O systems do nothing to alleviate the inability of Multibus I to accommodate 32-bit-wide data transfers, but they do offer performance increases that let you fabricate systems competitive with their 32-bit kin in certain market niches.

As a result of the inherent bus-width and bandwidth limitations, Multibus I systems tend to grow outward:

These intelligent I/O boards expand a Multibus system so that it can meet the needs of the application they serve. The I/O boards provide a system growth path, whether it is toward more and faster mass storage or toward interaction with other computer systems.

#### The definition process

For the purposes of this directory, we've grouped the boards into two large categories: data controllers and mass-storage controllers. The tables include only full Multibus I boards. We've elected to exclude iSBX and other subsidiary buses, which would serve to confuse rather than complement this directory.

The data-controller category (Table 1, pg 124) in-

cludes such communications boards as serial I/O, parallel I/O, and analog I/O. **Table 2** (pg 128) lists Multibus I mass-storage controller cards. You'll see that multifunction controllers are the mass-storage equivalents of intelligent I/O cards. These boards handle a variety of tape and disk devices rather than simply floppy or Winchester disk drives. Industry analyst Joe Jaworski, president of Peripheral Concepts (Irvine, CA), expects that 43.2% of all controllers will support multiple devices by 1988 (**Ref 1**). These controllers are changing primarily to meet the needs of CAD/CAM workstations, which represent the leading edge of affordable high-performance computer systems.

Use this directory as a starting point to determine

the features you can give your system. The board vendors listed will be delighted to tell you of the piggyback boards and other options that can extend a system's functionality even further.

#### Reference

1. 1985 Controller Concepts, Vol 2, Peripheral Concepts Inc, 18003-G2 Skypark Circle, Irvine, CA 92714. Phone (714) 250-9510.

Article Interest Quotient (Circle One) High 473 Medium 474 Low 475

#### For more information . . .

For more information on the Multibus I/O boards described in this article, contact the following manufacturers directly or circle the appropriate numbers on the Information Retrieval Service card.

Aviv Corp 26 Cummings Park Woburn, MA 01801 (617) 933-1165 Circle No 645

Burr-Brown Corp Box 11400 Tucson, AZ 85734 (602) 746-1111 Circle No 646

Central Data Corp 1602 Newton Dr Champaign, IL 61820 (217) 359-8010 Circle No 647

Ciprico Inc 2955 Xenium Lane Plymouth, MN 55441 (612) 559-2034 Circle No 648

Comark Corp 93 West St Medfield, MA 02052 (617) 359-8161 Circle No 649

Communications Machinery Corp 1421 State St Santa Barbara, CA 93101 (805) 963-9471 Circle No 650

Datacube Inc 4 Dearborn Rd Peabody, MA 01960 (617) 535-6644 Circle No 651 Data Technology Corp 2775 Northwestern Pkwy Santa Clara, CA 95051 (408) 496-0434 Circle No 652

Datel 11 Cabot Blvd Mansfield, MA 02048 (617) 339-9341 Circle No 653

E F Data Corp 1233 N Stadem Dr Tempe, AZ 85281 (602) 968-0447 Circle No 654

Intel Corp 5200 NE Elam Young Pkwy Hillsboro, OR 97123 (503) 640-7157 Circle No 655

Interphase Corp 2925 Merrel Rd Dallas, TX 75229 (214) 350-9000 Circle No 656

Konan Corp 1425 N 27th Ave Phoenix, AZ 85009 (602) 269-2649 Circle No 657

Matrox Electronic Systems Ltd 1055 St Regis Blvd Dorval, Quebec, Canada H9P2TP (514) 685-2630 Circle No 658 Metacomp Inc 9466 Black Mountain Rd San Diego, CA 92126 (619) 578-9840 Circle No 659

Microbar Systems Inc 785 Lucerne Dr Sunnyvale, CA 94086 (800) 821-1011; in CA, (800) 421-1752 Circle No 660

Mini Computer Technology 696 E Trimble Rd San Jose, CA 95131 (408) 942-1616 Circle No 661

Morrow Technologies Corp 3026 Owen Dr Antioch, TN 37013 (615) 793-3555 Circle No 662

Omnibyte Corp 245 W Roosevelt Rd West Chicago, IL 60185 (312) 231-6880 Circle No 663

Plessey Microsystems
1 Blue Hill Plaza
Pearl River, NY 10965
(800) 368-2738; in NY, (914) 735-4661
Circle No 664

Proteon Inc 4 Tech Circle Natick, MA 01760 (617) 655-3340 Circle No 665 Qualogy Inc 2241 Lundy Ave San Jose, CA 95131 (408) 946-5800 Circle No 666

SBE Inc 2400 Bisso Lane Concord, CA 94520 (800) 221-6450; in CA, (800) 328-9900 Circle No 667

Scientific Micro Systems 339 N Bernardo Mountain View, CA 94048 (415) 964-5700 Circle No 668

Systech Corp 6465 Nancy Ridge Rd San Diego, CA 92121 (619) 453-8970 Circle No 669

Wespercorp 14511 New Myford Rd Tustin, CA 92680 (714) 730-6250 Circle No 670

Xylogics 144 Middlesex Tpke Burlington, MA 01803 (617) 272-8140 Circle No 671

Zendex Corp 6700 Sierra Lane Dublin, CA 94568 (415) 828-3000 Circle No 672


#### TABLE 1-MULTIBUS I I/O BOARDS

VENDOR	MODEL	TYPE	NUMBER OF SERIAL CHANNELS	MAX BAUD RATE	NUMBER OF PARALLEL LINES	PRICE	COMMENTS
BURR-BROWN CORP	MP801	DIGITAL OUTPUT BOARD	0	N/A	16	\$325 (1 TO 49)	RELAY OUTPUT SYSTEM
	MP802	DIGITAL OUTPUT BOARD	0	N/A	32	\$495 (1 TO 49)	RELAY OUTPUT SYSTEM
	MP810	DIGITAL INPUT BOARD	0	N/A	24	\$450 (1 TO 49)	
	MP8304	D/A CONVERTER	4-CHANNEL D/A CONVERTER, 8 DIFFERENTIAL CHANNELS, 16 SINGLE-ENDED CHANNELS	N/A	0	\$775 (1 TO 49)	
	MP8418	ANALOG I/O	2 OUTPUT, 32 INPUT	N/A	0	\$740 (1 TO 49)	12-BIT RESOLUTION
	MP8632	ANALOG I/O	2 OUTPUT, 64 SINGLE-ENDED	N/A	0	\$535 (1 TO 49)	8-BIT RESOLUTION
CENTRAL DATA	B1031	SERIAL I/O	8	19.2k	0	\$705 (100)	BASED ON AN 8088; INCLUDES 64k- BYTE BUFFER
COMMUNICATION MACHINERY CORP	DNP-30	LAN BOARD	1	10M	0	\$2300	SUPPORTS TCP/IP AND X.2 PROTOCOLS
DATEL	ST-701	ANALOG-TO- DIGITAL	16 SINGLE-ENDED OR 32 DIFFERENTIAL	N/A	0	\$1170 TO \$1585	CHOICE OF 12- 14-, OR 16-BIT RESOLUTION
	ST-702	ANALOG-TO- DIGITAL	8	N/A	0	\$1095	FOR THERMO- COUPLE INPUT 13-BIT RESOLUTION/ 128-dB CMRR
F DATA CORP	BCM-201	MODEM BOARD	1	2.5M		\$780 (25 TO 50)	WORKS WITH COAXIAL LANS
NTEL CORP	ISXM MAP COMMENGINE	COMMUNICATIONS BOARD	1	10M	0	\$3750	SUPPORTS MAI PROTOCOL; INCLUDES 256k BYTES OF RAM
	iSBC 188/56	COMMUNICATIONS BOARD	8 (EXPANDABLE TO 12)	19.2k	0	\$1895	SUPPORTS ASYNC, BISYNC HDLC, AND SDL PROTOCOLS
	iSBC 88/45	COMMUNICATIONS BOARD	3	19.2k	0	N/A	SUPPORTS RS-232C, CCITT V.24, AND RS-422A/449
ATROX LECTRONIC YSTEMS LTD	CP2000	COMMUNICATIONS PROCESSOR	8 38	19.2k	0	\$2495	INCLUDES ETHERNET (802.3) CHANNE
IETACOMP INC	MSC-1062	SERIAL I/O	8 Turner of Jacobson Co.	76.8k		\$975 (50)	BASED ON AN 8088; INCLUDES 128k-BYTE BUFFER
	MPA-2160	SERIAL I/O	16	76.8k	0		INCLUDES 128k-BYTE BUFFER; JUMPER- SELECTABLE DT OR DCE

VENDOR	MODEL	TYPE	NUMBER OF SERIAL CHANNELS	MAX BAUD RATE	NUMBER OF PARALLEL LINES	PRICE	COMMENTS
MICROBAR SYSTEMS INC	COM16	COMMUNICATIONS BOARD	8 ON BASIC SYSTEM (EXPANDABLE TO 16)	56k	0	\$1890	EXPANDABLE BUFFER MEMORY TO 512k BYTES
MORROW TECHNOLOGIES CORP	MX-422	COMMUNICATIONS CONTROLLER	8	76.8k	0	\$895 (100)	FEATURES OPTIONAL TRANSIENT SUPPRESSION
OMNIBYTE CORP	OB68K/INT (S)	SERIAL I/O	4	38.4k	0	\$695	
	OB68K/OCTAL	SERIAL I/O	8	38.4k	0	\$795	
	OB68K/INT (P)	PARALLEL I/O	0	N/A	48	\$495	INCLUDES SASI AND CENTRONICS PRINTER INTERFACES
	OB68K/230	PARALLEL I/O	0	N/A	96	\$395	
PLESSEY MICROSYSTEMS	IOP-1	SERIAL I/O	8	19.2k	N/A	\$1988	16k-BYTE BUFFER; 8086- BASED
PROTEON INC	P1200	LAN BOARD	1	10M	0	\$3150	SUPPORTS PROPRIETARY TOKEN-PASSING LAN
	P1280	LAN BOARD	1	80M	0	\$8000	SUPPORTS PROPRIETARY TOKEN-PASSING LAN
SBE INC	COM-4	COMMUNICATIONS BOARD	4	3М	0	\$1195 (100)	INCLUDES TWO DMA CHANNELS; SUPPORTS SDLC HDLC, X.25, AND BISYNC
	COM-II	COMMUNICATIONS BOARD	2	3M	0	\$1295 (100)	SUPPORTS SDLC HDLC, X.25, AND BISYNC
	M68COM	COMMUNICATIONS BOARD	8	38.4k	0	\$1175 (100)	SUPPORTS SDLC HDLC, X.25, AND BISYNC
SYSTECH CORP	DCP-8804	SERIAL I/O	4	1M	0	\$1675 TO \$2365 (100)	INCLUDES TWO DMA CHANNELS AND A 64k- TO 512k-BYTE BUFFER
ZENDEX CORP	ZX-514	SERIAL I/O	4	19.2k	0	\$200 (100)	
	ZX-515	SERIAL I/O	5	19.2k	0	\$525 (100)	
	ZX-560	PARALLEL I/O	0	N/A	72	\$420 (100)	
	ZX-572	PARALLEL I/O	0	N/A	72	\$500 (100)	ORGANIZED AS NINE 8-BIT PORTS
	ZADC-518	COMMUNICATIONS BOARD	8	56k	O 26 30 30 30 30 30 30 30 30 30 30 30 30 30	\$2100 (100)	SUPPORTS HDLC, SDLC, AND X.25 PROTOCOLS

EDN February 6, 1986

# HONEST ENGINE



### An 80286 CPU Board Without Compromise.

The MPA-1000 is the only Multibus-compatible CPU that taps the full capabilities of the 80286 microprocessor. An honest engine, built to unleash the full potential of the 80286 in multi-user, multi-tasking or real-time applications. And it delivers the power and memory for these demanding applications all in a single card slot.

Up to 2 Mbytes of dual-ported zero wait state dynamic RAM. iLBX high speed memory bus interface. Two serial I/O ports, and programmable registers which allow flexible memory mapping and minimize option jumpers and possible configuration errors.


And for even greater performance, simply plug in the optional 80287 numeric coprocessor and the 82258 Advanced DMA Controller.

Don't compromise. Call or write METACOMP today. Discover what makes the MPA-1000 the honest 80286 engine.

#### METACOMP THE MULTIRUS BREAKTHROUGH REODLE

METACOMP, Inc 9466 Black Mountain Road San Diego, CA 92126 (619) 578-9840 TWX 910-335-1736 METACOMP SDG

MPA-1000 is a trademark of METACOMP, Inc. Multibus is a registered trademark of Intel Corporation.



# A Few Intimate Questions to Ask Your Supplier Before You Buy Your Next System Bus Boards:

1. Who really builds the boards?

Your supplier may not be building them . . . just selling them. Find out. Job shop quality can be risky business.

2. Is the production facility good enough to meet U.S. and U.K. mil specs?

Unless it's Plessey Microsystems, the answer is no. Only Plessey produces each and every board in a facility which meets U.S. (AQAP 1&2) and U.K. (DEF. STAN. 05-21) military specifications for production . . . giving you military quality at commercial prices.

3. Is your supplier silicon independent?

Some board level manufacturers are also semiconductor manufacturers who have to use their own company's chips. Not Plessey Microsystems. We use the world's market to get the best devices at the best prices.

4. How complete is the product line?

Does your supplier offer a full range of fully guaranteed Multibus\* and iLBX, and VERSAbus† memories; and VMEbus memories, CPU's, I/O and development systems? With a commitment to other major systems? Plus bubble memory? Plessey Microsystems does.

5. How much expertise in supermicros does your supplier really have?

That's a clue to the company's commitment to the market and its ability to deliver advanced technology on a continuing basis. At Plessey Microsystems, we've been advancing computer technology since the beginning of the computer age. And we're still doing it.

6. Can you get truly global technical support?

You may not need worldwide back-up now, but isn't it comforting to do business with a company that can support you almost anywhere?

Now, ask Plessey Microsystems.

If you're looking for that one supplier who can give you all the right answers, and all the right products, services and pricing... plus that priceless ingredient—The Comfort Sensation . . . just call Plessey Microsystems. And relax.

\*TM Intel +TM Motorola



Plessey and the Plessey symbol are registered trademarks of The Plessey Company plc

For additional that date,

**CIRCLE NO 73** 

England Water Lane Towcester Northants NN12 7JN (0327) 50312 France 7-9 rue Denis Papin 78194 Trappes Cedex (3) 0514952

Germany Bahnhofstraße 38 D-6090 Russelsheim (0 61 42) 6 80 04

United States One Blue Hill Plaza Pearl River NY 10965 (914) 735-4661

Microsystems Ind.

#### TABLE 2—MULTIBUS I MASS-STORAGE CONTROLLER CARDS

				DRIVE CHARACTER	DRIVE CHARACTERISTICS					
MANUFACTURER	MODEL NUMBER	CONTROLLER TYPE	DRIVE INTERFACE	MAXIMUM NUMBER OF DRIVES	SECTOR SIZES (BYTES)	ERROR DETECTION				
AVIV CORP	TFC 505	TAPE ONLY (9 TRACKS)	PERTEC/STC	4 TAPE DRIVES	TO 64k	N/A (IN THE FORMATTER)				
CENTRAL DATA CORP	CD21/4029	TAPE ONLY (1/4-IN. CARTRIDGE)	QIC-02	4 TAPE DRIVES	512	N/A (IN THE FORMATTER)				
	CD21/4300	MULTIFUNCTION (WINCHESTER/ FLOPPY/TAPE)	ST506 (WINCHESTER), SA850/450 (FLOPPY), QIC-02 (TAPE)	4 WINCHESTERS, 4 TAPES, 4 FLOPPIES	128 THROUGH 1k	32-BIT ECC				
CIPRICO INC	PICO-MATE	TAPE ONLY (1/4-IN. CARTRIDGE)	KENNEDY 6455	2 TAPE DRIVES	N/A	N/A (IN THE FORMATTER)				
	TAPEMASTER A	TAPE ONLY (9 TRACKS)	PERTEC	8 TAPE DRIVES	TO 64k	N/A (IN THE FORMATTER)				
	RIMFIRE 44A	MULTIFUNCTION (WINCHESTER/TAPE)	ANSI BSR X3.101 (DISK), QIC-02 (TAPE)	8 WINCHESTERS, 4 TAPES	128 THROUGH 1k	32-BIT ECC				
	RIMFIRE 45A	MULTIFUNCTION (WINCHESTER/TAPE)	ANSI BSR X3.101 (DISK), PERTEC (TAPE)	8 WINCHESTERS, 4 TAPE DRIVES	128 THROUGH 1k	N/A				
contract to	RIMFIRE 50	WINCHESTER ONLY (8- OR 14-IN.)	SMD (1.8M BYTES/SEC)	4 WINCHESTERS	PROGRAM- MABLE	48-BIT ECC				
	TAPEMASTER 1000	TAPE ONLY (9 TRACKS)	PERTEC	8 TAPE DRIVES	TO 64k	N/A (IN THE FORMATTER)				
	RIMFIRE 1200	WINCHESTER ONLY (8- OR 14-IN.)	SMD (2.5M BYTES/SEC)	4 WINCHESTERS	PROGRAM- MABLE	48-BIT ECC				
	RIMFIRE 75T	TAPE ONLY (1/4-IN. CARTRIDGE)	3M HCD-75	4 TAPE DRIVES	N/A	N/A (IN THE FORMATTER)				
	QUARTER- MASTER	TAPE ONLY (1/4-IN. CARTRIDGE)	QIC-02	4 TAPE DRIVES	512 BYTES	N/A (IN THE FORMATTER)				
COMARK CORP	MT80	TAPE ONLY (9 TRACKS)	PERTEC	8 TAPE DRIVES	TO 2k	N/A (IN THE S FORMATTER)				
	MT86	TAPE ONLY (9 TRACKS)	PERTEC	8 TAPE DRIVES	TO 65k	N/A (IN THE FORMATTER)				
	MF85	FLOPPY ONLY (5¼- OR 8-IN.)		FOUR 8-IN. AND THREE 51/4-IN. FLOPPIES	PROGRAM- MABLE	N/A				
DATA TECHNOLOGY CORP		WINCHESTER ONLY (51/4-IN.)	ST506	2 WINCHESTERS	128 THROUGH 1k	32-BIT ECC				
		MULTIFUNCTION (WINCHESTER/FLOPPY)		2 WINCHESTERS, 2 FLOPPIES		32-BIT ECC				
	2000	(WINCHESTER/	ST506 (WINCHESTER), SA450 (FLOPPY),	2 WINCHESTERS, 2 FLOPPIES, 1 CARTRIDGE TAPE		32-BIT ECC				

				HOST CHARA	CTERISTICS			
	ERROR CORRECTION	FLAW SKIPPING	SUPPORT LEVEL	SIZE OF BUFFER (BYTES)	HOST TRANSFER RATE	MINIMUM INTERLEAVE	OEM PRICE (US)	COMMENTS
	N/A (IN THE FORMATTER)	BLOCK REWRITES	24-BIT ADDRESSING	4k (32k OPTIONAL)	2.5M BPS	N/A	\$3800	TRIDENSITY TAPE COUPLER TO 200-IPS SPEEDS
	N/A (IN THE FORMATTER)	BLOCK REWRITES	D8/M24 (MASTER)	NONE	N/A	N/A	\$310	ONBOARD DMA
	11-BIT BURST	TRACK LEVEL	D16/M24 (MASTER)	2k (STD), 8k (OPTIONAL)	10M BPS	1:1	\$1300	OPTIMIZED FOR UNIX, ONBOARD CACHE, OPTIONAL ILBX DMA INTERFACE
2,000	N/A (IN THE FORMATTER)	N/A	24-BIT ADDRESSING	NONE	N/A	N/A	\$1190 	TAPEMASTER COMPATIBLE, ½-IN. TAPE EMULATION
	N/A (IN THE FORMATTER)	BLOCK REWRITES	24-BIT ADDRESSING	4 TO 16k (OPTIONAL)	N/A	N/A	\$1790	TRIDENSITY TAPE COUPLER START/STOP OR STREAMING
1	5-BIT BURST	N/A	24-BIT ADDRESSING	NONE	N/A	N/A	\$1995	AUTO-BACKUP/RESTORE
1	N/A	N/A	24-BIT ADDRESSING	NONE	N/A	N/A	\$2095	
1	16-BIT BURST	N/A	24-BIT ADDRESSING	8 TO 32k (OPTIONAL)	N/A	N/A	\$1775	
	N/A (IN THE FORMATTER)	BLOCK REWRITES	24-BIT ADDRESSING	1k (4k OPTIONAL)	4M BPS	N/A	\$1890	TRIDENSITY TAPE COUPLER; TAPE SPEEDS TO 1.5M BPS
	16-BIT BURST	N/A	24-BIT ADDRESSING	32k CACHE	N/A	1:1	\$2195	
	N/A (IN THE FORMATTER)	BLOCK REWRITES	24-BIT ADRESSING	N/A	N/A	N/A	\$995	ONBOARD BACKUP AND RESTORE
	N/A (IN THE FORMATTER)	BLOCK REWRITES	24-BIT ADDRESSING	NONE	N/A	N/A	\$550	
	N/A (IN THE FORMATTER)	BLOCK REWRITES	ONBOARD DMA	1k (8k OPTIONAL)	N/A	N/A	\$895	COUPLER FOR NRZ/PE TAPE DRIVES, TO 125-IPS SPEEDS
	N/A (IN THE FORMATTER)	BLOCK REWRITES	24-BIT DMA	N/A	N/A	N/A	\$895	COUPLER FOR NRZ/PE TAPE DRIVES, TO 125-IPS SPEEDS
	N/A	N/A	20-BIT ADDRESSING	NONE	N/A	N/A	\$695	SUPPORTS DOUBLE- SIDED, DOUBLE-DENSITY FLOPPIES; HAS ONBOARD MATH PROCESSOR
	11-BIT BURST	TRACK LEVEL	8/16 DATA, 16/20/24 ADD	N/A	1.6M BPS	1:1	\$495	
	11-BIT BURST	TRACK LEVEL	8/16 DATA, 16/20/24 ADD	N/A	1.6M BPS	PROGRAM- MABLE	\$620	
	11-BIT BURST	TRACK LEVEL	8/16 DATA, 16/20/24 ADD	16k	1.6M BPS	1:1	\$780	
								Table continued on pg

EDN February 6, 1986

#### TABLE 2—MULTIBUS I MASS-STORAGE CONTROLLER CARDS (continued)

				DRIVE CHARACTERI	STICS	
MANUFACTURER	MODEL NUMBER	CONTROLLER TYPE	DRIVE INTERFACE	MAXIMUM NUMBER OF DRIVES	SECTOR SIZES (BYTES)	ERROR DETECTION
INTEL CORP	iSBC 226	WINCHESTER ONLY (8- OR 14-IN.)	SMD (2M BYTES/SEC)	2 WINCHESTERS	1024 ONLY	32-BIT ECC
	iSBC 220	WINCHESTER ONLY (8- OR 14-IN.)	SMD	4 WINCHESTERS	128 THROUGH 1k	32-BIT FIRE CODE
	iSBC 208	FLOPPY ONLY (51/4- OR 8-IN.)	SA850/400	4 FLOPPIES	256 THROUGH 4k	N/A
	iSBC 214	MULTIFUNCTION (WINCHESTER/ FLOPPY/TAPE)	ST506 (WINCHESTER), SA450 (FLOPPY), QIC-02 (TAPE)	2 WINCHESTERS, 4 FLOPPIES, 4 TAPES	128 THROUGH 1k	32-BIT ECC
	iSBC 215G	WINCHESTER ONLY (51/4-IN.)	ST506	2 WINCHESTERS	PROGRAM- MABLE	32-BIT ECC
	iSBC 215	WINCHESTER ONLY (51/4-, 8, OR 14-IN.)	ANSI X379/1226	4 WINCHESTERS	128 THROUGH 1k	32-BIT ECC
INTERPHASE CORP	SDC 2203	FLOPPY ONLY (51/4- OR 8-IN.)	SA850/460	4 FLOPPIES	256 THROUGH 1k	N/A
	WDC 2881	WINCHESTER ONLY (8-IN.)	ANSI	4 WINCHESTERS	PROGRAM- MABLE	32-BIT ECC
	SMD 2181	WINCHESTER ONLY (8- or 14-IN.)	SMD (2.4M BYTES/SEC)	4 WINCHESTERS	PROGRAM- MABLE	32-BIT ECC
	SMD 2180	WINCHESTER ONLY (8- OR 14-IN.)	SMD	4 WINCHESTERS	128, 256, OR 512	ECC
	STORAGER	MULTIFUNCTION (WINCHESTER/ FLOPPY/TAPE)	ST506/412HP/ESDI (WINCHESTER), SA460 (FLOPPY), QIC-02 (TAPE)	2 WINCHESTERS, 2 FLOPPIES, 2 TAPE DRIVES	128 THROUGH 1k	32-BIT ECC
	SMD 2190	WINCHESTER ONLY (8- OR 14-IN.)	SMD (2.4M BYTES/SEC)	4 WINCHESTERS	PROGRAM- MABLE	32-BIT ECC
KONAN CORP	TAISHO 6000	MULTIFUNCTION (WINCHESTER/ FLOPPY)	ST506 (WINCHESTER), SA850/450 (FLOPPY), FLOPPY TAPE	4 WINCHESTERS, 4 FLOPPIES, OR 1 FLOPPY AND 1 FLOPPY TAPE	128, 256, OR 512	CRC .
MINI COMPUTER TECH	MCT 4300	WINCHESTER ONLY (8- OR 14-IN.)		4 WINCHESTERS	PROGRAM- MABLE	16-BIT CRC
	MCT 4500	WINCHESTER ONLY (51/4- OR 8-IN.)	SA1000/ST506	4 WINCHESTERS		32-BIT ECC
	1 1	MULTIFUNCTION (WINCHESTER/TAPE)		3 WINCHESTERS,		32-BIT ECC
QUALOGY		MULTIFUNCTION (WINCHESTER/FLOPPY)	ST506 (WINCHESTER),	2 WINCHESTERS,		32-BIT ECC
	5217B	MULTIFUNCTION (WINCHESTER/ FLOPPY/TAPE)		2 WINCHESTERS,		32-BIT ECC

				HOST CHAR	ACTERISTICS			
	ERROR CORRECTION	FLAW SKIPPING	SUPPORT LEVEL	SIZE OF BUFFER (BYTES)	HOST TRANSFER RATE	MINIMUM INTERLEAVE	OEM PRICE	COMMENTS
	11-BIT BURST	SECTOR LEVEL	24-BIT ADDRESSING	ONE SECTOR	N/A	1:1	\$2700	
	11-BIT BURST	TRACK LEVEL	20-BIT ADDRESSING	ONE SECTOR	N/A	N/A	\$2750	
	N/A	N/A	ONBOARD ISBX EXPANSION	N/A	N/A	N/A	\$1170	SINGE OR DOUBLE SIDED, SINGLE OR DOUBLE DENSITY
	11-BIT BURST	N/A	20/24-BIT ADDRESSING	32k CACHE	N/A	N/A	\$1450	iRMX/XENIX SUPPORT
	11-BIT BURST	N/A	N/A	ONE SECTOR	N/A	N/A	\$1650	MATES WITH ISBC 217/218, CONFIGURED AS ISBC 215 AND A DATA SEPARATOR BOARD
	11-BIT BURST	N/A	N/A	ONE SECTOR	N/A	N/A	\$2750	MATES WITH ISBC 217/218
	N/A	N/A	NONE	NONE	N/A	N/A	\$1795	ALSO HAS SCSI PORT AND ONBOARD CACHE, SINGLE OR DOUBLE DENSITY
200	11-BIT BURST	TRACK LEVEL	24-BIT ADDRESSING, DMA	NONE	N/A	SOFTWARE SELECTABLE	\$1695	
	11-BIT BURST	BAD-TRACK MAPPING	24-BIT ADDRESSING	ONE SECTOR	N/A	2:1	\$2250	
	8-BIT BURST	TRACK LEVEL	20-BIT ADDRESSING	NONE	N/A	N/A	\$1995	
	11-BIT BURST	TRACK LEVEL	24-BIT ADDRESSING	16k	3M-BPS DMA	1:1	\$1695	UNIX OPTIMIZED, ONBOARD CACHE, IMAGE BACKUP
	11-BIT BURST	TRACK AND SECTOR LEVEL	24-BIT ADDRESSING	16k	N/A	1:1	\$2250	UNIX OPTIMIZED, ONBOARD CACHE
3.13	ECC (WIN- CHESTER)	N/Å	24-BIT ADDRESSING	N/A	N/A	N/A	\$795	
	RETRY	SECTOR-LEVEL MAP	24-BIT ADDRESSING	N/A	N/A	1:1	\$1035	
	5-BIT BURST	SECTOR LEVEL	24-BIT ADDRESSING	N/A	N/A	1:1	\$1035	
	5-BIT BURST	SECTOR LEVEL	24-BIT ADDRESSING	N/A	N/A	1:1	\$1165	
	11-BIT BURST	N/A	24-BIT ADDRESSING	N/A	N/A	1:1	\$1175	4 ARBITRATION MODES
	11-BIT BURST	N/A	24-BIT ADDRESSING	N/A	N/A	1:1	\$1345	
								Table continued on pg 13.


EDN February 6, 1986

#### TABLE 2—MULTIBUS I MASS-STORAGE CONTROLLER CARDS (continued)

			DRIVE CHARACTERISTICS						
MANUFACTURER	MODEL NUMBER	CONTROLLER TYPE	DRIVE INTERFACE	MAXIMUM NUMBER OF DRIVES	SECTOR SIZES (BYTES)	ERROR DETECTION			
QUALOGY	RAMTRAC 5317	MULTIFUNCTION (WINCHESTER/ FLOPPY/TAPE)	ESDI (WINCHESTER), SA450 (FLOPPY), QIC-02 (TAPE)	2 WINCHESTERS, 2 FLOPPIES, 1 TAPE	128 THROUGH 1k	32-BIT ECC			
	RAMTRAC 6217B	MULTIFUNCTION (WINCHESTER/ FLOPPY/TAPE)	ST506 (WINCHESTER), SA850 (FLOPPY), QIC-02 (TAPE)	2 WINCHESTERS, 2 FLOPPIES, 1 TAPE	128 THROUGH 1k	32-BIT ECC			
	RAMTRAC 7217B	MULTIFUNCTION (WINCHESTER/ FLOPPY/TAPE)	SA1000 (WINCHESTER), SA850 (FLOPPY), QIC-02 (TAPE)	2 WINCHESTERS, 2 FLOPPIES, 1 TAPE	128 THROUGH 1k	32-BIT ECC			
SCIENTIFIC MICRO SYSTEMS	FWD 8001	MULTIFUNCTION (WINCHESTER/ FLOPPY)	SA1000 (WINCHESTER), SA850 (FLOPPY)	2 WINCHESTERS, 2 FLOPPIES	128 THROUGH 1k	32-BIT ECC			
	FWD 8006	MULTIFUNCTION (WINCHESTER/ FLOPPY)	ST506, SA850/450	2 WINCHESTERS, 2 FLOPPIES	128 THROUGH 1k	32-BIT ECC			
	FWD 8007	MULTIFUNCTION (WINCHESTER/ FLOPPY/TAPE)	ST506 (WINCHESTER), SA850/450 (FLOPPY), QIC-02 (TAPE)	2 WINCHESTERS, 2 FLOPPIES, 1 TAPE	128 THROUGH 1k	32-BIT ECC			
	FWD 8008	MULTIFUNCTION (WINCHESTER/ FLOPPY/TAPE)	ESDI (WINCHESTER), SA850/450 (FLOPPY), QIC-02 (TAPE)	2 WINCHESTERS, 2 FLOPPIES, 1 TAPE	128 THROUGH 1k	32-BIT ECC			
WESPERCORP	MB-QIC-2	TAPE ONLY (1/4-IN. CARTRIDGE)	QIC-02	4 TAPE DRIVES	512 BYTES	N/A (IN THE FORMATTER			
	MB-SMD	WINCHESTER ONLY (8- OR 14-IN.)	SMD (2.1M BYTES/SEC)	4 WINCHESTERS	PROGRAM- MABLE	32-BIT ECC			
	MB506/1000	MULTIFUNCTION (WINCHESTER/FLOPPY)	SA1000/ST506 (WINCHESTER), SA450 (FLOPPY)	3 WINCHESTERS, 4 FLOPPIES	128 THROUGH 1k	32-BIT ECC			
XYLOGICS	472	TAPE ONLY (9 TRACKS)	PERTEC	8 TAPE DRIVES	TO 2k	N/A (IN THE FORMATTER			
	450	WINCHESTER ONLY (8- OR 14-IN.)	SMD (1.9M BYTES/SEC)	4 WINCHESTERS	128 THROUGH 1k	32-BIT ECC			
	421	MULTIFUNCTION (WINCHESTER/TAPE)	ST506 (WINCHESTER), QIC-02 (TAPE)	2 WINCHESTERS, 4 TAPES	256 THROUGH 1k	32-BIT CRC			
	422	MULTIFUNCTION (WINCHESTER/TAPE)	ESDI (1.2M BYTES/SEC), QIC-02 (TAPE)	2 WINCHESTERS, 4 TAPES	256 THROUGH 1k	32-BIT ECC			
the state of the s	451	WINCHESTER ONLY (8- OR 14-IN.)	SMD (2.4M BYTES/SEC)	4 WINCHESTERS	256 THROUGH 1k	32-BIT ECC			

Support   Supp				HOST CHARA	CTERISTICS				
11-BIT BURST   N/A   24-BIT   ADDRESSING   N/A   N/A   N/A   1:1   \$1345     11-BIT BURST   N/A   24-BIT   ADDRESSING   N/A   N/A   N/A   1:1   \$1345     11-BIT BURST   N/A   24-BIT   ADDRESSING   N/A   N/A   N/A   1:1   \$1345     11-BIT BURST   TRACK LEVEL   16/20/24-BIT   ADDRESSING   N/A   N/A   N/A   \$1300   ISBC 215/ISBX 218     COMPATIBLE   COMPATIBLE   COMPATIBLE   COMPATIBLE     6-BIT BURST   TRACK LEVEL   16/20/24-BIT   ADDRESSING   N/A   N/A   N/A   \$1200   ISBC 215 COMPATIBLE     6-BIT BURST   TRACK LEVEL   16/20/24-BIT   ADDRESSING   ONE TRACK   N/A   N/A   \$1000   ISBC 214 COMPATIBLE     6-BIT BURST   TRACK LEVEL   16/20/24-BIT   ADDRESSING   ONE TRACK   N/A   N/A   \$1200   ISBC 214 COMPATIBLE     N/A   (N) THE   FORMATTER)   TRACK LEVEL   8/16-BIT   DATA PATH   1.5k   N/A   PROGRAM- MABLE     N/A   (N) THE   DATA PATH   1k   N/A   PROGRAM- MABLE     N/A   (N) THE   ONTA PATH   1k   N/A   PROGRAM- MABLE     N/A   (N) THE   ONTA PATH   1k   N/A   PROGRAM- MABLE     N/A   (N) THE   ONTA PATH   1k   N/A   PROGRAM- MABLE     N/A   (N) THE   ONTA PATH   1k   N/A   PROGRAM- MABLE     N/A   (N) THE   ONTA PATH   1k   N/A   PROGRAM- MABLE     N/A   (N) THE   ONTA PATH   1k   N/A   PROGRAM- MABLE     N/A   (N) THE   ONTA PATH   1k   N/A   PROGRAM- MABLE     N/A   (N) THE   ONTA PATH   2k   (ONTONAL)   3M-BPS DMA   1:1   S2295     N/A   (N) THE   ONTA PATH   2k   ONTONAL   3M-BPS DMA   1:1   S1995     N/A   (N) THE   ONTA PATH   2k   ONTONAL   S1995 DMA   1:1   S1995     N/A   (N) THE   ONTA PATH   S1995   SECTOR LEVEL   N/A   4k (DISK), 512 (TAPE)   2.5M-BPS DMA   1:1   S1995     N/A   N/A   S1995 DMA   1:1   S1995     N/A   N/A   S1995 DMA   1:1   S1995     N/A   N/A   S1995 DMA   1:1   S1995     N/A   ONTA PATH   S1995 DMA   1:1   S1995     N/A   ONTA PATH   S1995 DMA   1:1   S1995     N/A   S1995 DMA   S1995 DMA		2 10 10 10 10 10 10 10 10 10 10 10 10 10	at the control of the	BUFFER	TRANSFER			COMMENTS	
ADDRESSING   AND ADDRESSING	11-BIT BURST	N/A		N/A	N/A	1:1	\$1375		
6-BIT BURST TRACK LEVEL 16/20/24-BIT ADDRESSING N/A N/A N/A \$1300 ISBC 215/ISBX 218 COMPATIBLE 6-BIT BURST TRACK LEVEL 16/20/24-BIT ADDRESSING N/A N/A N/A \$1200 ISBC 214 COMPATIBLE 6-BIT BURST TRACK LEVEL 16/20/24-BIT ADDRESSING ADDRESSING ADDRESSING ADDRESSING ADDRESSING N/A N/A S1200 ISBC 214 COMPATIBLE  N/A (IN THE FORMATTER) PATCH ADDRESSING AND ADDRESSING ADDRESSING AND AND AND ADDRESSING AND AND ADDRESSING AND AND AND ADDRESSING AND AND AND ADDRESSING AND	11-BIT BURST	N/A		N/A	N/A	1:1	\$1345		
COMPATIBLE  6-BIT BURST CORRECTION  TRACK LEVEL  16/20/24-BIT ADDRESSING 6-BIT BURST TRACK LEVEL  16/20/24-BIT ADDRESSING 6-BIT BURST TRACK LEVEL  16/20/24-BIT ADDRESSING 6-BIT BURST TRACK LEVEL  16/20/24-BIT ADDRESSING N/A	11-BIT BURST	N/A		N/A	N/A	1:1	\$1345		
CORRECTION		TRACK LEVEL		N/A	N/A	N/A	\$1300		
6-BIT BURST TRACK LEVEL 16/20/24-BIT ADDRESSING ONE TRACK N/A N/A \$1200 ISBC 214 COMPATIBLE  N/A BLOCK REWRITES DATA PATH DATA PATH  11-BIT BURST TRACK LEVEL B/16-BIT DATA PATH  N/A BLOCK REWRITES DATA PATH  11-BIT BURST TRACK LEVEL B/16-BIT DATA PATH  N/A BLOCK REWRITES DATA PATH  N/A BLOCK REWRITES DATA PATH  N/A BLOCK REWRITES ADDRESSING 2k OPTIONAL)  N/A (IN THE FORMATTER)  11-BIT BURST SECTOR LEVEL 16/20/24-BIT ADDRESSING (BK OPTIONAL)  11-BIT BURST N/A N/A N/A N/A SECTOR LEVEL N/A AK (DISK), 512 (TAPE)  11-BIT BURST SECTOR LEVEL N/A 4k (DISK), 512 (TAPE)  11-BIT BURST SECTOR LEVEL 16/20/24-BIT (TAPE)  11-BIT BURST SECTOR LEVEL N/A 4k (DISK), 512 (TAPE)  11-BIT BURST SECTOR LEVEL 16/20/24-BIT (TAPE)  11-BIT BURST SECTOR LEVEL 16/20/24-BIT 2k 3M-BPS DMA 1:1 \$1695  11-BIT BURST SECTOR LEVEL 16/20/24-BIT 2k 3M-BPS DMA 1:1 \$1795  11-BIT BURST SECTOR LEVEL 16/20/24-BIT 2k 3M-BPS DMA 1:1 \$1795		TRACK LEVEL		N/A	N/A	N/A	\$1200	iSBC 215 COMPATIBLE	
N/A	6-BIT BURST	TRACK LEVEL		N/A	N/A	N/A	\$1000	ISBC 214 COMPATIBLE	
TRACK LEVEL   B/16-BIT   DATA PATH   DAT	6-BIT BURST	TRACK LEVEL		ONE TRACK	N/A	N/A	\$1200	iSBC 214 COMPATIBLE	
11-BIT BURST   TRACK LEVEL   8/16-BIT   DATA PATH   1.5k   N/A   PROGRAM-MABLE   \$2100   ISBC 220 COMPATIBLE	(IN THE			2k	N/A	N/A	\$890	er i State en anne State en antante, a primaren a en en State et de Paris State et State et de State	
N/A		TRACK LEVEL		1.5k	N/A		\$2100	ISBC 220 COMPATIBLE	
N/A	11-BIT BURST	N/A		1k	N/A		\$1060		
11-BIT-BURST	(IN THE				3M-BPS DMA	N/A	\$1695	COUPLER TO	
11-BIT BURST SECTOR LEVEL N/A 4k (DISK), 512 (TAPE) 11-BIT BURST SECTOR LEVEL 16/20/24-BIT 2k 3M-BPS DMA 1:1 \$2495	11-BIT BURST	SECTOR LEVEL			3M-BPS DMA	1:1	\$2295		
11-BIT BURST   SECTOR LEVEL   16/20/24-BIT   2k   3M-BPS DMA   1:1   \$2495	11-BIT-BURST	N/A	N/A		2.5M-BPS DMA	1:1	\$1695		
TI-DIT DONOT   OLOTOTELEVEL   TOTAL TEXT   T	11-BIT BURST	SECTOR LEVEL	N/A		2.5M-BPS DMA	1:1	\$1795		
	11-BIT BURST	SECTOR LEVEL			3M-BPS DMA	1: <b>1</b>	\$2495		

EDN February 6, 1986




# Now 68000 computers cost less, do more.

SBE Multibus computers bring out all the power of the 68000 in a highly adaptable form.

The M68CPU above runs at 10 MHz, accessing 512 KB to 8 MB RAM on companion boards.

This CPU sets a new standard for multi-user, realtime applications. High speed with multi-megabyte memory is now possible because SBE's unique memory management unit eliminates all wait states. It contains 32 independent maps for task sizes from 4 KB to 8 MB, permitting rapid real-time task



control, data analysis, ATE, and other systems

applications. Contains up to 1 MB of dual-ported RAM accessible with no wait states. Has a 16-bit counter/timer and a 24-bit parallel port right on board.

Both fit in almost anywhere. Both are Multibus/IEEE 796 compatible. With two iSBX Multimodule connectors. Two multiprotocol serial I/O ports. And options like a 68010 in place of the 68000.

M68K10 boards available from stock in batches of 100 for \$700. M68CPU's in batches of 100 for \$1050. We can offer these super competitive prices because we manufacture in-house, in volume. And we offer on-going software support hard to find elsewhere. All from SBE, Inc., 2400 Bisso Lane, Concord. California 94520. TWX 910-366-2116.

Phone free 800-221-6458 for literature mailed today. In California call (415) 680-7722.



# Basic programs solve differential equations quickly

Differential equations that describe the performance of various devices can be difficult to solve, but you can convert them to integral equations and let a small computer solve them with Basic-language programs.

Ron Rippy, National Institute of Environmental Health Sciences

Obtaining analytical solutions to differential equations that describe devices such as electronic filters and shock absorbers can be difficult or even impossible. However, by using your computer's ability to run short, repetitive routines quickly, you can obtain very close approximations to most differential equations. To solve a differential equation, you first convert the equation into integral form and then let the computer sum the area under the equation's curve by rectangular integration (Ref 1).

For example, a resistor and capacitor form a classic integrator circuit (**Fig 1**) whose performance can be described by a differential equation. The circuit produces a slowly increasing output voltage ( $E_0$ ) after you connect the input voltage ( $V_0$ ) to the circuit. A differential equation describes the circuit's transfer function, or the ratio between the two voltages:

$$\frac{E_0}{V_0} = \frac{1}{sRC + 1}.$$
 (1)




Fig 1—A simple RC circuit provides an example that lets you explore the use of Basic programs to solve differential equations.

In Eq 1, s indicates a differential with respect to time. The term  $sE_0$ , for example, would represent  $dE_0/dt$ . Conversely, the notation 1/s represents an integral with respect to time, so  $E_0/s$  would represent  $\int E_0 dt$ .

The s terms let you quickly rearrange the equation and solve it for one unknown. Because you want to find out how the integrator's output voltage,  $E_0$ , changes after you close the switch, you rearrange  $Eq\ 1$  and solve it for the highest order differential term,  $sE_0$ . All the lower-order equation terms go on the right side:

$$sE_0 = -\frac{1}{RC} E_0 + \frac{1}{RC} V_0.$$
 (2)

To convert from a differential to an integral equation, divide each side of the equation by the highest order s term you find on the left side of the equation. In **Eq 2**, the highest order s term is simply s, so dividing each

# Algorithms solve differential equations by applying numerical integration.

term on both sides of the equation by s yields

$$E_0 = -\frac{1}{RC} \frac{1}{s} E_0 + \frac{1}{RC} \frac{1}{s} V_0.$$
 (3)

Integral equations are relatively easy for a computer to solve because they involve repetitive addition operations that the computer does with software loops. To solve **Eq** 3 and produce values of  $E_0$  as it changes with respect to time, your program must include a statement like

$$E1 = T*E0 + E1$$

in a short DO or FOR-TO program loop. The program statement maintains a running sum (E1) of the output voltage. This running sum closely approximates the integral of the output voltage.

In effect, the program uses a rectangular-integration technique that finds the area under the  $E_0$  vs t curve by breaking the curve into narrow rectangles. The program calculates the area of each rectangle in the  $T^*E_0$  step and adds the area to the running total,  $E_1$ . Keep in mind that rectangular integration doesn't give you an exact solution for an integral equation. To keep errors small, choose a short time interval (t, or T in the program code) for the integration program step so that the integrator circuit's output voltage  $E_0$  won't change greatly during the interval.

Because **Eq** 3 contains two 1/s, or integral, terms—one for  $E_0$  and one for  $V_0$ —you must include two summation steps in your program:

$$E1=T*E0+E1$$
  
 $V1=T*V0+V1$ 

By substituting E1 for  $E_0$ /s and V1 for  $V_0$ /s in Eq 3, you get the new output voltage from a third program line:

$$E0 = -1/RC*E1 + 1/RC*V1$$

In other words, the integrator circuit's output voltage equals a constant (-1/RC) times the first integral of the output voltage, added to another constant (1/RC) times the first integral of the input voltage. The program in **Listing 1** solves the differential equation—now in integral form—and plots the results (**Fig 2**). The computer plot shows the results you'll obtain for sample intervals (T) of 0.5 and 0.05 sec.

The result for the 0.5-sec integration period isn't accurate because the integrator circuit's output voltage, E<sub>0</sub>, varies considerably during this period. When

you specify 0.5-sec periods, however, the computer requires only seven passes through the program loop between lines 1040 and 1090. In complex programs you can use longer intervals to check your program and obtain rough results quickly.

Note that the program in **Listing 1** calculates the E1 value and uses it immediately to calculate E0. The V1 calculation, however, takes place later in the loop, and its value isn't used until the computer makes its next pass through the loop. By calculating V1 later in the loop, you ensure that the voltage across the capacitor is 0V at the start of the program, a practice learned from experience.

When the sample intervals are small, you can have the computer calculate V1 before it calculates E0. When you use large sample intervals, however, the order is important. For example, if you choose an

#### LISTING 1

```
1000 E0,E1,V1=0 @ V0,R,C=1
1010 SCALE 0,3,0,1
1020 XAXIS 0, .5 @ YAXIS 0, .25
1030 MOVE 0,0 @ T=.5
1040 FOR X=0 TO 3 STEP T
1050 E1=T*E0+E1
1060 E0=-(1/R*C*E1)+1/R*C*V1
1070 V1=T*V0+V1
1080 DRAW X,E0
1090 NEXT X
1100 END
```




Fig 2—A plot of  $E_0$  vs t for an RC circuit illustrates that sample-interval selection influences the output-voltage calculation. Long sample intervals provide poor approximations for the rectangular-integration method.

interval of 0.5 sec and program the computer to calculate V1 before it calculates E0, the computer plots a 0.5V output from the circuit as soon as you close the switch—a condition you know can't exist.

By reducing the sample interval to 0.05 sec, you improve the accuracy of the numerical integration because  $E_0$  changes only slightly during each integration period. When you use a 0.05-sec period, the calculated result closely approximates the differential equation's exact mathematical solution,  $E_0=1-e^{-t/RC}$ . After one second, the accuracy of the results for sample intervals of 0.5, 0.05, and 0.005 sec is 18.6%, 1.49%, and 0.146%, respectively.

#### Solve multiple integrations

The RC integrator circuit requires only a single integration of variables. Equations that require two integrations are slightly more complex. Consider an RLC filter circuit (Fig 3) that requires a second-order differential equation to describe its transfer function:

$$\frac{E_0}{V_0} = \frac{1}{LCs^2 + \frac{L}{R}s + 1}.$$
 (4)

The equation calculates the ratio of the input and output voltages after you close the switch and apply voltage to the circuit. With  $\omega$  standing for the filter's natural frequency (W in the program code), use the relationships  $\omega=1/\sqrt{LC}$  and  $Q=\omega\cdot R\cdot C$  to simplify Eq 4 and put the highest order derivative term,  $s^2E_0$ , on the left:

$$s^{2} E_{0} = -\frac{\omega}{Q} sE_{0} - \omega^{2} E_{0} + \omega^{2} V_{0}.$$

Then divide each side of the equation by s2 to yield

$$E_0 = -\frac{\omega}{Q} \frac{1}{s} E_0 - \omega^2 \frac{1}{s^2} E_0 + \omega^2 \frac{1}{s^2} V_0.$$
 (6)

Now the original second-order differential equation is in integral form, and you can use your computer to solve it. You must, however, calculate both the first and second integral of  $E_0$ . Calculate the first integral of  $E_0$  the same way you calculated it in the program for the RC integrator circuit and then integrate the result to give the second integral of  $E_0$ :

$$E1=T*E0+E1$$
  
 $E2=T*E1+E2$ 




Fig 3—A typical RLC filter circuit provides an example of a circuit that requires two integration steps to calculate its output voltage.

Calculate the second integral of V<sub>0</sub> the same way:

$$V1=T*V0+V1$$
  
 $V2=T*V1+V2$ 

Once you calculate E1, E2, and V2, substitute those values into Eq 6 and calculate E<sub>0</sub>. Your computer program requires an equivalent summation step to calculate E0:

$$E0 = -W/Q*E1-W*W*E2+W*W*V2$$

You can calculate the second integral of  $V_0$  before or after the summing equation, but placing the calculation after the equation assures you that the program starts with a value of 0V across the output capacitor. The complete Basic program (**Listing 2**) includes the calculations for E1, E2, V1, V2, and E0. When you run the program, the computer calculates and plots a damped sine wave (**Fig 4**) as the filter circuit's output.

When you close the switch, the RLC filter circuit

#### **LISTING 2**

2000 EØ,E1,E2,V1,V2=0 @ VØ=1
2010 W=1 @ Q=5
2020 SCALE Ø,7\*PI,Ø,2
2030 XAXIS 1,PI/2 @ YAXIS Ø,.5
2040 MOVE Ø,0 @ T=.05
2050 FOR X=0 TO 7\*PI STEP T
2060 E1=T\*EØ+E1
2070 E2=T\*E1+E2
2080 EØ=-(W/Q\*E1)-W\*W\*E2+W\*W\*V2
2090 V1=T\*VØ+V1
2100 V2=T\*V1+V2
2110 DRAW X,EØ
2120 NEXT X
2130 END

Use your computer's ability to run repetitive routines that closely approximate most differential equations.




Fig 4—A damped sine wave or ringing signal results when you run the program in Listing 2.

responds to the 1V signal by generating a damped sine wave or ringing signal with a 1-radian/sec frequency. You can test the circuit's response to other input voltages by substituting different values for V0 in the program. Instead of using a fixed voltage for V0 in the program, you can include an equation that calculates V0 voltages that vary with time.

As a final example of the integration technique, consider a tracking filter circuit (Fig 5) that locks onto an input signal and tracks changes in frequency, as long as they aren't too great and don't take place too quickly. Tracking filters correct Doppler shifts that arise in signals from communication satellites.

The filter tracks and cancels the slowly changing Doppler shifts caused by the satellite's orbital motion. The network passes high-frequency data-communication signals because the lowpass filter prevents them from generating a correcting feedback voltage. However, the filter passes low-frequency signals and generates a feedback voltage that corrects the input signal. The feedback circuit is a third-order lowpass filter.

The tracking filter's transfer function is expressed in the following equation:

$$\frac{E_0}{V_0} = \frac{s^3}{s^3 + 2\omega s^2 + 2\omega^2 s + \omega^3}$$

To solve the filter's transfer function, first rearrange it so that it expresses  $E_0$  as the highest order differential




Fig 5—A third-order tracking filter generates a feedback voltage that cancels slow variations in the input signal. The circuit is useful in tracking communication-satellite signals that are subject to the Doppler effect.

on the left side of the equation:

$$s^{3}E_{0} = -2\omega s^{2}E_{0} - 2\omega^{2}sE_{0} - \omega^{3}E_{0} + s^{3}V_{0}.$$

Next, divide each side of the equation by  $s^3$  to solve for  $E_0$ , and transform the equation into integral form:

$$E_0 = -2\omega \frac{1}{s} E_0 - 2\omega^2 \frac{1}{s^2} E_0 - \omega^3 \frac{1}{s^3} E_0 + V_0.$$
 (9)

To solve Eq 9 and compute values of  $E_0$ , you must write a program that calculates the first, second, and third integrals of  $E_0$ .


E1=T\*E0+E1 E2=T\*E1+E2 E3=T\*E2+E3 E0=-2\*W\*E1-2\*W\*W\*E2-W\*W\*W\*E3+V0

The complete program (**Listing 3**) presets the filter's natural frequency (W) to 1 radian/sec.

When you close the switch, you create an error signal

#### LISTING 3

3000 E0,E1,E2,E3=0 @ V0,W=1
3010 SCALE 0,8,-.5,1.5
3020 XAXIS 0,1 @ YAXIS 0,.1
3030 MOVE 0,0 @ T=.05
3040 FOR X=0 TO 8 STEP T
3050 E1=T\*E0+E1
3060 E2=T\*E1+E2
3070 E3=T\*E2+E3
3080 E0=-(2\*W\*E1)-2\*W\*W\*E2-W\*W\*E3+V0
3090 DRAW X,E0
3100 NEXT X
3110 END



How can you be sure you're getting the best wire—the right wire—for all your transmission needs? Specify AT&T wire.

Because nobody gives you AT&T's years of experience and understanding in designing wiring for transmission and computer systems. And, nobody can give you all of AT&T's product innovations, such as dual foam insulation for greater data transmission rates;

irradiated PVC for tougher wire protection; and low friction vinyl jackets for pulling wire through tight spaces. And, nobody gives you AT&T's experts, who will work with you to match the right insulation, shield and sheath to optimize the performance of your wire.

So why make choosing wire an adventure when you can be sure? Make "The right choice." Call 1800 372-2447 for more

information about AT&T's full line of wire and cable products for premise distribution and peripheral connections. © 1985 AT&T Technologies, Inc.



## smallest



# Faraday delivers the Micro PC.™ A single board computer with the capabilities of the IBM® PC but only 3.9 x 5.5 inches in size.

With the Faraday Micro PC, you can imbed the power of the IBM PC into thousands of new applications. The Micro PC features:

 Plug-in card ■ ROM BIOS on board ■ 8088 processor with optional 8087 co-processor ■ 256K RAM memory ■ 32K ROM memory ■ CMOS version optional ■ 4.77 mhz

You can depend on Faraday to deliver 100% PC BUS compatibility. We supply OEMs in telecommunications, office automation, industrial automation, instrumentation, manufacturing test equipment, medical instruments, point of sale, computer terminals and personal computing applications.

For more information on the Micro PC or other Faraday PC BUS single board computers, call us at 408-749-1900.

Faraday Electronics, 743 Pastoria Avenue, Sunnyvale, California 94086, TLX 706738.



Faraday quality at 1/5 the size.

IBM is a registered trademark of International Business Machines Corporation.

Micro PC is a trademark of Faraday Electronics.

**CIRCLE NO 76** 




Fig 6—A plot of output and feedback voltages for a tracking filter illustrates how a short computer program (Listing 3) simulates complex filter behavior.

of 1V, or an input-signal phase error of 1 radian. The filter counteracts the 1V error by applying an equal and opposite voltage (VF) to the input signal. The filter can't act instantaneously, however, and it must conform to the time constraints of the filter circuit. Consequently, at first  $E_0$  equals  $V_0$ , and the filter's feedback voltage is 0V. The feedback voltage increases, however, and eventually cancels the error voltage (Fig 6), thereby tracking the error voltage.

#### Author's biography


Ron Rippy is an electronic engineer with the Laboratory of Molecular Biophysics at the National Institute of Environmental Health Sciences in Research Triangle Park, NC. Ron designs and maintains nuclear magnetic resonance (NMR) spectrometers and has 22 years of experience in designing RF circuits and in programming computers. He enjoys programming a VAX computer at work and includes reading among his leisure activities.



#### Reference

1. Cushman, R, "Digital simulation techniques improve μP-system designs," *EDN*, January 7, 1981, pg 142.

Article Interest Quotient (Circle One) High 476 Medium 477 Low 478



When Carroll Touch, Inc. decided to redesign its line of touch input products, it had two major goals. One was to reduce the number of parts by 50 percent. Which meant Carroll Touch™ could drastically cut its manufacturing costs. And lower its price in the market.

The second goal was to build in an abundance of flexibility in a base product. This would allow Carroll Touch to expedite orders for custom systems. As well as respond to rapid changes in its market.

Carroll Touch achieved both of these goals when it unveiled its first model of the Smart-Frame™ scanning infrared touch input system. And the key ingredient was Motorola's MC68705R3 microcomputer.

The MC68705R3 with its built-in EPROM gave the new Smart-Frame unprecedented flexibility. Special features could be added or changed by reprogramming Motorola's MCU instead of replacing it.

Because the MC68705R3 is a full-function microcomputer, most I/O support chips were eliminated. And many functions previously handled by task-specific hardware could now be handled by Motorola's MCU through software.

Motorola also satisfied the stringent requirements for reliability. Serviceability. And price. The MC68705R3 costs significantly less than its closest competitor. Yet its functionality and overall performance are significantly greater.

Fewer parts. More flexibility. Higher performance. The successful blending of two advanced technologies.

Together Motorola and Carroll Touch are putting touch technology within reach.









# FINELY TUNED FOR DIGITAL TEST

Flexibility that only comes from experience: The RS-670 40 MHz Digital Word Generator.

If you're going to use a logic analyzer module, or custom circuitry, or a rack of pulse generators, consider the RS-670 instead. It provides speed, flexibility and performance: On-board floppy to store test routines • Unique clock periods for tables • Dynamic tristate control • Data rates to 40 MHz • Up to 64 channels, each with 4K bits of memory • Table and looping capability • Parallel or serial operation • 128K bits of serial memory • Remote control by any host computer.

The RS-670 is our fourth generation digital word generator. We've

made each one better and easier to use, without the price associated with high speed electronics, but with the capability to handle the most diverse applications easily.

Let a hands-on demo prove it. Just call (818) 914-2741 today to arrange for a demo and finetune your own test program.




Interface Technology, 2100 East Alosta Avenue, Glendora, CA 91740. TLX: 4945489.

Interface TECHNOLOGY

UK: Microsystem Services, (0494) 41661; GERMANY: Instrumatic Electronic, (089) 85 20 63 FRANCE: MB Electronique, 956 81 31; ITALY: Vianello, (02) 6596171; JAPAN: TET, Ltd., 0425-73-1295

**CIRCLE NO 78** 



## Floating-point µP implements high-speed math functions

This final article in a 3-part series describes how to incorporate a floating-point processor into your system. It discusses criteria for the selection of the algorithms you'll use, and in particular it details the methods used to implement transcendental functions.

#### David Quong, Advanced Micro Devices

If your application must perform a variety of math functions at high speeds on a wide range of input data, consider designing a math subsystem based upon a VLSI floating-point processor. A floating-point processor, a microsequencer, RAM, and ROM, configured as shown in Fig 1, together with the appropriate algorithms, will allow you to perform most math functions at real-time speeds with high precision and a very large dynamic range. A system of this type will outperform even the fastest floating-point coprocessor.

The choice of algorithms is an important step in the realization of your math processor. You can choose from a variety of methods for implementing transcendental and other math functions: The Taylor series, the Chebyshev series expansion, and the Newton-Raphson approximation are just a few of the many possible approaches. Which algorithm is the best one for your particular application will depend upon what functions you want to perform, the hardware architecture you are

using, and the system throughput and accuracy you expect to receive.

Many designers select the Taylor series for performing math functions. This well-known method allows you to find equations for various functions in most books of math tables. The Taylor series has a major drawback, however: It has a nonuniform convergence rate in the number of terms needed to achieve a desired accuracy. Consider, for example, the Taylor series expansion of the sine function:

$$\sin(x) = x - \frac{x^3}{3!} + \frac{x^5}{5!} - \frac{x^7}{7!} \dots$$

For values of x near zero radians, this equation converges very quickly, but as x becomes larger, you'll need a larger number of terms to evaluate  $\sin(x)$  to the same accuracy that you obtained for the smaller values.

The Chebyshev expansion method, like the Taylor method, produces a polynomial approximation, but it's not so well known. The generation of the Chebyshev approximation for a particular function is more complex than for the Taylor series, but the resulting polynomial is just as easy to implement. The major advantage of the Chebyshev method is that it has uniform convergence. Moreover, for any given function, over the operating range of the Chebyshev series this method yields smaller errors than almost any other method. You can usually determine by inspection the upper bound of the error; the error of the truncated series

A math-processing subsystem incorporating a VLSI floating-point processor will outperform even the fastest available floating-point coprocessor.

cannot exceed the sum of the absolute values of the remaining Chebyshev coefficients. (For details of the derivation of the Chebyshev series, see box, "Deriving a Chebyshev series.")

#### Iteration handles simple functions

For some simple functions such as division and square-root extraction, the Newton-Raphson method, an iterative approach for approximating such functions, works well. When using this or any other iterative method, you have to start with a seed, or initial approximation. The better this approximation is, the faster will be the convergence. You can store predetermined seed values in a look-up table. This method usually requires extra hardware (in the form of ROMs), but it gives you flexibility, because you can store seed values that are as accurate as you want.

The chief attraction of the Newton-Raphson method is its rapid convergence; the number of iterations required is low. The method converges quadratically,

ie, the order of the error is squared by each iteration. For example, if the seed is accurate to eight bits, the first iteration improves the accuracy to 16 bits, and the second iteration improves it to approximately 32 bits (variance depends on the magnitude of the error).

The math processor shown in Fig 1 evaluates Chebyshev and Newton-Raphson approximations very efficiently. The system performs transcendental (trigonometric, logarithmic, and exponential) functions by the Chebyshev method and division and square-root extraction by the Newton-Raphson method.

#### Understand the algorithms

The algorithms for 10 very common math functions are described below. You'll need these functions for applications associated with navigation, guidance, image processing, signal processing, and many other areas. The algorithms for the transcendental functions are based on the Chebyshev method and consist of a 3-stage process. The first stage reduces the range of




Fig 1—This math subsystem is based on a VLSI floating-point processor. It performs math functions with high precision and a large dynamic range.

#### Deriving a Chebyshev series

The Chebyshev series expansion is a procedure for generating a polynomial approximation for a given math function, f(x). To expand the function, you must express it as a Chebyshev series:

$$f(x)=0.5C_0+C_1T_1(x)+C_2T_2(x)+...$$

for  $-1 \le x \le 1$ , where  $T_n(x)$  is the Chebyshev polynomial of degree n given by

$$T_n(x) = \cos(n \times a\cos(x))$$

and  $C_n$  is a coefficient of the Chebyshev series. The value of  $C_n$  is dependent upon the function f(x). You can determine the value of  $C_n$  by evaluating the following relationship:

$$C_n = \frac{2}{\pi} \int_{-1}^{+1} \frac{f(x) T_n(x)}{\sqrt{1 - x^2}} \delta x.$$

Alternatively, you can obtain the  $C_n$  coefficients in tabular form, for a wide variety of functions, from books on mathematical tables (**Ref 2**).

Examples of the T<sub>n</sub>(x) polynomial include the following:

$$\begin{split} T_0(x) &= \cos(0) = 1 \\ T_1(x) &= \cos(a\cos(x)) = x \\ T_2(x) &= \cos(2a\cos(x)) \\ &= 2\cos^2{(a\cos(x))} \\ &= 2x^2 - 1. \end{split}$$

You can generate a polynomial equation for a function by combining the above equations and combining terms with common exponents. The accuracy of the result depends

upon the number of terms you use. (If you are interested in a formal derivation of the Chebyshev method, see **Refs 1** and **2**.)

#### **Expansion for sine function**

If you want to find the Chebyshev expansion for the sine function, first go to the coefficient tables in Ref 2 and look up the coefficients for the sine function (or calculate them from the formula given above). Next, determine the number of coefficients required to provide the accuracy you want. For example, to achieve 24 bits of accuracy, the error should be no greater than one part in 17 million. Compare the magnitude of this largest acceptable error with each of the coefficients. The first term that contains a coefficient that's less than the error can be the last term in the series. It's common practice, however, to include one extra term in the series.

Using the above criteria, you need only six coefficients for the sine function using  $\sin(\frac{1}{2}\pi x)$  in order to obtain a result that's accurate to 24 bits. These coefficients are

- $\bullet$   $C_0 = C_{sin0} = +2.552557925$
- $\bullet$   $C_1 = C_{sin1} = -0.285261569$
- $\begin{array}{c} \bullet \quad \text{C}_2 = \text{C}_{\sin 2} = +9.118016007 \\ \times 10^{-03} \end{array}$
- $\begin{array}{c} \bullet \quad C_3 = C_{sin3} = -1.365875135 \\ \times 10^{-04} \end{array}$
- $\begin{array}{c} \bullet \quad C_4 = C_{sin4} = +1.184961858 \\ \times 10^{-06} \end{array}$
- $C_5 = C_{\sin 5} = -6.702792 \times 10^{-09}$

Substituting the T<sub>n</sub>x polynomials into the Chebyshev series gives

$$\begin{aligned} \sin(\frac{1}{2}\pi x) &= \\ 0.5C_0 + C_1x + C_2(2x^2 - 1) \\ + C_3(4x^3 - 3x) \\ + C_4(8x^4 - 8x^2 + 1) \\ + C_5(16x^5 - 20x^3 + 5x). \end{aligned}$$

Simplifying the terms gives

$$\sin(\frac{1}{2}\pi x) = a_0 + a_1 x + a_2 x^2 + a_3 x^3 + a_4 x^4 + a_5 x^5.$$

where

- $\bullet$  a<sub>0</sub>=(0.5)C<sub>0</sub>-C<sub>2</sub>+C<sub>4</sub>
- $a_1 = C_1 3C_3 + 5C_5$
- $a_2 = 2C_2 8C_4$
- $a_3 = 4C_3 20C_5$
- $a_4 = 8C_4$
- $a_5 = 16C_5$ .

The final result for the sine function is a simple polynomial equation that you'll find easy to implement. You can precalculate the coefficients  $a_0$  through  $a_5$  and store them in a ROM table. You can apply the same procedure to any well-behaved function for which you can find or compute the Chebyshev coefficients.

The Chebyshev expansion method, like the Taylor method, produces a polynomial approximation, but it's not so well known.

the input arguments to values between +1 and -1, because the Chebyshev expansion operates only over this range. The second stage evaluates the polynomial derived from the Chebyshev expansion. The third stage performs any postprocessing that may be required, such as correction of the sign.

The detailed descriptions were developed by Clenshaw, Miller, and Woodger (Ref 1). They use the terms RND and CSERIES: RND indicates that the result of the operation must be rounded towards minus infinity, and CSERIES indicates that the Chebyshev series for the input must be evaluated.

#### Range reduction prepares arguments

The range-reduction steps for the sine function are

- $\bullet$   $x=x(2/\pi)$
- x=x-(4(RND(0.25(x+1))))
- If x>1 then x=2-x.

As noted, these steps reduce the input argument to the range  $-1 \le x \le 1$ . You then evaluate the sine function by summing the terms of the following polynomial equation derived for the sine function:

$$\sin(x) = x(CSERIES_{\sin}(2x^2-1)).$$

The range-reduction steps for the cosine function are

- $\bullet$   $x=x(2/\pi)$
- x=4(RND(0.25(x+2)))-x+1
- If x>1 then x=2-x.

You then evaluate the cosine function by using the same polynomial equation as for the sine function:

$$\cos(x) = x(CSERIES_{sin}(2x^2-1)).$$

The range-reduction steps for the tangent function are

- $x=x(2/\pi)$
- x=x-(4(RND(0.25(x+1))))
- $\bullet$  y=x
- If x>1 then x=2-x.

The Chebyshev polynomial evaluation for the tangent function is

$$tan(x) = x(CSERIES_{tan}(2x^2-1)).$$

You have to perform one postprocessing step:

If 
$$y>1$$
 then  $tan(x)=1/tan(x)$ .

You don't need any range-reduction steps for the

arcsine function, because all values outside the range  $-1 \le x \le 1$  indicate an error condition. For input arguments in the range  $x^2 \le \frac{1}{2}$ , you evaluate the arcsine as follows:

$$a\sin(x) = x(\sqrt{2}(CSERIES_{asin}(4x^2-1))).$$

For input arguments in the range  $\frac{1}{2} < x^2 \le 1$ , you evaluate the arcsine as follows:

$$asin(x) = sign(x)(\pi/2)(\sqrt{2-2x^2})(CSERIES_{asin}(3-4x^2)),$$

where sign(x) is the sign of x.

You use the following trigonometric identity to evaluate the arc-cosine function:

$$a\cos(x) = \pi/2 - a\sin(x)$$
.

The range-reduction steps for the arctangent function are

- 11=x
- If ABS(x)>1 then x=1/x,

where ABS(x) is the absolute value of x. The Chebyshev polynomial evaluation is

$$atan(x) = x(CSERIES_{atan}(2x^2-1)).$$

The postprocessing steps are

If 
$$u>1$$
 then  $atan(x) = +(\pi/2) - atan(x)$ 

and

If 
$$u < -1$$
 then  $atan(x) = -(\pi/2) - atan(x)$ .

The range-reduction steps for the exponentiation function are

- $x=x(log_2e)$
- N=1+RND(x).

The Chebyshev polynomial evaluation is

$$\exp(x)=2^{N}(\text{CSERIES}_{\exp}(2(N-x)-1)).$$

Only positive values are valid input arguments for the natural-log function; a zero or a negative value should be flagged as an error;

$$ln(x) = (CSERIES_{ln}(4(mant(x))-3)) + (expo(x)-1)(ln(2)),$$

where mant(x) is the mantissa value of x, expo(x) is the exponent value of x, and ln(2) is a constant value.

You perform division operations by evaluating the

reciprocal function. For example, you can express the division operation C=A/B in its reciprocal form, C=A(1/B). By using the Newton-Raphson method, you can find an iterative expression for the reciprocal function. This expression is

$$x_{i+1} = x_i(2 - B(x_i)),$$

where  $x_0$  is the initial divisor reciprocal (seed value) for i=0, and  $X_i$  is the ith approximation.

The square-root function also uses the Newton-Raphson method. The iterative expression for the inverse square-root function is

$$x_{i+1} = 0.5(x_i(3.0 - Ax_i^2)).$$

You then evaluate the square root of A by the equation

$$B = A(x_{i+1}),$$

where A is the input argument, B is the square root of A,  $x_0$  is the initial approximation (seed value) for i=0, and  $x_i$  is the ith approximation.

The principal component of the math-processor subsystem described here is the Am29325 floating-point processor. The subsystem also contains RAM, bipolar PROMs to store coefficients, a subsystem controller, and a host interface. The floating-point processor performs all computations under control of the subsystem controller; microcoded programs to perform the functions you need reside in the subsystem controller's PROM. If you wish to modify existing functions or add new functions, you merely change the microprogrammed PROM.

The Am29325 floating-point processor (Fig 2) provides many features that simplify subsystem design. The 3-port, 32-bit I/O structure of the Am29325 avoids data multiplexing and allows efficient transfer of information. The 32-bit internal registers and data paths allow the chip to store the results of intermediate calculations for use in subsequent operations, thereby avoiding the delays that transfer of these results to and from off-chip storage would entail. Many functions don't need to send data out of the chip until the final results of an operation are ready.

The floating-point-processor hardware detects exceptional conditions and, rather than compounding the error until the end of the calculation, immediately notifies the host system. The chip notifies the host by means of flags that indicate underflow, overflow, inva-




Fig 2—This VLSI floating-point processor is fast because it contains all the major components for 32-bit operations on a single chip. It has one input for an external clock and 17 inputs for instruction-select and control functions.

lid operation, and other error conditions.

Subsystem data storage consists of a high-speed, 4-port RAM. You can load the data memory from the host computer (using DMA), from the floating-point processor, or from an integer processor. You'll need to process integers during operations such as isolating the exponent and mantissa portions of a floating-point word. You can have the host processor perform integer processing, or you can arrange it so that the math subsystem performs the required operations by incorporating an integer processor chip in your design.

#### Learn to microprogram the processor

Two examples of how to implement math functions on the Am29325 floating-point processor will give you an introduction to the microcoding procedures you'll use in the math processor. Recall, that, for a given division operation (C=A/B), the Newton-Raphson division algorithm begins by obtaining the reciprocal of the divisor by means of an iterative equation. A single iteration requires just three arithmetic operations:

- multiplication:  $B(x_i)=u$
- subtraction: 2-u=v
- multiplication:  $v(x_i)=x_{i+1}$ .

You can microcode this procedure with a 3-instruction loop that you repeat until you obtain a sufficiently accurate value of  $x_{i+1}$ . You then perform a single multi-

The math processor uses the Newton-Raphson method to execute the division and square-root functions.

plication,  $A \times x_{i+1}$ , to obtain the quotient.

The conventional way to obtain a seed is to use the most significant 16 or so bits of the divisor as a pointer into a look-up table in ROM; the contents of the address to which the divisor bits point become the seed output, which usually has approximately the same number of bits. You might think that use of a 16-bit address would require a ROM that's 64k words deep, but this is not so. In floating-point division, you can reciprocate the exponent and significand separately, each from its own table, and then recombine them. Consequently, for an 8-bit exponent and the eight most significant bits of the significand, you require only two tables, each just 256 words deep.

You can also trade ROM word width for execution time (ie, the number of iterations); doubling the width of the significand stored in ROM will reduce reciprocal refinement time by roughly one iteration. Convergence is specified by the inequality  $2/B > |x_0| > 0$ .

The microcoding for the complete Newton-Raphson division is shown in **Table 1**. The operation requires six lines of microcode. In cycle 1, you load the seed into register R of the floating-point processor and load the divisor into register S. In cycle 2, you multiply the contents of registers R and S; the result appears in register F.

In cycle 3, you perform the subtraction, using the 2-S instruction of the floating-point processor. The

input for port S comes from register F via the internal feedback path. The result of the subtraction appears in register F.

In cycle 4, you perform the second multiplication. This operation multiplies the contents of register F (via port S) by  $x_i$  (from register R). The result,  $x_{i+1}$ , replaces  $x_i$  in register R. In parallel with the multiplication, the microsequencer executes a jump back to cycle 2 to begin the next iteration.

Cycle 5 begins after the last iteration of cycles 2 through 4. In this cycle, you load the dividend (A) into register S and multiply it by the contents of register R to produce the final result. This result appears in register F, from which you can unload it via the F bus to local data storage or to the host.


The second implementation example uses the Chebyshev method to perform a sine calculation. In the polynomial equation that evaluates the sine function,

CSERIES<sub>sin</sub>=
$$a_0+a_1x+a_2x^2+a_3x^3+a_4x^4+a_5x^5$$
.

The range-reduction steps require eight or nine operations. Evaluation of the polynomial equation requires 23 additional operations, including processing of the  $2x^2-1$  expression. One final operation multiplies the result of the polynomial evaluation by x. The sine function therefore requires 32 or 33 operations.

You can, however, save 10 cycles in the evaluation of

													CE FOF E Am29	
	ı	ł	ı	1		1	1	_	1	.0.0			- AIII2	1
CLOCK CYCLE	10-ALU SELECT	11-ALU SELECT	12-ALU SELECT	13-SMUX CONTROL	14-RMUX CONTROL	ENR-R REG ENABLE	ENS-S REG ENABLE	ENF-F REG ENABLE	OE-OUTPUT ENABLE	ALU OPERATION	CONTENT OF REG R	CONTENT OF REGS	CONTENT OF REG F	COMMENT
	х	х	Х	х	0	0	0	Х	х	x	?	?	?	LOAD B AND SEED INTO Am29325
2	0	1	0	0	X	1	1	0	X	R*S	X(0)	В	?	BEGIN FIRST ITERATION
	1	1	0	1	Х	1	1	0	Х	2-S	X(0)	В	B*X(0)	
CACHE N	0	1	0	1	1	0	0	0	X	R*S	X(0)	В	2-B*X(0)	X(1)=X(0)[2-B*X(0)], LOAD A
	0	1	0	0	Х	1	1	0	X	R*S	X(1)	Α	X(1)	A*X(1), X(1)=1/B
	X	X	X	X	X	X	X	X	0	X	X(1)	A	A*X(1)	OUTPUT RESULT, A/B



March 11-13, 1986 Moscone Convention Center · San Francisco, California

#### WHERE THE FUTURE OF **ELECTRONICS DESIGN BEGINS TODAY.**

By the end of this decade, the majority of IC, logic, and printed circuits will be designed and engineered using CAE and CAD technology. Prepare yourself for the dramatic impact these major technological advances will have on the electronics marketplace.

ADEE™ West '86 is a major conference and exhibition dedicated to helping you learn how to use CAE and CAD tools to design electronic circuits faster and more profitably.

This important event puts you in touch with the nation's leading engineering minds...as well as the major CAE and CAD vendors in the industry.

Complementing the CAE and CAD equipment demonstrations will be a comprehensive technical program designed to enhance your technical awareness and professional advancement.

The ADEE™ West '86 technical program

has been developed by Andrew Rappaport, president of the Technology Research Group, and is divided into the following tracks:

- CAE/CAD Management
- Systems Applications
- Logic, IC, and PC Board Design
- Simulation/Test

For more information on ADEE™ West '86, call (312) 299-9311, or detach and mail the coupon below.

#### Sponsored by



Electronic Technology for **Engineers and Engineering** Managers

#### Endorsed by these leading publications

- Electronic Business
- Design News Electronic Packaging and Production
  - Semiconductor International

**Cahners Exposition Group** 

ADEL THOOL OF LOCALITICAL PROGRA			
Yes, I am interested in attending ADI Please send advance registration information and advance registration information.	EE™ West '86.	the technical	
Yes, I am interested in Please send advance registration in program.	Title		
Name			
CompanyAddress	StateStateCa	_Ziphners Plaza,	
Address  City  Photocopy this coupon for associa	tes who should be should b	EDN 2-6	
Detach and 1350 E. Touhy Avenue, F.O. 1350 E. To			© Reed Holdings, Inc. 1985

The floating-point processor hardware detects exceptional conditions and, rather than compounding the error, immediately notifies the host system.

the polynomial equation by applying Horner's Rule, an algebraic method for rearranging components in a polynomial. The polynomial equation then becomes

CSERIES<sub>sin</sub>=
$$((((a_5x+a_4)x+a_3)x+a_2)x+a_1)x+a_0$$
.

The total number of operations in the sine function then decreases to 22 or 23. Evaluation of the rearranged polynomial equation is complete in 10 clock cycles.

In cycle 1, you load x into the S register and  $a_5$  into the R register. Multiply these two operands to produce  $a_5 \times x$ . In cycle 2, you load the result of the multiplication into the F register, load  $a_4$  into the R register, and add the contents of the F and R registers to yield

$$(a_5 \times x) + a_4$$
.

In cycle 3, you load the result of the addition into the R register; the S register still contains x. Perform R×S to obtain

$$((a_5 \times x) + a_4)x$$
.

Cycles 4 through 10 perform similar addition and multiplication operations, progressively using the terms a<sub>3</sub> through a<sub>0</sub>. The final result of evaluating the polynomial equation is available in the F register after cycle 10.

The ability to perform both simple and complex math functions rapidly is critical in systems that process data in real time. You won't yet find many simple, compact solutions to this problem on the market. Math-coprocessor ICs are available, but they are still in the low-to medium-performance range, and they limit you to a microprocessor environment. (Table 2 shows compara-

tive timings for two floating-point coprocessor chips and the Am29325 floating-point processor.)

You can design and build your own MSI chip, but such a product will require much development time and cost, and it will probably be large and consume lots of power. Another possible approach is to compute the values of the math functions you will need and to store these values in ROM, but such a look-up-table method is adequate only for small amounts of data. At the present time, the use of a math subsystem based upon a VLSI floating-point processor with a relatively small amount of support circuitry appears to be the most cost-effective solution.

#### References

1. Clenshaw, CW, Miller, GF, and Woodger, M, "Algorithms for Special Functions I," *Numerische Mathematik*, Vol 4, 1963, pg 403. See also Miller, GF, "Algorithms for Special Functions II," *Numerische Mathematik*, Vol 7, 1965, pg 194.

2. Clenshaw, C W, "Chebyshev series for mathematical functions," Vol 5 of the Mathematical Tables of the National Physical Laboratory, HM Stationery Office, London, 1962.

#### Author's biography

David Quong is an engineer in the product planning division of Advanced Micro Devices (Sunnyvale, CA). He received a BSEE from California State University at Sacramento, and in his spare time enjoys fishing, hiking, and skiing.

Article Interest Quotient (Circle One) High 479 Medium 480 Low 481

#### TABLE 2—TIMING COMPARISON OF SINGLE-PRECISION FLOATING-POINT FUNCTIONS

							_	
FLOATING-POINT CHIP	SPEED (MHz)	ADD (μSEC)	MULTIPLY (μSEC)	DIVISION (μSEC)	SQUARE ROOT	SINE (µSEC)	COSINE (μSEC)	TANGENT (μSEC)
INTEL 80871	8.0	12.5	18.1	25.4	23.3	NOTE 3	NOTE 3	67.5
MOTOROLA 688812	16.67	2.8	3.1	3.8	N/A	23.0	23.0	27.2
AMD Am29325	8.0	0.125	0.125	1.125	1.625	2.875	3.125	4.750

#### NOTES:

N/A = TIMES NOT AVAILABLE

- 1. TIMES FOR THE INTEL 8087 WERE DERIVED FROM THE INSTRUCTION CLOCK COUNT GIVEN IN THE INTEL DATA PAMPHLET (1984). ALL TIMES LISTED ARE WORST CASE.
- 2. TIMES FOR THE MOTOROLA MC68881 WERE TAKEN FROM A NEWS ITEM IN ELECTRONIC PRODUCTS, FEBRUARY 15, 1985, PG 43.
- 3. THIS OPERATION IS NOT COVERED BY THE INSTRUCTION SET AND MUST BE IMPLEMENTED BY USING OTHER INSTRUCTIONS.

# You don't have to give up a thing to get CMOS.

Full Z80° performance guaranteed—from the company that invented it.

If your Z80 applications are getting too hot to handle, it's time to turn down the wattage. What better source for a low-power CMOS version of your favorite CPU than the company that designed it in the first place? And, nothing has been left out of Zilog's CMOS implementation of the Z80 to give you the low power, low heat, high noise immunity, temperature tolerances and economical packaging that make CMOS technology so attractive.

We plan to stay the leader in 8-bit—in both design and delivery.

The Zilog Z80 family is the most widely second-sourced chip in history. Amazingly, though, there is only one domestic U.S. supplier *committed* to meeting your 8-bit needs both

today and in the future, the first source...Zilog. And, Zilog's implementation of the Z80 is powerful enough to give you the system performance improvement you're looking for without redesigning your application to 16 bits. In fact, ordering your Z80 from us can be the advantage you need when you "just have to have" that reliable low-cost 8-bit engine.

The added value of a full family of compatible peripherals.

There's more. These important peripherals are available in CMOS, too: Parallel I/O (PIO), Counter Timer (CTC), Serial I/O (SIO), Direct Memory Access (DMA) and Clock Generator Controller (CGC).

Zilog
an affiliate of
EXON Corporation

The freedom to specify CMOS or NMOS as best suits your design.

And that's just the

And, that's just the beginning. Zilog customers will soon have the option of specifying CMOS or NMOS versions of every product, 8- or 16-bit, that we make.

Want to know more? It's easy to get all the design and ordering information you need. Simply mail in the coupon or call. Zilog, Components Division, 1315 Dell Avenue, A2-8, Campbell, CA 95008; (408) 370-5992.

Z80 is a registered trader	nark of Zilog, Inc.
information	l me my Zilog CMOS n kit. me. My number is:
Name Title Company	
Address	
City	State/Zip EDN-2/6/86

**CIRCLE NO 161** 

## DON'T LET YOUF'S REFERENCE DRIFT AWAY.




Anchor your system with the LT1021 Precision Voltage Reference and banish drift forever.

The LT1021 is the ultimate calibrated output voltage reference IC for time and temperature stability. Using a subsurface zener, the LT1021 achieves drifts as low as 2ppm/°C maximum. An extremely tight output voltage tolerance of ±0.05% maximum is also available in 5V, 7V and 10V versions.

Operating in either series or shunt mode, the LT1021 reference is ideal for applications involving A/D and D/A converters, digital voltmeters, inertial navigation systems, precision scales, and portable reference standards.

A companion circuit, the LT1019 bandgap reference with thin-film resistors, is offered with

LT1021 Temperature Drift



LINEAR

TOUGH PRODUCTS
FOR TOUGH APPLICATIONS

CIRCLE NO 80

outputs of 2.5V, 5V or 10V. This reference can operate with supplies under 5V and has a temperature sensing output.

Both the LT1021 and LT1019 references are available in standard industry pinout configurations.

Drop anchor on drift with the LT1021 and LT1019 references, or select from our list of 29 other precision references available in both commercial and military grades. 100-piece prices for the LT1021DC/LT1019C in TO-5 packages are \$3.50 each, and \$2.75 each in 8-pin plastic packages. For technical datasheets and a comprehensive guide to our complete reference line contact:

LINEAR TECHNOLOGY CORPORATION, 1630 McCarthy Blvd., Milpitas, CA 95035 (408) 942-0810.

#### **DESIGN IDEAS**

EDITED BY TARLTON FLEMING

#### Use simple circuit to program EPROMs

Richard Poindexter Telex Computer Products, Tulsa, OK

You can program 21V, 28-pin EPROMs (eg, models 2764 or 27128) using a circuit that occupies little space on a pc board (**Fig 1**). The signal interface consists of an 8-bit control word and an 8-bit data bus.

The switching regulator (IC<sub>3</sub>) provides the EPROM's programming voltage by stepping the 5V supply to 21V. The 12-bit binary counter (IC<sub>1</sub>) simplifies the generation of EPROM addresses. After resetting the counter to 0 by applying a pulse to pin 11, you can step

the EPROM through its addresses by applying pulses to the counter's clock input, pin 10. Refer to the EPROM data sheet for details on controlling the other inputs  $(O_1, O_2, \text{ and } O_5 \text{ to } O_7)$ .

You can verify the contents of the EPROM against your original object code by the same process of strobing the counter for each address and reading the data bus for that address. Again, refer to the data sheet for details on reading data from the EPROM.

To Vote For This Design, Circle No 746




Fig 1—Program EPROMs using a binary counter for address generation and a step-up switching regulator to supply the 21V programming voltage.

#### Algorithm approximates sum of quadratures

Grimes G Slaughter Conray Inc, Oak Ridge, TN

To calculate the magnitude of a complex frequency, you can use both hardware and software approaches. Unfortunately, you need square-root routines (which are relatively slow) to calculate the expression in software;

to calculate it in hardware, you need expensive analog multipliers. However, if your application can tolerate the resulting error (Fig 1b), you can approximate the expression using a simple Basic algorithm that does the job quickly.

The magnitude of a complex frequency is equal to the vector sum  $(A^2+B^2)^{0.5}$  of its quadrature components




Fig 1—Basic lines 100 and 110 in the accompanying text approximate a vector sum of quadrature components (a). To improve the approximation, use lines 200 and 210 (b).




Fig 2—This analog realization of the Basic algorithm given in lines 200 and 210 is based on inexpensive amplifiers.

## transformers



3 KHz-800 MHz **over 50 off-the-shelf models** from \$295

Choose impedance ratios from 1:1 up to 36:1, connector or pin versions (plastic or metal case built to meet MIL-T-21038 and MIL-T-55831 requirements\*). Fast risetime and low droop for pulse applications; up to 1000 M ohms (insulation resistance) and up to 1000 V (dielectric withstanding voltage). Available for immediate delivery with one-year guarantee.

Call or write for 64-page catalog or see our catalog in EBG, EEM, Gold Book or Microwaves Directory.



finding new ways . . . setting higher standards

#### Mini-Circuits

World's largest manufacturer of Double Balanced Mixers
P.O. Box 166, Brooklyn, New York 11235 (718) 934-4500
Domestic and International Telex 125460 International Telex 620156

C71 Rev. Orig.

CIRCLE NO 81

#### **DESIGN IDEAS**

 $\cos(2\pi ft)$  and  $j\sin(2\pi ft)$ , where A and B are the magnitudes of those components. The algorithm is as follows:

100 C=ABS(A)+0.4142137\*ABS(B) 110 IF ABS(B)>ABS(A) THEN C=ABS(B)+0.4142137\*ABS(A)

The multiplying constant is chosen for a correct approximation (no error) when the vector sum C and the reference axis form a  $45^{\circ}$  angle. At  $45^{\circ}$  both the sine and cosine have a value of 0.7071067, so either must have a correction of (1-0.7071067), or 0.2928933, added to give the correct vector sum of unity. If K is the correction factor, then K=0.2928933/0.7071067, or 0.4132137.

The algorithm gives an approximation that is correct at 0° and at every multiple of 45° thereafter; in the algorithm's logic, the sine and cosine exchange roles at those points. Fig 1a shows the correct vector sum

(unity) vs results using the algorithm as functions of the vector's angle with the reference axis. The maximum error (1.08239, or about 8%, occurring at 22.5°) may be halved by adding a factor of 0.96 to the algorithm expressions:

200 C=0.96\*ABS(A)+0.3976451\*ABS(B) 210 IF ABS(B)>ABS(A) THEN C=0.96\*ABS(B)+0.3976451\*ABS(A)

Fig 1b shows the result of this modification.

You can also implement lines 200 and 210 in hardware using inexpensive amplifier configurations as shown in Fig 2. You can expand the scheme by obtaining additional terms from the resistor string to achieve an error of 1 or 2%. Further, when inputs A and B are positive, you don't need the absolute amplifiers.

To Vote For This Design, Circle No 750

#### Drive stepper motor without missing steps

Pieter Kleingeld

Rijksuniversiteit Utrecht, Instituut voor aardwetenschappen, Utrecht, The Netherlands

The shaft of a stepper motor should advance by one

increment of angular rotation for each digital pulse you apply. As the shaft's rpm value approaches its region of mechanical resonance, however, the motor sometimes misses steps; ie, its shaft may advance by fewer increments of rotation than the number of pulses applied.




Fig 1—Using this circuit, you can prevent the missing steps that result when a stepper motor is driven near its resonant frequency. The circuit avoids the corresponding inputs to the motor's VCO controller.

## MICRO CAP and MICRO LOGIC put your engineers on line... not in line.



MY OWN WORKSTATION



How many long unproductive hours have you spent "in line" for your simulation? Well, no more. MICROCAP and MICROLOGIC can put you on line by turning your PC into a productive and cost-effective engineering workstation.

Both of these sophisticated engineering tools provide you with quick and efficient solutions to your simulation problems. And here's how.

#### MICROCAP: Your Analog Solution

MICROCAP is an interactive analog circuit drawing and simulation system. It allows you to sketch a circuit diagram right on the CRT screen, then run an AC, DC, or Transient analysis. While providing you with libraries for defined models of bipolar and MOS devices, Opamps, transformers, diodes, and much more, MICROCAP also includes features not even found in SPICE.

MICROCAP II lets you be even more productive. As an advanced version, it employs sparse matrix techniques for faster simulation speed and larger net-




"Typical MICROCAP Transient Analysis"

works. In addition, you get even more advanced device models, worst case capabilities, temperature stepping, Fourier analysis, and macro capability.

#### MICROLOGIC: Your Digital Solution

MICROLOGIC provides you with a similar interactive drawing and analysis environment for digital work. Using standard PC hardware, you can create logic diagrams of up to 9 pages with each containing up to 200 gates. The system automatically creates the netlist required for a timing simulation and will handle networks of up to 1800 gates. It provides you with libraries for 36 user-defined basic gate types, 36 data channels of 256 bits each, 10 user-defined clock waveforms, and up to 50 macros in each network. MICROLOGIC produces high-resolution timing diagrams showing selected waveforms and associated delays, glitches, and spikes-just like the real thing.

**CIRCLE NO 82** 



"Typical MICROLOGIC Diagram"

#### Reviewers Love These Solutions

Regarding MICROCAP..."A highly recommended analog design program" (PC Tech Journal 3/84). "A valuable tool for circuit designers" (Personal Software Magazine 11/83).

Regarding MICROLOGIC . . . "An efficient design system that does what it is supposed to do at a reasonable price" (Byte 4/84).

MICROCAP and MICROLOGIC are available for the Apple II (64k), IBM PC (128k), and HP-150 computers and priced at \$475 and \$450 respectively. Demo versions are available for \$75.

MICROCAP II is available for the Macintosh, IBM PC (256k), and HP-150 systems and is priced at \$895. Demo versions are available for \$100.

Demo prices are credited to the purchase price of the actual system.

Now, to get on line, call or write today!

#### Spectrum Software

1021 S. Wolfe Road, Dept. E Sunnyvale, CA 94087 (408) 738-4387

#### **DESIGN IDEAS**

For systems that use a voltage-controlled oscillator (VCO) for motor control, you can avoid missing steps by using the Fig 1 circuit to supply the VCO input. The circuit output combines a voltage-dependent step waveform with a waveform that is linearly related to  $V_{\rm IN}$ . The resulting transfer function (Fig 2) skips the output-voltage range that produces the pulse frequencies that cause the motor to resonate.

For positive values of  $V_{OUT}$ , component values  $R_1$  and  $R_2$  in **Fig 1** set the threshold  $(\gamma)$  and width  $(\delta)$ , respectively, of the forbidden  $V_{OUT}$  range (**Fig 2**).  $R_3$  sets the




Fig 2—The circuit in Fig 1 yields this transfer function. Choose  $R_1$  to set the  $V_{OUT}$  threshold  $\gamma$  and  $R_2$  to set the  $V_{OUT}$  range  $\delta$  to be excluded.




Fig 3—The dynamic behavior of the Fig 1 circuit exhibits a controlled response (set by capacitor  $C_1$ ) and excludes troublesome values of  $V_{OUT}$ .

overall gain,  $V_{OUT}/V_{IN}$ , which is reduced for  $V_{IN}$  above or below the step thresholds.

Fig 3 shows the circuit's dynamic response. You choose the value of capacitor  $C_1$  for the desired rate of change in  $V_{\text{OUT}}$ —ie, outside its forbidden zone. (The 2- $\mu$ F value shown for the capacitor is typical; in fact, all component values shown in Fig 1 are typical.)

To Vote For This Design, Circle No 749

#### Pulse generators offer improved performance

P Gascoyne UKAEA, Culham Lab, Oxon, UK

With certain modifications and additions to a circuit (Fig 1) from an earlier Design Idea (Barnett, T G, "Pulse generator has variable duty cycle," EDN, October 4, 1984, pg 249), you can enhance the performance of a variable-duty-cycle pulse generator.

If only  $\pm 15$ V power supplies are available, it's better to attenuate the output of the duty-cycle potentiometer (**Fig 2b**) than to reduce the voltage across the potentiometer (**Fig 2a**). Either method produces the desired  $\pm 1$ V output range, but **Fig 2b** offers as much as a  $\times 14$  improvement in rejecting asymmetrical changes in the supply voltages.

The voltage follower  $IC_C$  in **Fig 1** is not essential for buffering the potentiometer. If desired, this op amp could instead be used to provide an inverted output. Or,





Fig 1—This pulse generator offers independent control of frequency and duty cycle, and it can be enhanced in several ways.

using a second potentiometer, it could generate an output with a different duty cycle.



#### **DESIGN IDEAS**

Some hysteresis via positive feedback (obtained by adding 1-k $\Omega$  and 1-M $\Omega$  resistors, as shown in Fig 3) will improve the output stability and shorten the rise and fall times. The resistors allow a clean response for output frequencies as low as 0.02 Hz.

By replacing Fig 1's 2-op-amp ( $IC_A$  and  $IC_B$ ) triangle-wave generator with a generator based on one op amp, you can build an economy-version pulse generator using a dual op amp (Fig 4). Although Fig 4's triangle waveform consists of exponential rather than linear segments, the resulting error is small because the timing capacitor charges to only 10% of maximum on each cycle. This circuit tolerates power-supply variations—a 3V change in either supply causes little effect on the duty cycle.

Finally, you can sweep or otherwise modulate the duty cycle by replacing the potentiometer with a suitable ac signal. The deluxe-version swept-pulse genera-




Fig 2—The divider shown in b is preferable to that shown in a because it provides more rejection for asymmetrical changes in the supply voltages.




Fig 3—Improve the low-frequency response of the output stage in Fig 1 by adding 1-k $\Omega$  and 1-M $\Omega$  resistors to provide hysteresis.




Fig 4—This pulse generator uses one dual op amp and provides independent control of frequency and duty cycle. In addition, it tolerates an unbalance of 3V or more in the power supplies.

tor in Fig 5 uses a second low-frequency wave generator for the sweeping.

#### To Vote For This Design, Circle No 747




Fig 5—A deluxe version of the pulse generator offers a swept duty cycle as an option.

## FAST ENOUGH NEVER IS.

You can have the fastest system one day, and be passed the next. Or you can do something about it.

Like go with the company that makes the fastest I/O controllers in the business.

Adaptec.

Our ACB-5500 and ACB-5580 controllers can boost your system's throughput by up to 137 percent. And since they're based on SCSI, they offer unlimited flexibility.

© 1985, Adaptec, Inc.

The ACB-5500 is the performance leader for ST506/ST412 drives. While the ACB-5580 is the only Multi-threaded SCSI controller fast enough to handle SMD drives. (Yet costs about \$700 less than a dedicated bus controller.)

Both boards offer Multithreaded I/O. Which means you can run up to four drives concurrently with true overlapped operation. You can even upgrade from ST506 to SMD with-

out having to rewrite your I/O driver.

So for our latest benchmarks and a brochure, call 408/946-8600, ext. 400. Or write Adaptec, 580 Cottonwood Drive, Milpitas, CA 95035.

Of course, we should warn you that someday someone will build controllers even faster than these.

In fact, we're already working on them.

adaptec

#### Calculator performs binary arithmetic

D G Sporea and V G Velculescu Central Institute of Physics, Magurele, Romania

Using a binary-arithmetic program called Binarth

(Listing 1), you can perform binary arithmetic on an HP67 or HP41 handheld calculator. The binary-arithmetic capability is useful for checking the results of programs and algorithms developed for multibyte

	TING 1							
	f LBL A Binary-to-decimal conversion	060	f GSB D	120	1.	180		Initiation of registers 5, 6, and 7
	h CF 0		RCL 9		0	1	1	
	Cl x		RCL 8		STO 2		0	
	STO 9		RCL 6		RCL 7		2	
	RCL A		×		STO 3		4	
			•				h ↑	
	f x=0				hF?			
	GT 04		STO 9		GTO 0		STO 7	
	f GSB D		RCL 1		f LBL 1		g x <sup>2</sup>	
	RCL 5		f LBL 8		RCL 3		STO 6	
010	×		STO B		2		×	
	STO 9	070	RCL 9	130	÷	190	STO 5	
	f LBL 4		RCL 7		STO 3		DSP 0	
	RCL B		÷		RCL 2		CIX	
	f x=0		f INT		1		h RTN	
			STO 8				II LILIA	
	GT 05				0			
	f GSB D		f x=0		÷			
	RCL 6		GT 09		STO 2			
	×.		f GSB D		RCL 0			
	STO +9		RCL 9		h x <del>≠</del> y			
020	f LBL 5		RCL 8		g x > y			
	RCL C	080	RCL 7	140	GTO 2			
	f x=0		Χ.		-			
	GT 06		_		STO 0			
			STO 9		RCL 3			
	f GSB D							
	RCL 7		RCL 1		RCL 1			
	X		f LBL 9		+			
	STO +9		STO C		STO 1			
	f LBL 6		RCL 9		f LBL 2			
	RCL D		f GSB D		1			
	f GSB D		STO D		RCL 3			
	STO +9	090	h RTN	150	g x > y			
	RCL 9	000	f LBL C	150	GTO 1			
			f GSB A		RCL 1			
	h RTN							
	f LBL B Decimal-to-binary conversion		STO 8		h RTN			
	h SF 0		R/S		f LBL 0			
	STO 9		f GSB A		RCL 2			
	RCL 5		RCL 8		1			
	÷		$h x \stackrel{\longrightarrow}{=} y$		0			
	f INT		STO E		÷			
	STO 8		R/S		STO 2			
	f x=0	100	h ABS	160	RCL 3			
	GT 07	100	h ↑	100	2			
	f GSB D		g FRAC		÷			
	RCL 9		h STI		STO 3			
	RCL 8		h J		RCL 0			
	RCL 5		f INT		$h x \rightarrow y$			
	×		f GSB B		g x > y			
			R/S		GTO 3			
	STO 9		RCL E					
	RCL 1		h RCI		STO 0			
		110		170				
	f LBL 7	110		170	RCL 1			
	STO 8		f INT		RCL 2			
	RCL 9		f GSB B		+			
	RCL 6		h RTN		STO 1			
	÷		f LBL D		f LBL 3			
1	FINT		STO 0		RCL 0			
	STO 8		CIX		f x > 0			
	f x=0		STO 1		GTO 0			
					RCL 1			
- 1	GT 08		1		HUL I			

#### Getting A DMM?

## KNOW WHAT YOU'RE GETTING.

When you invest in a Keithley DMM, you're getting the benefit of 40 years of experience in sensitive electronic measurements. You're also getting extended capabilities—at an affordable price—made possible by the latest advances in solid-state technology.

That's not all. Only Keithley has trend recording and digital

calibration in a bench/portable DMM. Keithley's exclusive TRANSLATOR software in the Model 193 system DMM is a powerful tool for simplifying your IEEE-488 programming.

From basic bench measurements to sophisticated systems applications, a Keithley DMM can match your measurement needs and budget. Contact the Product Information Center at the address below or at (216) 248-0400 for technical information, FREE programming guides, or to order a 175, 197, or 193 for a 20-day FREE trial. And know what you're getting in your next DMM.

Keithley Instruments, Instruments Division, 28775 Aurora Road, Cleveland, Ohio 44139. Phone: (216) 248-0400.



#### Model 175 Autoranging DMM

4½ digits

☐ Data logger, relative reference, dB

☐ IEEE-488 interface option

Rechargeable battery pack option

\$430

#### Model 197 Autoranging Microvolt DMM

- ☐ 5½ digits, 220,000 count display
- $\square$  1 $\mu$ V, 1m $\Omega$ , 1nA sensitivity
- ☐ Data logger, relative reference, dB
- ☐ Analog & IEEE-488 output option
- \$595





Model 193 System DMM □ 3½ to 6½ digits □ 2,200,000 counts

- ☐ Up to 1000 readings/second ☐ TRANSLATOR software
- ☐ 9 measurement functions ☐ 500 reading memory
- ☐ Low frequency AC ☐ Programmable power-up states

□ \$2100

**CIRCLE NO 85** 



#### **DESIGN IDEAS**

#### **Design Entry Blank**

\$75 Cash Award for all entries selected by editors. An additional \$100 Cash Award for winning design each issue, determined by vote of readers. Additional \$1500 Cash Award for annual Grand Prize Design, selected among biweekly winners by vote of editors.

To: Design Ideas Editor EDN Cahners Publishing Co 275 Washington St, Newton, MA 02158

I hereby submit my entry for EDN's Design Ideas program.

Name		
Title		Phone
Company		
Division (if any)		
Street		
City	_ State _	Zip
Design Title		
Home Address		
Social Security No _		

Entry blank must accompany all entries. Design entered must be submitted exclusively to EDN, must be original with author(s), must not have been previously published (limited-distribution house organs excepted), and must have been constructed and tested.

Exclusive publishing rights remain with Cahners Publishing Co unless entry is returned to author or editor gives written permission for publication elsewhere.

In submitting my entry, I agree to abide by the rules of the Design Ideas Program.

Signed \_\_\_\_\_\_

Your vote determines this issue's winner. All designs published win \$75 cash. All issue winners receive an additional \$100 and become eligible for the annual \$1500 Grand Prize.

**Vote now**, by circling the appropriate number on the reader inquiry card.

Submit your own design, too. Mail entries to Design Ideas Editor, EDN, 275 Washington St, Newton, MA 02158.

arithmetic in microprocessor systems. The program is based on software routines that appeared in an earlier Design Idea (Talmor, Shlomo, "Convert binary/decimal numbers," EDN, February 9, 1984, pg 228).

The Binarth program performs addition, subtraction, multiplication, and division for binary numbers as long as four bytes. The operands are introduced in binary form. The results are presented in binary, but the intermediate operations are performed in decimal format. Operands and results must not exceed  $2^{32}-1$ .

In operation, subroutine LBL E (line 180) generates and stores the first, second, and third powers of 1024, a base number (2<sup>10</sup>) that is compatible with the 10-digit calculator display.

Subroutine LBL A (line 1) converts a binary number to its decimal equivalent. You partition the binary number into 10-bit groups, beginning with the LSB. For a maximum-length 32-bit number, the partitioning leaves only two bits in the last (most significant) byte. Next, enter each byte into the calculator, from right to left, as in the following example:

#### 10 0011000100 11111110001 0110001100

Key in 110001100- STO D, 1111110001- STO C, 11000100- STO B, 10- STO A. Then press key A to display the result in decimal form: 2354038156.

In contrast to subroutine LBL A, subroutine LBL B (line 34) converts a decimal number to binary form. To convert 2354038156, for example, enter the number into the calculator and press key B. You obtain the result via the calculator's RCL function (but you must add the required number of zeros to the right side of each group so that each contains 10 digits):

RCL A- 10

RCL B- 0011000100

RCL C- 11111110001

RCL D- 0110001100

The program uses subroutine LBL C (line 91) to convert binary operands to decimal (by calling LBL A); the program then executes the required arithmetic operation on the decimal numbers and converts the result to binary by calling LBL B.

To Vote For This Design, Circle No 748

systems and much, much more.


You've chosen precision Airpax stepper motors before, so when you find yourself in the market for a linear actuator, here's something to remember. When we modify a stepper motor to become a linear actuator, the change lies in the threaded shaft and resulting linear

motion, not in the Airpax quality

you've come to know. Our linear actuators come in an array of low, medium

and high force models with push/pull ratings of less than 21 ozs. to 25 lbs. in increments of .001 to .004" per pulse. Whenever rapid response and precision movement are called for, our engineers are ready to help you design the linear actuator for your specific application. Airpax linear actuators are the ones to depend on, for valve actuation, medical pumps, robotics, HVAC

> To get your designs in motion, contact the Airpax Corporation, Cheshire Division, West Johnson Avenue, Cheshire, CT 06410. (203) 272-0301. A North American Philips Company.


















CHESHIRE DIVISION

#### NEW PRODUCTS: COMPUTER-AIDED ENGINEERING



#### SCHEMATIC DESIGN

Running on an IBM PC or compatible computer, this company's /SDT schematic-capture program allows you to place parts, wires, text, and other objects on a screen via kevboard or mouse commands. You can move, rotate, replicate, and delete selected parts. Possible worksheet sizes range from A to E. The package features hierarchical schematic organization and rubberbanding of wires, buses, and blocks. An on-line, 1200-part library contains TTL and CMOS devices, memories, discrete components, µPs, and peripherals.

You can suspend a session and switch to DOS command execution. The package provides four utility programs: schematic-output generation, net-list creation, design checking, and a bill-of-materials file. It requires MS-DOS, version 2.0 or higher, a 360k-byte floppydisk drive, and 256k bytes of RAM. \$495.

OrCAD Systems Corp. 23315 W Baseline Rd, Hillsboro, OR 97123. Phone (503) 640-5007.

Circle No 350

#### PLD DESIGN

You can use Vista to design schematics on an IBM PC, PC/XT, or PC/AT and translate the design into a format that you can program into a standard PLD. It uses an optical mouse for schematic input and interfaces to either a 640×400-pixel color-graphics display (16 colors) or a 640×200-pixel monochrome-



graphics display. The package includes Assisted Technology's CUPL compiler. After you have entered your schematic, the package creates a net-list file and passes that file to the CUPL program for compilation, simulation, and verification. Finally, the compiler translates the schematic to a standard JEDEC file with test vectors. The company's 160 Universal Memory/Logic Programming System can use the JEDEC file to program PLDs. The package can interface with Data I/O, Stag, Kontron, and other programmers.

#### THE \$1995 SET PROGRAMMER THAT'S A GANG DUPLICATOR

When you are ready to program production volumes, Data I/O's 280 Set Programmer doubles as a highspeed gang duplicator. With menudriven operation, 3-key control and intelligent algorithms, it delivers the throughput you need, at a price you can afford. Automatic calibration, pre-programming tests and a fourpass verify provide the reliability you demand. And with set programming capabilities, you can also program multiple EPROMs with different sets of data in just one operation — ideal for just-in-time production and product upgrades.

The 280 also offers production: ■ Socket isolation for superior relia-



DATA I/O

\$3395 (without graphics card).

Valley Data Sciences, 2426 Charleston Rd, Mountain View, CA 94043. Phone (415) 968-2900. TLX 4993461.

Circle No 351

#### TEST MANAGER

The Boardwatch software system collects and analyzes board-test data. It interfaces with its manufacturer's L200 Series VLSI board testers. The package features a paperless repair system that automates the collection and analysis of test, diagnosis, and repair data. To use this software, you enter the serial number of each board that you test and relay the serial number, along with the test results for that board, to the system. If the board fails its tests and requires further diagnosis, you send the board to a diagnostic station, where you enter the board's serial number once more

and relay that number to the test manager. The package includes a relational-database manager, a utility that controls an operator's access to test systems, a utility for monitoring tester use, and L200-system interfaces to a LAN. You can modify standard report formats or create new ones. You can store, catalog, and update all jobs on any VAX. Conversely, users of L200s can use their terminals to access the package on a VAX. \$75,000 to \$200,000, depending on the number of L200 test systems on a network. Deliveries to begin in mid-1986.

**Teradyne Inc**, 321 Harrison Ave, Boston, MA 02118. Phone (617) 482-2700. TWX 710-321-1055.

Circle No. 352

#### FAULT SIMULATOR

This fault simulator, Megafault, is an enhanced version of the Daisy Megalogician fault simulator. A concurrent algorithm and a hardware accelerator increase the speed of the package's fault simulations. For example, this unit evaluated a 10,000-gate fault simulation in a few hours; on a VAX 11/780, the same process required a day of computation. The fault simulator uses the same models and test vectors as the Megalogician. \$45,000.

Daisy Systems Corp, 700 Middle-field Rd, Mountain View, CA 94043. Phone (415) 960-0123.

Circle No 353

#### ANALOG DESIGN

The Analog Designer brings CAE to analog boards and circuits. It runs a set of software analog-design instruments that help you validate your designs. These software instruments consist of mock-ups of a digital voltmeter, an oscilloscope, a network analyzer, and a function generator. The instruments use

#### THE \$1995 GANG DUPLICATOR THAT'S A SET PROGRAMMER.



No other eight-socket EPROM programmer offers set programming at a price this low. Data I/O's 280 Set Programmer can program multiple EPROMs with different sets of data in just one operation. You can also use one of two remote control modes to easily operate the programmer from your PC or terminal. When your design is ready for volume programming, the 280 Set Programmer doubles as a gang duplicator, giving you even more value for your programming dollars.

The 280 also offers design engineers: ■ 32-bit wide programming. ■ Isolated sockets for superior reliability. ■ 16-key HEX keyboard.

■ Compatibility with PROMlink™ interface and file management software. ■ User-installable algorithm updates.

#### 15-DAY TRIAL AT NO OBLIGATION.

Try Data I/O's 280 Set Programmer for 15 days at no obligation. You'll discover that no other programmer can beat the performance for the price.

Call us today at:

1-800-547-4000

Dept. 141.

Mastercard or Visa is accepted.



VISA

In Oregon or outside the U.S.A. call 1-503-684-3000, Dept. 141.

DATA I/O

**CIRCLE NO 87** 

ValidSpice for modeling circuits. You select your software instruments from a menu on the company's workstation. Prices start at \$79,000; to upgrade an existing Scaldsystem costs \$25,000.

Valid Logic Systems Inc, 2820 Orchard Parkway, San Jose, CA 95134. Phone (408) 945-9400.

Circle No 354

#### PC-BOARD LAYOUT

Because the CT2400 pc-board layout system uses the same set of commands as this company's other CAE products, you can learn how to use this layout package quickly. The pc-board layout program provides automatic placement and packaging of components. The router displays connections among all components.



Component interconnections move in a rubberbanding style when you move components. Both 45 and 90° angles are available. Using this program, you can identify critical gates during schematic design. The program then automatically packages the remaining gates for maximum design efficiency. During pc-board layout, the program's interactive design-rule checkers point out any rule violations. Back annotation furnishes documentation and schematic hard copy. The program runs on IBM PC/ATs under the PC-DOS operating system. \$4250.

Case Technology Inc, 633 Menlo Ave, Menlo Park, CA 94025. Phone (415) 322-4057. TLX 506513.

Circle No 355

#### DESIGN AND TEST SET

TestEdge is a set of simulation and testing tools that allows you to create fully testable designs. The set includes a simulation and test language (STL), testability analysis tools, and a graphical fault-simulator interface. STL's simulation output-comparison feature lets you model the behavior of your circuit and compare the simulation results of a logical model and a behavioral model. The package interfaces with Simucad's Silos logic and fault simulator, Spice circuit simulators, and the Sentry tester. The software is offered as an option to this company's IC design systems. \$16,500.

SDA Systems, 2461 Mission College Blvd, Santa Clara, CA 95054. Phone (408) 727-7811.

Circle No 356

## The only power entry module that can be called "complete" everywhere in the world.

#### **Introducing The Schaffner FN 390 Filter**

The first truly universal power entry module.


Schaffner's FN 390 is a single, compact, neat module that has integrated every component necessary for complete power entry function anywhere in the world...including:

- · High performance RFI filter
- Universal voltage selector

IEC Connector

- On/off power switch
- Fuse drawer that accepts either American or European size fuses

The FN 390 gives you complete acceptance worldwide without the need for changes, additions, or adaptations. It's the first truly universal power entry module.



If you're familiar with Schaffner's FN 370 and FN 380 power entry modules, you'll recognize the FN 390 as a natural extension.

For more information about the universal power entry module series (FN 370/380/390), and all three dimensions of Schaffner EMC, call or write today.

🗟 🔇 🕾 🕦 🏮 submitted

#### SCHAFFNER

• RFI Suppression Filters • EMC Test Equipment • Test and Application Services

Schaffner EMC, Inc., 825 Lehigh Ave., Union, NJ 07083 • 201-851-0644 • 1-800-367-5566

Switzerland: Schaffner Elektronik AG, CH-4708 Luterbach, Switzerland/Telefon 065 4231 31

## 3 MORE KEPCO/TDK SWITCHERS PROVE THAT LOW-PRICED DOESN'T HAVE TO MEAN CHEAP.

Our popular Series MRM — compact, multi output, PC Card switching power supplies for the logic, display, communications, and disk drive requirements of CRT terminals and microcomputers — now has five TÜV-certified members. The power range of the series has been extended to 120 Watts, as the 40-Watt MRM 144KV and the 60-Watt MRM 250KV are joined by the 80-Watt MRM 260KV and the 120-Watt MRM 270KV and MRM 280KV.

MRM 260KV MRM 270KV

KEPCO

POWER SUPPLIER "

Like all Kepco/TDK switching power supplies, their prices are surprisingly low. But they offer all the most-needed features and possess all these well-known Kepco/TDK hallmarks of quality:

Hybrid microcircuits, designed and manufactured in-house, provide control, OVP, current limit, and start-up functions. They greatly reduce parts count and improve MTBF.

8mm primary-secondary, 4mm primary-to-ground spacing for the safety requirements of IEC 380/VDE 0806. All these power supplies have been certified by TÜV Rheinland, and are UL Recognized, CSA Certified.

Transformers of TDK H7C1 ferrite meet the 3750V withstand test of VDE 0806/IEC 380. All chokes also have TDK H7C1 cores.

100KHz switching for fast response, lower EMI, high efficiency, and smaller transformers and chokes.

105°C input capacitors, which store enough energy for at least 20 milliseconds holding time.

Input filters of our design and manufacture attenuate conducted EMI below FCC 20780 Class B.

All components mounted on PC board by machines developed in-house.

1	MRM	MRM	NEW! MRM	NEW! MRM	NEW! MRM						
MODEL	144KV	250KV	260KV	270KV	280KV						
a-c input	115/230	115/230	115/230	115/230	115/230						
d-c outputs	d-c outputs										
+5V	0.45-5.0A1	2.0-6.0A (l <sub>1</sub> ) <sup>2</sup>	3.0-8.0A	3.0-15A	3.0-11A						
+12V	0.3-2.5A1	0.5-3.0A (l <sub>2</sub> ) <sup>2</sup>	0.5-3.0A	0.5-5.0A <sup>3</sup>	0.5-5.0A						
-12V	0-0.5A1	0-1.0A	0-0.7A	0-0.7A	0-0.5A						
-5V	_	0-0.5A	0-0.3A	0-0.3A	_						
+24V				<del></del>	0.3-1.3A (1.7A peak)						
Prices *	\$80	\$99	\$130	\$185	\$185						

(1) The maximum combined power for all three outputs is 40W (0-50°C)

\*Substantial OFM discount available

For complete specifications write to Dept. HRF-12
KEPCO, INC. 131-38 Sanford Avenue,
Flushing, NY 11352 USA, (718) 461-7000
TWX: #710-582-2631
FAX: (718) 767-1102
CIRCLE NO 89

MRM 280KV

#### NEW PRODUCTS: COMPUTERS & PERIPHERALS



#### DISK READER

If you have a DEC Rainbow, IBM PC, or compatible computer, you can use a CD Massfile to access large databases. It reads removable compact disks (CDs) that are prerecorded with information in a Uni-File data format. The unit lets you access permanent data stored in large read-only databases such as encyclopedias, dictionaries, catalogs, and technical manuals. Each optical CD can hold 550M bytes of information, equivalent to 250,000 single-spaced typed pages or 1600 51/4-in. floppy disks. The CD Massfile includes a CD reader, a controller board that supports as many as

two readers, and diagnostic software. A lighted panel on the reader provides power-on, activity, and error indications. \$1695; each controller card, \$295.

Tecmar Inc, 6225 Cochran Rd, Solon, OH 44139, Phone (216) 349-0600. TLX 466692.

Circle No 357



#### LIGHT PEN

ZIITEK


The FT-176 light pen provides an optical user interface for monochrome displays. This light pen's circuitry overcomes the problem of long-persistence phosphor that made previous pens incompatible with monochrome displays. You can also use the light pen with color monitors. When used as a pointing device, it simplifies menu selections and windowing tasks on a personal computer, \$235.

FTG Data Systems, Box 615, Stanton, CA 90680, Phone (714) 995-3900. TLX 887840.

Circle No. 358

#### DAISY-WHEEL PRINTER

The \$399 KX-P3131 daisy-wheel printer accommodates proportional spacing, impression intensity, automatic justification, superscript, and subscript printing. The printer uses Diablo 630 ribbons and 96-character plastic print wheels and prints 17 cps. It offers word-processing features like centering, bold print, shadow, outline, and single and double underlining. You can select char-





#### **ICE-ENGINE** series

MODEL BX-8 supports Z80<sup>TM</sup>, 8085, 6809, 8048 series by pod selection

MODEL BX-86 supports 8086, 8087, 8088

- High level symbolic debugger and powerful debug command
- Trigger types: sequential, delayed, external, executive etc.
- Trigger-pulse output
- Program run-time timer
- · Battery back-up RAM for file retention
- Built-in ROM programmer and eraser
   Compatible with IBM®PC and CP/M® machines + Stand-alone

ZILTEK CORPORATION

1651 East Edinger Ave., Santa Ana, CA 92705 Phone: (714)541-2931 In CA: (714)835-9512



## Powerful new solution to high-speed local networking:

### The 200 Mbp/s Fiber Optics Transceiver

It's the SUMILINK-DM Series. If you're building high-speed LAN capabilities into computers, workstations or PBX installations, the Sumilink DM-56 offers a powerful competitive edge...now.

Specify the SUMILINK DM-56—the DIP-packaged, PC-mountable module that brings fiber optics up to speed and down in cost for high-rate optical digital data transmission over distances up to 7,000 feet.

One big advantage: no LDs. The DM-56 integrates the simpler, more-reliable technology of the 1300nm LED/PIN detection device. You get full compatibility with standard differential ECL circuitry. You get 9mm-thick low-profile design that lets you save precious board space as well as money. You even get the field-mountability of our mini-


BNC connectors. So you can stop worrying about fiber optics viability and start benefitting from the superior performance of small-diameter, light weight, EMI/lightning-immune fiber cable.

Don't stop there; meet the family. The Sumilink-DM Series provides long-wavelength capabilities for a variety of fiber optics/data communications needs, including 40 Mbp/s and 125 Mbp/s optimized data links as well as 20 Mbp/s and 100 Mbp/s DC-coupled devices. For full details and evaluation samples delivered from stock, write or call today.



#### SUMITOMO ELECTRIC U.S.A. Inc.

551 Madison Avenue, New York, N.Y. 10022/(212) 308-6444





**Bt101.** Triple 8-bit VIDEODAC, 50 & 30 MHz, Monolithic, +5v CMOS, 40-pin CERDIP.



Bt102. 8-bit VIDEODAC, 75 MHz, Monolithic, +5v CMOS, 22-pin 0.3" CERDIP.



Bt103. Triple 4-bit VIDEODAC, 75 & 30 MHz, Monolithic, +5v CMOS, 28-pin CERDIP.



Bt104. 12-bit DAC, 35 ns Settling, Monolithic, +5v CMOS, 20-pin 0.3" CERDIP.



Bt105. 12-bit DAC with latch, 35 ns Settling, Monolithic, +5v CMOS, 20-pin 0.3" CERDIP



Bt106. 8-bit VIDEODAC, 50 & 30 MHz, Monolithic, +5v CMOS, 20-pin 0.3" CERDIP.



Bt444. 4-bit VIDEODAC, 40 MHz, Hybrid, +5v CMOS, Pin-compatible VDAC 444TD.



Bt452. 4-bit RAMDAC, 16 x 12 Color Lookup Table, 40 MHz, Hybrid, +5v CMOS, Pin-compatible to RGB DAC 4TD.



Its 8-bits. It runs at 300 MHz. And we'll unveil it in April.

### Flock of DACs.

We promised you the fastest-growing family of high speed, high performance data converters and display and imaging ICs. And we've delivered.

Our highly-integrated approach to DAC design gives you monolithic parts where before you had to settle for hybrids, provides TTL-compatible CMOS components where before you had to use power hungry, complex ECL solutions, and delivers bipolar converters running at speeds that make high resolution systems eminently practical.

We'll continue to unveil a flock of important new DACs in coming months, putting our technology to work to deliver solutions that help you build systems worth bragging about. That's the Brooktree way. Make it yours.

For samples, evaluation kits, or the location of your nearest Brooktree representative, call our DAC hotline, 1-800-VIDEO IC. Brooktree Corporation, 9950 Barnes Canyon Rd., San Diego, CA 92121. 619/452-7580.

TLX 383 596.

Brooktree

Brooktree, VIDEODAC and RAMDAC are trademarks of Brooktree Corporation.  $\circledcirc$  1985 Brooktree Corporation. Pat. Pending.

#### **COMPUTERS & PERIPHERALS**

acter pitch, line spacing and justification, and margin widths. An automatic paper loader feeds single sheets and envelopes. You can order an optional tractor-feed mechanism or cut-sheet feeder.

Panasonic Industrial Co, Computer Products Div, 1 Panasonic Way, Secaucus, NJ 07094. Phone (201) 348-7183.

Circle No 359



#### COMPUTERS

The Fast Series of computers offers IBM PC/AT compatibility and a host of standard features. Fast-1 comes with 640k bytes of RAM, a 1.2Mbyte 51/4-in. floppy-disk drive, a speaker, a 200W power supply, 64k bytes of ROM, eight I/O expansion slots, a clock/calendar with battery backup, a key lock, an 84-key keyboard, a controller card, and a socket for an 80287 math coprocessor. Fast+ adds a 20M-byte hard-disk drive, a serial port, and two parallel ports. Both computers are available with 1M byte of onboard RAM; expansion boards let you configure the systems with as much as 16M bytes of RAM. Fast-1, \$2500; Fast+, \$3000.

Innovative Computer Technology Inc. 30 Broad St. Denville, NJ 07834. Phone (201) 586-2600.

Circle No 360

#### SERIAL MATRIX PRINTER

Featuring interchangeable font cartridges, the MT290 serial matrix printer also gives you a choice of paper-feed methods. The printer includes both tractor- and frictionfeed mechanisms for rear and bot-



tom feeding of continuous-form paper, multiple-part forms, or single sheets. The adjustable tractors can accommodate paper widths from 3 to 16 in. Optionally, you can use the printer's automatic frontfeed mechanism for cut sheets of paper without removing the continuous-form paper from the tractor mechanism. The printer prints 200 cps in draft mode or 50 cps in correspondence mode. The plug-in print cartridges include Courier, Helena, letter Gothic, italic, and modern fonts. The printer comes with a parallel interface, but optional RS-232C, current-loop, and IEEE interfaces are available. \$895; with automatic front feed, \$1149.

Mannesmann Tally Corp, 8301 S 180th St, Kent, WA 98032. Phone (206) 251-5500. TLX 320200.

Circle No 361



#### COMPUTER

The 6170 computer, a rugged version of the IBM PC/AT, uses an 80286 processor operating at 8 MHz and is 30% faster than IBM's 7532 industrial computer, according to the manufacturer. The computer alprogrammable simulation of transducers ± 4 to 20mA, 10 to 50mAdc thermocouples

 $\pm$  0.1  $\mu$ V to 10.0 Vdc and calibration to

1000V & ± 100mA



Stability and accuracy are quaranteed with **EDC's new Programmable DC Voltage and Current Calibration Standard** 

#### Model 520A is:

- Accurate (±0.002%) guaranteed for
- Highly stable ( ± 20 ppm for 12 months)
- Extremely versatile in voltage and cur rent modes

Voltage range:

- ± 100mVdc resolved to 0.1μV
- 10Vdc resolved to 10μV
- ± 100Vdc resolved to 100µV
- ± 10mAdc resolved to 0.01μA Current range:
  - 100mAdc resolved to 0.1µA (± 100V compliance with vari-
- able limit) Programmable with zero "crowbar"
- GP-IB IEEE-488 (1978) programmable Priced at \$2650

(1000Vdc range optional \$575).

#### The 520A is ideally suited for the following applications:

- Calibration of DVMs, DMM, meters, chart recorders, A/D converters, ATE, monitors, controllers, logging sys-
- Simulation of thermocouples and strain gages. (4 to 20 mA and 10 to 50 mA) + other transducers Note: compliance voltage up to 100Vdc.
- Linearity check of amplifiers and function modules

For more information call Bob Ross Engineering representatives throughout the U.S.A., Canada and Mexico. Distributors in Europe and selected countries throughout the world



ELECTRONIC DEVELOPMENT CORPORATION

11 Hamlin St., Boston, MA 02127, U.S.A. Tel: (617) 268-9696. TLX: 951596 (ELECDEVCO BSN). Cable Addr. ELECDEVCO BOS



#### POLYPROPYLENE



#### AC or DC

#### ... the People's Choice



AC or DC operation—it's the "Cube's" miniature Series 900 metallized and foil Polypropylene capacitors by a landslide. This broad line offers units with 67VAC/100VDC, 135VAC/200VDC and 270VAC/400VDC ratings and values from 0.0010 to 10 mfd. For higher voltages, call the Cube. Get complete information today on these "choice" capacitors . . . write or call Electrocube, 1710 So. Del Mar Ave., San Gabriel, CA 91776; Tel. (818) 573-3300.

**CIRCLE NO 95** 

## Choke in tiny spaces and shield, too.

**Excellent replacements for pot cores.** 

You pack a lot of choking into small space, lose little resistance — and also shield against EMI — with our miniature low-cost inductors. Perfect for sensitive high-density applications, as low-level power supplies, telecommunications, filters, switching circuits, audio frequency equalizers and special effects circuits.

Series RL1123 is 0.5" diam. x 0.9" long, 15 g. RL1124 is 0.25"x 0.7", 5 g. Inductances 1µH to 47.0 H, currents 0.0054 to 1.5AC amps. Windings configured on a ferrite bobbin; precisely set ferrite shield sleeve ("shell") ensures specific inductance required. Epoxy sealed and non-flammable. For automatic insertion, a clear PVC "cushioning" sleeve is optional. Coils can be supplied pre-bent and cut at our factory at additional cost.

Depending upon inductance, the 20% tolerance prices for RL1123 range \$1.12 to \$1.40/1,000-stock; for RL1124, \$.92 to \$1.08/1,000-stock; For our 46-page catalog of coils & transformers, call/write Marvin Scheck, 60 Jefryn Blvd. East, Deer Park, NY 11729. 1-516-586-5566. For engineering advice only call toll-free 1-800-645-5828, from anywhere outside of NY State.

#### RENCO ELECTRONICS, INC.

30 years of excellence in coil winding





#### COMPUTERS & PERIPHERALS

lows either software or hardware selection of 6- or 8-MHz operation. Its 12 expansion slots accommodate either PC/AT- or PC/XT-compatible boards. The computer comes with a 200W international power supply; a 250W supply is optional. Housed in a metal, rack-mountable 19-in, enclosure, the computer has dual cooling fans for operation to 122°F. You can add as many as three disk drives, including 360k- or 1.2M-byte floppy-disk drives and 10M- to 44Mbyte Winchester drives. Options include a tape-drive backup, 2M bytes of bubble memory, and nonvolatile EPROM expansion. The front panel locks to prevent unauthorized access to the power and reset buttons and the disk drives. From \$4000.

ISI International Corp, 1275 Hammerwood Ave, Sunnyvale, CA 94089. Phone (408) 743-4300. TWX 910-339-9369.

Circle No 362

#### STREAMING-TAPE DRIVE

The Roadrunner is a 1/4-in., halfheight streaming-tape drive that stores 60M bytes of data for disk backup. The drive comes with a standard QIC-36 interface. Its single-axis head-positioning mechanism eliminates head-registration problems, facilitates QIC-24 format implementation, and provides reliable cartridge interchanging among drives. An automatic gain control ensures correct data recognition. If your application requires start/stop capability, you can override the standard streaming-tape mode. The drive uses low-power CMOS circuitry and a brushless dc motor for 20W power consumption at a 100% duty Its dimensions are 5.25×8×1.63 in. Less than \$500 (1000).

North Atlantic Industries Inc, Peripheral Products Div, 60 Plant Ave, Hauppauge, NY 11788. Phone (516) 582-6060.

Circle No 363

### **OU ASKED FOR A FAST VMEbus 1/2" TAPE CONTROLLER THAT WOULD ALSO OPTIMIZE YOUR SYSTEM'S PERFORMANCE**



Tapemaster 3000 design engineers Bob Simning and Larry Hull

#### WE RESPONDED WITH THE TAPEMASTER 3000

From our unequalled experience as the leading supplier of Multibus compatible half inch tape controllers, we developed a new controller architecture for the VMEbus. We call it the "Dualranked FIFO."

The Dual-ranked FIFO is comprised of a 4 Kbyte Data FIFO and a proprietary, VLSI based, 32 byte Short Burst FIFO. The 4 Kbyte Data FIFO is coupled to the tape interface through a 2-level pipeline that enables read/write data rates up to 2 Mbytes/second. The 32 byte Short Burst FIFO links the Data FIFO to the VMEbus and is designed to attain burst transfer rates greater than 10 Mbytes/second.

With this architecture we've given you the ability to operate the slowest start/stop to the fastest GCR caching tape drives at maximum efficiency on the VMEbus. You've asked us for the highest performance products possible. At Ciprico we listen . . . and respond.

#### Other Tapemaster 3000 features include:

- 32 bit addressing, 8, 16, or 32 bit data transfers
- Programmable interrupt level and interrupt vector
- Hardware byte-order swapping
- Supports pass-through commands with optional parameters to support vendor-unique features
- Three cable exit options: through P2, from on-board connector, or through additional face-plate
- Scatter Read/Gather Write
- Reads or writes tape records of unknown and unlimited record length
- Device drivers for many operating systems including UNIX V and UNIX BSD 4.2
- Companion board to the Ciprico Rimfire 3200 VMEbus SMD-E disk controller

For information about our full line of Rimfire and Tapemaster products contact us at the following locations:




Ciprico Inc. 2955 Xenium Lane Plymouth, MN 55441 612/559-2034 European Office: United Kingdom Phone (0276) 682-149 Telex: 858306

... where people listen-and respond.

CIRCLE NO 97

UNIX is a registered trademark of AT&T. Rimfire, Tapemaster and Ciprico are all registered trademarks of Ciprico Inc.

#### NEW PRODUCTS: COMPONENTS & PACKAGING



#### TIME-DELAY RELAYS

The ERD and OR Series time-delay relays are designed to eliminate the need for hand wiring during board assembly. The ERD Series features digital timing circuits and plastic housings. The dpdt output has a 10A rating. You can order the relays with remote adjustment, onboard adjustment (knob and dial), or with

a fixed delay. Time delay ranges from 100 msec to 15 minutes, and repeat accuracy specs at  $\pm 0.5\%$ . These devices are available in delayon-make, interval, and single-shot versions. The OR Series units feature an open board construction and use an analog timing circuit. The output relay (spdt or dpdt) has a 10A rating. Delays range from 50 msec to 5 minutes, and repeat accuracy specs at  $\pm 2\%$ . ERD Series, \$15.64; OR Series, \$12.83 (500).

SSAC Inc, Box 395, Liverpool, NY 13088. Phone (315) 622-1000.

Circle No 364



### WHEREVER YOU SEE LCDS YOU WILL SEE OPTREX

Optrex liquid crystal displays, both custom and standard designs, are found in automotive dashboards, office equipment, telecommunications, industrial and medical instrumentation, plus an entire range of other applications.



With the combined strengths of it's parent companies — Asahi Class and Mitsubishi Electric — Optrex is a specialist in development, design, and the manufacture of LCD's.

The vast selection of standard LCD products by Optrex consists of:


Seven-segment display panels

- Alpha-numeric dot matrix modules with on-board character generator
- Full dot graphic modules

Options include:

- E/L backlighting
- Wide temperature range displays

With the combination of selection, availability, price, and above all, quality, you can see why so many have chosen Optrex LCD's.



Call the OPTREX LCD specialists at: ASAHI GLASS EMP. CORP. 26533 Evergreen Road, Suite 533 Southfield, Michigan 48076 U.S.A.

Telephone (313) 557-0018





#### MOTOR CONTROLLER

The SMC-202A provides computer or manual control of one or two stepping motors and comes in a sloped-front cabinet that includes all necessary power supplies, motor drives, and an RS-232C interface. Both rack-mount and circuit-board versions are available. A μP controls motions, including acceleration and deceleration ramping, storedprogram control, relative and absolute positioning, and automatic backlash compensation. The RS-232C port and an optional GPIB/ IEEE-488 bus allow simplified interfacing to computers, controllers, and terminals. Programming commands are single-letter mnemonic codes. Manual control features include a front-panel momentary toggle switch to run the motors, a front-panel speed control to adjust the stepping rate, and an optional joystick control to provide remote manual control of the two axes. Optional digital displays allow you to monitor the motors' positions at all times. \$995 (single-motor drive):

**CIRCLE NO 98** 

In addition to monitoring bus activity, you can simulate dynamic-data updates in real time. That means that if you are developing a new product that is going to work on a MIL-STD-1553 bus, you can



Systems Integration: The SSA 100 can simulate expensive or non-existent hardware and software.

user programmable processing algorithms and conversions.
You can then display the processed data in real time, by means of tables, graphs and charts for quick look capability.

Introducing a new real-time Systems Integration tool

#### Process MIL-STD-1553 data in real-time and simulate up to eight 1553 buses simultaneously with the new SSA 100

The new SSA 100 (Serial Systems Analyzer) is the first and only commercially available pre-processor/ simulator that processes real-time data on the MIL-STD-1553 data bus. Now, not only can you check MIL-STD-1553 protocol with our SBA 100, but you can look at specific data values and perform data analysis and reduction with the all new SSA 100 embedded in a proven parallel-processing system architecture.

time on as many as eight MIL-STD-1553 dual-redundant buses simultaneously. The SSA's modular system

The SSA's modular system architecture offers many optional features that make it easier for you to integrate and test MIL-STD-1553 products. Some options include IRIG time code generation and correlation capability, analog/discrete input and output capability, automatic error and limit checking, as well as a bi-directional DMA channel to your host computer. The DMA allows the SSA 100 to function as a preprocessing element within a system.

generate simulated remote

and do it in real

controller (BC) responses,

terminals (RT) and bus

As a stand-alone, the SSA 100 can pre-filter MIL-STD-1553 data and perform various pre-programmed or The SSA can also be programmed to distribute this processed data through the many available interfaces such as IEEE 488,

RS 232, analog/digital outputs, and to mass storage devices including digital tape and disk controllers.

If MIL-STD-1553 avionics is your arena, then the SSA 100 will help you save time and money. Contact Loral Instrumentation today.



Flight Dynamics Simulation: The SSA 100 substantially reduces the time required to write real-time software in the host processor.



#### INSTRUMENTATION

A SUBSIDIARY OF LORAL CORPORATION

8401 Aero Drive San Diego, California 92123 (619) 560-5888 Telex 695222



## THE FASTEST SAMPLE-AND-HOLD AMPS IN THE GALAXY? AS FAR AS WE KNOW, YES!

#### Galaxy's Fastest: HA-5330

This sample-and-hold's acquisition time: 0.5 µs to 0.01%! That beats all other monolithics known to man. It also includes a 90pF hold capacitor dedicated to high-speed performance. Impressive specs:

- Acquisition time: 0.5 μs
- Droop rate: 0.01 μV/μs (fixed) (No external hold capacitor)
- DC gain: 2x10<sup>7</sup> V/V
  Aperture time: 20 ns
- Hold step error: 0.5 mV, adjustable to zero

#### Performance Leader: HA-5320

For a wide range of 12-bit high-speed data acquisition systems: acquisition time,  $1.0 \mu s$  to 0.01%. It includes an internal 100pF hold capacitor with the option to add capacitance externally. Impressive specs:

- Acquisition time: 1.0 to 5 μs
- Droop rate: .05 to .005 μV/μs (For OpF to 1000pF of added capacitance)
- DC gain: 2x106 V/V
- Aperture time: 25 ns
- Hold step error: 1.0 mV

#### Universal: HA-2420 & HA-2425

Add an external hold capacitor and HA-2420 or HA-2425 becomes a highperformance sample-and-hold amp with acquisition time of 3.2 µs to 0.01% or extremely low droop rate (for slower operation). Impressive specs:

- Acquisition time: 3.2 to 500 μs
- Droop rate: .005 to .000005 μV/μs (For 1000pF to 1,000,000pF of added capacitance)
- DC gain: 5x104 V/V
- Aperture time: 30 ns
- Slew rate: 7V/µs

All three members of the Harris sample-and-hold amplifier family can operate at gains greater than 1, eliminating the need for external scale amplifiers in many cases. In addition, they are specified for operation with ±15 Volt supplies, but they work well from ±12 Volts to ±18 Volts. Options include 14-pin dual-in-line or 20-pin surface-mount packaging plus either military or commercial temperature ranges. Applications include: automatic offset zeroing, peak detector, de-glitcher, gated op amp, and input conditioner for a wide range of analogto-digital converters.

For information contact Harris/MHS Semiconductor Sales Ltd., Eskdale Road, Winnersh, Wokingham, Berks, RG11 5TR, England.

Harris Semiconductor: Analog - CMOS Digital - Gallium Arsenide - Semicustom - Custom - Hybrids



For your information, our name is Harris.

\$1170 (2-motor drive).

Maxwell Electronics Inc, Dept C, Box 12033, Research Triangle Park, NC 27709. Phone (919) 846-1633.

Circle No 365



## CONNECTORS

Series 266 IEEE-488 shielded pcboard connectors are available with 0.125- and 0.17-in. tail lengths. They are preassembled to ease board installation. A plug version is available in grid patterns measuring  $0.085 \times 0.151$  in. or  $0.085 \times 0.160$ in.: a receptacle version comes in  $0.085 \times 0.169$ -in. or  $0.085 \times 0.160$ -in. patterns. Both versions are available in 24-, 36-, and 50-position versions. You can choose from a variety of screw-lock hardware kits and grounding straps, depending on your application. The connectors feature copper-alloy contacts with selective gold-over-nickel plating on the mating end and tin on the tail. 36-position connector, \$2.14 (5000).

Winchester Electronics, Main St and Hillside, Oakville, CT 06799. Phone (203) 755-5000.

Circle No 366



# THERMAL PRINT HEADS

Onboard electronics for the SM-Series of thermal print heads include double-latched printer inputs. Suit-

able for graphics applications, the devices print on a thermal roll or label stock, or print through thermal transfer ribbon onto plain paper. Printing time is 4 msec per cycle (2 msec on; 2 msec off) for dot densities as high as 102 dots per in. and speeds as high as 4 in./sec. The dot line is along the substrate edge for early last-line visibility. Other

features include thick-film construction, a factory-replaceable protective bar in front of the resistive printing element, and  $HVI^2L$  32-bit IC drivers. Thermistor preheaters are optional. A minimum thermal life of  $50\times10^6$  dot lines is guaranteed. The units are ready to use with an integral heat sink and connector-terminated PVC cable. \$160

# From A P PRODUCTS: The first Surface Mount Test Clip.

There has never been anything like it.
A P PRODUCTS has broken into a new frontier in testing: the SURFACE MOUNT TEST CLIP. Our exclusive design provides gripping tension on all four sides when testing Plastic Leaded Chip Carrier (PLCC) style integrated circuits. This provides a faster and easier attachment on PLCCs.
But we didn't stop there. Our narrow body design allows components to be tested with as little as . 100" lead-to-lead spacing.


Probe access points are immediately visible for fast and safe lead testing.

And staggered contact rows on 100" centers allow for easy probe attachment. Our SURFACE MOUNT TEST CLIP is available in gold plated or alloy versions.

Get the best grip on your work. Call TOLL FREE, 800-321-9668 for the name of the APPRODUCTS distributor near you. (In Ohio, call collect: (216) 354-2101).



A P PRODUCTS INCORPORATED 9325 Progress Parkway 8ox 540, Mentor, Ohio 44060 [216] 354-2101, TWX: 810-425-2250




**CIRCLE NO 101** 

to \$400. Delivery, 90 days ARO.

Gulton Industries Inc, Graphic Instruments Div, Gulton Industrial Park, East Greenwich, RI 02818. Phone (201) 548-6500. TWX 710-387-1500.

Circle No 367



## HYBRID T/H AMPLIFIER

Suitable for throughput rates as high as 5 MHz, the hybrid THA-05210 track/hold amplifier offers a 150-nsec acquisition time to  $\pm 0.01\%$  of full scale for a 10V step. It also

conforms to the reliability requirements of MIL-STD-883C. Other electrical performance figures include a 0.005% linearity error, 60psec aperture jitter, 74-dB feedthrough attenuation, a roomtemperature droop rate of 0.5 μV/μsec, and a 16-MHz small-signal bandwidth. Operating ranges of -25 to  $+85^{\circ}$ C and -55 to  $+125^{\circ}$ C are available. The circuit consists of a unity-gain inverting op amp with series and shunt switches at its summing point. Placing the device in the hold mode opens the series switch and closes the shunt switch; placing it in the track mode has the opposite effect. While in hold mode, the analog output is held constant by the hold capacitor at the value just prior to the opening of the series switch. The THA-05210 is pin compatible with the HTC-0300A and TP4860 but uses fewer internal components than these hybrid units. Full military version, \$179 (100).

Delivery, stock to eight weeks

ILC Data Device Corp, 105 Wilbur Pl, Bohemia, NY 11716. Phone (516) 567-5600. TWX 510-228-7324.

Circle No 368

## SMART DISPLAY

The HPDFL-1414 is a red, 0.112-in., 4-character monolithic alphanumeric display that combines built-in RAM, ASCII decoders, and LED drive circuitry. It features electrostatic-discharge protection furnished by large input-protection diodes, an access time of 160 nsec at 25°C, and full TTL compatibility. The device is wave solderable and is specified for operation over -40 to +85°C. \$16.35 (1000).

Hewlett-Packard Co, 1820 Embarcadero Rd, Palo Alto, CA 94303. Phone local office.

Circle No 369



# KEYBOARDS SO THIN... YOU'D THINK THEY WERE MEMBRANES



Grayhill Series 89 Keyboards offer the reliability and performance benefits of snap dome contacts, packed into a board as thin as a membrane switch! Only 1/10" thick plus tactile and audible feedback for the operator.

- 3x4, 4x4 or 5x4 format on 0.75" centers (19.05 mm)
- Colorful standard or custom graphic overlays
- Matrix, 2 out of 7(8), or SP/common bus circuitry

For FREE literature, including specifications

and prices, contact

- 3,000,000 operations per button at logic level loads
- Sealed against common contaminants; washable surface
- Available off-the-shelf from Grayhill or your local Grayhill distributor.



561 Hillgrove Ave., La Grange, IL 60525 • (312) 354-1040 • TWX 910-683-1850


Sunnyvale, Ca. 94086 408 737-7727

"Computer Modules, Inc.


1190 Miraloma Way #Y

\*TM INTEL CORP

\$255 OEM QTY



# NEW PRODUCTS: ICs & SEMICONDUCTORS



# SCSI CONTROLLER

This company claims that the MB87030 is the first SCSI chip to support ANSI X3T9.2 (Revision 10) standards and to operate in synchronous and asynchronous modes. In the synchronous transfer mode, its maximum throughput rate is 4M bytes/sec. The single-chip LSI controller can replace 30 to 50 TTL and memory devices, and it can operate as a transmitter or receiver. It handles synchronous data transfer with a programmable offset of 8 bytes max and in four selectable speeds to 4 MHz. Standard SCSI protocols

and procedures are built-in. The device has an 8-byte FIFO buffer and a 24-bit counter that keeps track of byte counts, phase-control logic, arbitration, and selection logic. In addition, it has provisions for single-ended and differential connections. In an 88-pin pin-grid-array package, \$35 (1000).

**Fujitsu Microelectronics Inc,** Integrated Circuits Div, 3320 Scott Blvd, Santa Clara, CA 95054. Phone (408) 727-1700. TWX 910-338-0190.

Circle No 370

# MICROPROCESSOR

The 80186-12  $\mu P$  is a 12.5-MHz version of the 16-bit 80186  $\mu P$ . According to the manufacturer, the chip can operate twice as fast as its predecessor. Because it's manufactured with a proprietary 1.5- $\mu m$  HMOS-III process, it has a 30% smaller die size. The  $\mu P$  combines a CPU with the equivalent of 20 components on


one chip and is available in three packages: a PLCC, a pin-grid-array package, and an LCC. You can choose from commercial, industrial, and military grades. \$36 (100). Samples are available now, and production quantities are scheduled for mid-1986.

Intel Corp, 3065 Bowers Ave, Santa Clara, CA 95051. Phone (408) 496-4580.

Circle No 371

# **CMOS LOGIC DEVICES**

The V54/74 ACT family of CMOS interface logic devices provides 50 interface functions, including 8-, 9-, and 10-bit buffers, latches, flipflops, and transceivers. Fabricated using a proprietary, 1.6-µm double-level-metal CMOS process, the devices operate over the industrial temperature range (-40 to +85°C) at frequencies to 75 MHz. Constant current drive is 48 mA, typical



# ICs & SEMICONDUCTORS

propagation delay is 5 nsec, and typical quiescent power consumption is 5  $\mu$ W. The company guarantees that ESD protection exceeds 2000V. The devices are housed in 20- or 24-pin plastic DIPs. Prices start at \$3.25 (100).

**VTC Inc,** 2401 E 86th St, Bloomington, MN 55420. Phone (612) 851-5000.


Circle No 372

## SMT TRANSISTORS

These 10 bipolar and three TMOS power MOSFETs come in D packs, which the manufacturer claims are the first power packages designed for surface-mount applications. The D pack resembles a miniature TO-220 enclosure and offers costreducing features, including the elimination of pc-board through holes, reduction of the size of the pc board, use of both sides of the board, and the ability to handle power levels exceeding 1W. Prices range from \$0.54 to \$1.53 (100).

Motorola Semiconductor Products Inc, Box 20912, Phoenix, AZ 85036. Phone (602) 244-4911.

Circle No 373




# 64k-BIT EEPROM

The Am2864B EEPROM features page-mode write and data-bar polling operations and a 250-nsec access time. Data-bar polling on all pins allows a single read-and-comparison operation to determine the chip's status and eliminates the need for

external hardware. The 32-byte page-mode operation allows you to write one to 32 bytes of data in one write cycle; according to the manufacturer, the write cycle takes half the time that other 64k-bit EEPROMs require. Organized as 8k×8 bits, the EEPROM has a ready/busy pin that automatically signals the  $\mu P$  that the write cycle is complete. Available in a sidebrazed package or a ceramic DIP, \$22.27 (100).

Advanced Micro Devices Inc, Box 3453, Sunnyvale, CA 94088. Phone (408) 982-7448.

Circle No 374





#### MODEM IC

The XR-2123A belongs to the phase-shift-keying (PSK) family of devices for full-duplex (to 1200 bps) and half-duplex (to 2400 bps) modem applications. You can program the IC to meet Bell 212A and 202 or CCITT V.22 and V.26 specifications; the device provides the ±7-Hz carrier-capture range required to meet the CCITT standards. If you want the modem to operate asynchronously, you'll need the XR-2125 synchronous-to-asynchronous converter. Phase-locked loops provide digital demodulation functions, and the modulator provides a synthesized sine-wave output in a dibit PSK format. The CMOS IC requires ±5V supplies and operates between 0 and 70°C. It comes in a 28-pin plastic or ceramic DIP. \$13.85 (100).

**Exar Corp,** 750 Palomar Ave, Sunnyvale, CA 94088. Phone (408) 732-7970. TWX 910-339-9233.

Circle No 375





CHECK THE ITINERARY FOR THE DATE WE VISIT YOU!









# 1986 EDN CARAVAN TRAVELING ELECTRONIC SHOW

February 24 to March 28 (first half)

	TIME	SITE	DATE	TIME	SITE
day	8-9:30	IBM CORPORATION	3/10	3-4:30	TELEX TERMINAL COMMUNICATIONS
	AM	1000 NW 51st St., Boca Raton, FL	Monday	PM	3301 Terminal Dr., Raleigh, NC
day	10:15-12	IBM CORPORATION	3:11	8:30-9:45	AT&T TECHNOLOGIES, INC.
	AM	1626 S. Congress Ave., Del Ray, FL	Tuesday	AM	204 Graham Hopedale Rd., Burlington, NC
day	1:30-3	MOTOROLA INC.	3/11	2:30-4:30	GENERAL ELECTRIC CO.
	PM	1500 NW 22nd Ave., Boynton Beach, FL	Tuesday	PM	1501 Roanoke Blvd., Salem, VA
day	8-9:30	BENDIX AVIONICS	3/12	9-10:30	GENERAL ELECTRIC CO.
	AM	2100 NW 62nd St., Ft. Lauderdale, FL	Wednesday	AM	Mountain View Rd., Lynchburg, VA
day	10:30-12	RACAL-MILGO	3/12	1:30-3:30	GENERAL ELECTRIC CO.
	AM	1601 N. Harrison Parkway, Sunrise, FL	Wednesday	PM	U.S. Hwy 29 North, Charlottesville, NC
day	2-4:30	MOTOROLA INC.	3/13	9-11	IBM CORPORATION
	PM	8000 W. Sunrise Blvd., Plantation, FL	Thursday	AM	9500 Godwin Dr., Manassas, VA
nesday	9-12	HARRIS CORPORATION GOVERNMENT SYSTEMS	3/13	1-2:45	E-SYSTEMS, INC. MELPAR DIVISION
	AM	Palm Bay Rd., Palm Bay, FL	Thursday	PM	7700 Arlington Blvd., Falls Church, VA
nesday	2-3:30	HARRIS CORPORATION SATELLITE COMMUNICATIONS	3/13	3:30-4:30	E-SYSTEMS, INC. MELPAR DIVISION
	PM	1380 Harris Rd., Melbourne, FI	Thursday	PM	11225 Waples Mill Rd., Fairfax, VA
sday •	8-9:30	MARTIN MARIETTA AEROSPACE	3/14	9-11	LITTON SYSTEMS, INC. AMECOM DIVISION
	AM	E. Sand Lake Rd., Orlando, FL	Friday	AM	5115 Calvert Rd., College Park, MD
sday	10:30-12 AM	MARTIN MARIETTA AEROSPACE 12506 Lake Underhill Dr., Orlando, FL	3/14 Friday	1:30-3 PM	WESTINGHOUSE ELECTRIC OCEANIC DIVISION Oceanic Dr., Annapolis, MD
sday	2:30-4:30	GENERAL ELECTRIC CO.	3/17	8:30-11	WESTINGHOUSE ELECTRIC AESD & CCD
	PM	1800 Volusia Ave., Daytona Beach, FL	Monday	AM	Baltimore Int'l Airport, Baltimore, MD
B	8-9:30	E-SYSTEMS, INC. ECI DIVISION	3/17	1-2:15	BENDIX COMMUNICATIONS DIVISION
ay	AM	1501 72nd St. North, St. Petersburg, FL	Monday	PM	1300 E. Joppa Rd., Baltimore, MD
ıy	10:30-12 AM	PARADYNE CORPORATION 8550 Ulmerton Rd., Largo, FL	3/17 Monday	3-4:30 PM	AAI CORPORATION York Rd. & Industry Ln., Cockeysville, MD
у	2-4:15	HONEYWELL INC. AVIONICS	3/18	9-11:30	RCA CORPORATION
	PM	13350 Hwy 19, Clearwater, FL	Tuesday	AM	Front & Cooper St., Camden, NJ
day	8:30-9:45 AM	CHRYSLER MILITARY-PUBLIC ELECTRONIC SYSTEMS 5021 Bradford Dr., Huntsville, AL	3/18 Tuesday	1:30-4 PM	RCA CORPORATION Marne Hwy., Moorestown, NJ
day	10:30-12	CHRYSLER ELECTRONICS DIVISION	3/19	9-12	AT&T BELL LABORATORIES
	AM	102 Wynn Dr., Huntsville, AL	Wednesday	AM	Crawfords Corner Rd., Holmdel, NJ
day	1-2	SCI SYSTEMS, INC.	3/19	2-4	AT&T INFORMATION SYSTEMS
	PM	5000 Technology Dr., Huntsville, AL	Wednesday	PM	200 Laurel Ave., Middletown, NJ
day	3-4:30	SCI SYSTEMS, INC.	3/20	8:30-9:45	SYSTEMS DEVELOPMENT CORP., A BURROUGHS
	PM	8600 S. Memorial Pkwy, Huntsville, AL	Thursday	AM	Swedsford Rd., Paoli, PA
day	8:30-10	SCIENTIFIC-ATLANTA	3/20	10:30-12	BURROUGHS SDG
	AM	4311 Communications Dr., Norcross, GA	Thursday	AM	Swedsford Rd., Paoli, PA
sday	10:45-12	AT&T TECHNOLOGIES	3/20	2-4	SPERRY CORPORATION
	AM	2000 Northeast Expressway, Norcross, GA	Thursday	PM	Union & Jolly Rd., Blue Bell, PA
day	2-3	SCIENTIFIC-ATLANTA	3/21	9-11	HONEYWELL PROCESS CONTROL DIVISION
	PM	3845 Pleasantdale Rd., Doraville, GA	Friday	AM	1100 Virginia Dr., Ft. Washington, PA
nesday	8:30-9:45	ROCKWELL INTERNATIONAL CORPORATION	3/21	1:30-3	RCA CORPORATION
	AM	1800 Satellite Blvd., Duluth, GA	Friday	PM	201 Washington Rd., Princeton, NJ
nesday	10:30-11:30 AM	ROCKWELL INTERNATIONAL CORPORATION Gwinnett Industrial Park, Norcross, GA	3/24 Monday	9-10:30 AM	AT&T BELL LABORATORIES 555 Union Blvd., Allentown, PA
sday	9-10:30	NCR CORPORATION	3/24	2-4	LOCKHEED ELECTRONICS
	AM	3325 Platt Springs Rd., West Columbia, SC	Monday	PM	US Hwy 22, Plainfield, NJ
sday	2-4 PM	IBM CORPORATION 1001 Harris Blvd., Charlotte, NC	3/25 Tuesday	9-11 AM	AT&T BELL LABORATORIES 600 Mountain Ave., Murray Hill, NJ
ay	9-11:30	IBM CORPORATION	3/25	1:30-4	AT&T BELL LABORATORIES
	AM	Research Triangle Park, NC	Tuesday	PM	Whippany Rd., Whippany, NJ
ay	1-2:15	NORTHERN TELECOM INC. BNR	3/26	9-11	HEWLETT-PACKARD CO.
	PM	Research Triangle Park, NC	Wednesday	AM	150 Green Pond Rd., Rockaway, NJ
ay	3-4:15	IBM CORPORATION	3/26	1:30-4	SINGER CO. KEARFOTT DIVISION
	PM	2520 North Blvd., Raleigh, NC	Wednesday	PM	150 Totowa Rd., Wayne, NJ
0	8:30-9:30	ITT TELECOMMUNICATIONS 2912 Wake Forest Rd., Raleigh, NC	3/27	9-11	ITT DEFENSE COMMUNICATIONS
Iday	AM		Thursday	AM	492 River Rd., Nutley, NJ
0	10:15-11:30	ITT TELECOMMUNICATIONS 3127 Smoketree Ct., Raleigh, NC	3/27	1-3	ITT AVOINICS
Iday	AM		Thursday	PM	390 Washington Ave., Nutley, NJ
0 nday	1-2 PM	ITT TELECOMMUNICATIONS 6131 Falls of the Neuse Rd., Raleigh, NC			

# NEW PRODUCTS: COMPUTER-SYSTEM SUBASSEMBLIES



# **ACQUISITION SYSTEM**

The Premas 2-board set plugs into an IBM PC, PC/XT, or PC/AT to sample data from four input channels. It comes with floppy-disk-based support software that directs the hardware to sample the data channels, store the data on the PC's floppy or hard disk, and display a plot on the PC's monitor, all at the same time. By storing data to a disk


in real time, the acquisition system can store more data than systems that store only to the PC's memory. Using the software, you program each of the four channels to one of four input ranges—±300 mV, ±3V, ±30V, or ±300V—and to one of three degrees of resolution—12, 16, or 19 bits. Sample rates for the three degrees of resolution are 33, 10, and 2.5 samples/sec, respectively. You can program the board for autozeroing and autoranging modes. \$1465.

Dataq Instruments Inc, 100 Lincoln St, Akron, OH 44308. Phone (216) 434-4284.

Circle No 377

# SINGLE-BOARD µP

The MC68020 µP powers the Micro-20 single-board computer. The computer includes 2M bytes of RAM, as much as 256k bytes of EPROM, four serial ports, and an 8-bit parallel



port. A controller for 51/4-in. floppy disks, an SASI-peripheral interface, and a 16-bit expansion connector attach I/O devices to the computer. The 8.8×5.75-in. board mounts in the same space as a standard 51/4-in. floppy-disk drive, and it uses the same supply voltages as the drive. A separate board, included with the computer, provides RS-232C-level translation and DB-25-type connectors for the serial ports. The computer draws 4.5A from a 5V supply and 125 mA from a 12V supply; it generates its own -12V supply. With 020Bug monitor/debugger and






# COMPUTER-SYSTEM SUBASSEMBLIES

hardware diagnostics, \$2200 (25).

GMX Inc. 1337 W 37th Pl. Chicago, IL 60609. Phone (312) 927-5510. TWX 910-221-4055.

Circle No 378



# TAPE CONTROLLER

The STC-TSQ11 emulates Digital Equipment Corp's TK25/TS11 to connect LSI-11 computer systems to QIC-2 streaming-tape cartridge drives. The drives back up largecapacity hard disks, saving or restoring 60M bytes of data on a 1/4in.-tape cartridge in 12 minutes. The controller connects to LSI-11 computers, including the MicroVAX II, and works under operating systems and applications programs that control the TK25/TS11. Its dual-wide Q Bus module fits in a Q Bus backplane slot. \$1250.

Sigma Information Systems, 3401 E La Palma Ave, Anaheim, CA 92806. Phone (714) 630-6553. TLX 298607.

Circle No 379



## MS-DOS ON STD BUS


You can run programs developed under MS-DOS on the STD Bus by adding either the STD-DOS prototyping system (PS 1.1) or the STD-DOS OEM system (OS 1.1) to the STD Bus. Both systems plug into

the STD Bus and connect to IBM PC-compatible computers through an RS-232C link. You can develop programs for the STD Bus on the PC and then download them to the systems. Both systems include MS-DOS 3.1 in ROM, support utilities on floppy disks, and 8088-based CPU cards. The PS 1.1 also offers four memory cards, an extender

card, a card cage, a power supply, and the RS-232C cable. \$2895. The OS 1.1 has only the CPU, two memory cards, and utility disks, but it can run applications developed on the PS 1.1. \$1690.

Pro-Log Corp, 2411 Garden Rd, Monterey, CA 93940. Phone (408) 372-4593, TWX 910-360-7082,

Circle No 380



- 50¢ per watt in volume
- Three to five outputs
- 100 amp output
- Parallel operation
- FCC EMI filters
- UL / CSA / IEC / VDE approvals pending.

# Call Our Toll Free Information Hot Line Today! (800) 645-2074

In Texas Call (214) 231-1456 Jack Barry, Vice President Marketing Steve Mole, Sales Manager Bryan Bristol, Customer Service



855 East Collins Boulevard Richardson, Texas 75081



# GPIB > PC

# **Hardware Flexibility**

- Low cost for instrument control
  - 300K bytes per second
  - \$395 complete with software
- High performance data links
  - Maximum speed of GPIB
  - On-board buffering

# Software

- Software specially tested for the IBM PC and compatibles
- Over \$1,000,000 in software development
- Easy to use, yet handles any GPIB application
- Works with Lotus 1-2-3
- UNIX, DOS and over 12 languages

# **Applications Support**

- Applications Library with sample programs & TIPS for all major instruments
- Full staff of Applications Engineers dedicated to support your specific needs

# Other IEEE-488 Products


- Interfaces & Software for
  - Multibus VMEbus
  - DEC Q-bus & UNIBUS
  - STD & S-100 bus
- General GPIB Products
  - GPIB Bus Testers
  - GPIB Bus Extenders
  - Stand-Alone Controllers



1 (800) 531-GPIB In Texas (800) IEEE-488 Telex: 756737 NAT INST AUS

**CIRCLE NO 36** 

# **COMPUTER-SYSTEM SUBASSEMBLIES**



# STD BUS BOARDS

STD Bus-compatible single-board computers in the VL-7800 Series. which are plug-in replacements for Pro-Log's Z80-based models, are available in 6-MHz versions. The series comprises three processor boards, each of which is available in 2.5-, 3.68-, 4-, and 6-MHz versions. The VL-7806 has two RS-232C channels; the VL-7807 provides one RS-232C channel and one 8-bit Centronics port. The VL-7842 version offers either two RS-422 channels or one RS-422 and one RS-232C channel. All three boards use a buffered Z80 CPU and include sockets for as much as 128k bytes of onboard RAM or EPROM; three generalpurpose, 8-bit counter/timers; and vectored interrupt inputs. C4 Basic for industrial-control applications and the companion Novos (nonvolatile operating system) permit program storage in nonvolatile IC memory. The boards carry a 3-year warranty. 6-MHz versions, \$300 to \$330.

VersaLogic Corp, 87070 Dukhobar Rd, Eugene, OR 97402. Phone (800) 824-3163; in OR, (503) 485-8575.

Circle No 381


# 1-BOARD COMPUTER

The Cobra/16 single-board computer is based on the DEC J11 16-bit CPU chip. The module includes a 15-MHz CPU with floating-point arithmetic, a 4k-byte bipolar cache

memory, 512k bytes of dynamic RAM, 5½-in. ST506 Winchester disk and SA850 floppy-disk controllers, and a 4-port serial interface. The board measures 11.5×12 in. and supports PDP-11-compatible operating systems, including RSX11/M, RSX11/M-Plus, RT11, RSTS/E, TSX-Plus, Mumps, and Unix. It's available as a board-level product, in a desktop chassis, or in a custom system. Less than \$3000.

General Robotics Corp, 57 N Main St, Hartford, WI 53027. Phone (414) 673-6800. TLX 269686.

Circle No 382



# X.25 INTERFACE

The 5250 single-board MicroVAX front-end communications processor with onboard X.25 firmware allows users of MicroVAX II and other Q Bus computers to connect to packetswitched networks, including Telenet, Tymnet, and DDN, Two versions are available: The Basic Mode comes with 128k bytes of memory and standard network default capacities. The Extended Mode provides 512k bytes of memory, frame and packet sizes of 1024 bytes, and extended sequence numbering. Both versions accommodate as many as 128 switched or permanent circuits at network-line speeds as fast as 64k bps. Basic Mode, \$5290; Extended Mode, \$5890.

Advanced Computer Communications, 720 Santa Barbara St, Santa Barbara, CA 93101. Phone (805) 963-9431. TWX 910-334-4907.

Circle No 383

Staying

Ahead With


VME

Requires

More Than

Brute

Force



# Heurikon's Technology and Experience in Microcomputers Add Value Beyond Brute Computing Power.

The HK68/V<sup>™</sup> family of processor boards combines the advantages of VME architecture with Heurikon's thirteen years of microcomputer experience and expertise. With these processors, Heurikon keeps you and your application moving. Smoothly. Dependably. Toward your goal.

There is no more powerful or versatile single VME processor board for UNIX™, image processing, graphics, communications and scientific applications than the HK68/VIO.

Some key product features include:

- No wait state 10 or 12.5 MHz 68010 CPU
- Up to 1 MByte of on-card dual ported DRAM
- 128K of EPROM
- Single cycle mode DMAC
- Optional MMU
- Full SCSI high speed parallel bus
- 2 serial ports
- Optional floating point processor

For real time systems, the HK68/VE combines the power of the HK68/VI0 with the agility and economy you require. For industrial vision, data acquisition or control applications, the HK68/VE is an unsurpassed price performer.

CIRCLE NO 110

To stay ahead, Heurikon offers another valuable tool: *Technical Support* to help solve your complex application problems. To learn more, just call:

1·800·356·9602 HEURIKON

Heurikon Corporation, 3201 Latham Drive, Madison, WI 53713. 608-271-8700.

UNIX is a trademark of Bell Laboratories, Inc.

# NEW PRODUCTS: INSTRUMENTATION & POWER SOURCES




# 32-BIT BUS ATE

The Z3200 tester for boards with 32-bit buses includes a performance-test unit, which comprises two bus-timing emulators and which is synchronized with a functional-test unit. The tester features diagnostics via a guided probe. Busstructured boards with or without μPs can be tested at full speed, with bus-cycle and pattern bursts to 12 MHz. Timing-interface pods are available for boards based on 80186. 80286, 68000, and 68020 μPs. In combination with the programmable bus pod, the tester can emulate Multibus or VME Bus boards.

A measurement module provides CRC readings to 40 MHz and frequency measurements to 100 MHz. \$250,000.

Zehntel Automation Systems, 2625 Shadelands Dr., Walnut Creek, CA 94598. Phone (415) 932-6900.

Circle No 384



# STD BUS DEVELOPER

The Over-Nighter, a portable version of the company's Z80-based STD Bus development system, contains an 8-slot card cage, a 75W

switching power supply, a fan, two floppy-disk drives, and STD Bus cards for a CP/M development computer. The unit measures 17×17×7 in, and fits a 19-in, rack, Options include additional mounting rails, EPROM programmers, terminals, printers, and development software as well as 10-, 12-, and 16-slot card cages and a 10M- or 20M-byte harddisk drive. A 4-MHz, Z80-based configuration with 64k bytes of static RAM, an 8-slot card cage and power supply, two card-mounted microfloppy-disk drives, and CP/M operating system costs \$2790.

Computer Dynamics Inc. 105 S Main St, Greer, SC 29651. Phone (803) 877-7471.

Circle No 385

# DEVELOPMENT BOARD

With the Support 329 DB01 development board, you can evaluate the company's PD32HC01, an interface

Get a handle on simpler wire connections

allows frequent circuit board

for flammability.

data sheet on the PCB3S/D.

"Quality By Design"

removal/insertion with virtually no

pad scoring. Selective goldplating

For quick, easy wire connections, all you need is a screwdriver. Just strip end, insert wire, tighten screw - no wire lugs, no soldering, no crimping, no wire wrapping.

#### **Highest Density Screw-Dedicated PC** Connector

The PCB3S/D is available for single or double sided boards with .156" centerlines. Non-rotating wire contacts handle solid or stranded wire #12 thru #30 AWG.


## Up to 500 insertions/removals

Dual fingers ensure reliability thru redundant board contact, while their cantilever design

.with the Buchanan PCB 3S/D connector.



AMERACE CORPORATION 1065 FLORAL AVENUE, UNION NEW JERSEY 07083 (201) 289-8200





IC for Texas Instruments' TMS 32010 digital-signal-processor chips. The board allows you to access the PD32HC01 using TI's EVM module or XDS development system. The interface IC provides a serial codec interface, an RS-232C port, I/O and interrupt control, an I/O expansion interface, and a 2400-Hz bit-rate generator. The board also includes a µlaw Codec, RAM and ROM, a 32010 socket, and an uncommitted breadboarding area for prototyping

additional functions. \$475.

Pacific Microcircuits Ltd, Product Development Group, 240 H St, Blaine, WA 98230. Phone (604) 536-1886.

Circle No 386



# IN-CIRCUIT ATE

The Model 875 in-circuit tester can have as many as 640 hybrid, non-multiplexed test points. The tester runs the same software and accepts the same test programs as other devices in the 800 Series. The tester

can have as many as 512 digital test points plus analog test points backed by a 16-bit A/D converter. The unit incorporates a 68010-based computer and runs the Unix operating system. An operator-training package is included. The Model 875 with 208 test points costs less than \$85,000.


Zehntel Automation Systems, Box 8016, Walnut Creek, CA 94596. Phone (415) 932-6900. TLX 3716185. Circle No 387

# 600W SWITCHER

The Case 22/23 switching power supply delivers 300 to 600W from as many as seven outputs. The supply measures  $3\times5\times14.25$  in. and meets UL, CSA, IEC, and VDE certification requirements. Load regulation is 1% for all outputs having remote sensing or 2% for outputs without remote sensing. Line regulation is  $1\%\pm15\%$  of line-voltage range. The

# SEE WHAT A DIFFERENCE CMOS MAKES!

CMOS is fast becoming the chosen technology for developing integrated circuits. That's because CMOS ICs are able to implement ultra-complex system-level functions on a chip!



Now you can meet the special challenges posed by this new breed of ICs with *A Designer's Guide to CMOS ICs*. You'll learn the advanced design and fabrication techniques required. Plus the latest linear and digital CMOS ICs available.

Mail coupon to: CMOS IC reprints — EDN Magazi	ne
Cahners Building	
275 Washington Street	
Newton MA 02158-1630	

Please send \_\_\_\_\_ copies of A Designer's Guide to

CMOS ICs (92 pages)

☐ \$6.95 USA surface mail ☐ \$8.95 non USA air mail Check or money order made out to *EDN REPRINTS* must accompany each order. No COD. Mass. residents add 5% sales tax.

Mail	bookl	et to:

NAME			-	
TITLE				
COMPA	NY	 		_

ITY STATE ZIP \_\_\_\_

# **INSTRUMENTATION & POWER SOURCES**

supply has a built-in fan. Less than \$1/W (100). Delivery, six to eight weeks ARO.

Qualidyne Systems Inc, 3055 Del Sol Blvd, San Diego, CA 92153. Phone (619) 575-1100.

Circle No 388



# IN-CIRCUIT EMULATOR

Unlike other small emulators, the Icebox has 65,535 true hardware breakpoints and performs full-speed emulation. It maintains the Z80 and NSC800 refresh signals during all phases of operation, so that dynamic memories in the target system will retain their data. The emulator uses

the target system's V<sub>CC</sub> to operate, requiring less than 500 mA. If the target system doesn't have enough available power, you can use an external power source. The emulator is available for the Z80, 8085, and NSC800 processors. \$600.

**Softaid Inc**, Box 2412, Columbia, MD 21045. Phone (301) 792-8096.

Circle No 389


tions, maximum and minimum points, and other mathematical characteristics. The calculator has a  $2.17 \times 1.5$ -in. LCD with a resolution of  $96 \times 64$  dots. The unit weighs about 5.5 oz and measures  $3.3 \times 6.5 \times 0.5$  in. \$99.95.

Casio Inc, 15 Gardner Rd, Fairfield, NJ 07006. Phone (201) 575-7400.

Circle No 390

# GRAPHIC CALCULATOR

At the touch of a button, the FX7000G scientific calculator lets you make graphic representations of numerical equations. Furthermore, the calculator displays changes in numerical values as continuous graphic fluctuations. You can simultaneously portray two or more function equations in one graphic display or mix several equations as a combined graph. The FX7000G also displays the intersection and approach of different func-



# MIL SUPPLIES

Military power supplies in the Powereg Series provide as many as five outputs, output voltage ranges of 2 to 28V dc, and output current ranges from 2 to 70A. The supplies operate over -55 to +85°C (baseplate temperature) and meet MIL-STD 202 (Method 204D, condition D and Method 214, condition J) requirements for vibration. A multiple-output converter has a 2-transistor forward-converter module and a saturable-reactor regulator module for each output. The module meets DOD-STD-1399 and MIL-STD-704D and -461B, Part 4 CEO3; it features current limiting, undervoltage lockout, and inrushcurrent limiting. MTBF, under Navy-sheltered conditions and per MIL-HDBK-217D, is over 90,000 hours. Line and load regulation are 1.0%. Additional features include a 2-stage filter for low noise operation and optional status indicators. \$12.50 to \$20/W. Delivery, 10 weeks ARO.

ATC Power Systems Inc, 472 Amherst St, Nashua, NH 03063. Phone (603) 882-1366. TLX 756779.

Circle No 391



# NEW PRODUCTS: INTERNATIONAL

# **GATE ARRAYS**


Providing respective gate counts of 3289, 4290, and 6000, the M3000C2, M4000C2, and M6000C2 2-um double-metal-layer gate arrays feature a 2-input NAND gate propagation delay of 1.7 nsec and a toggle frequency of 100 MHz max. I/O pin counts are 90, 104, and 130, respectively; you can use the TTL- and CMOS-compatible I/O buffers as standard- or Schmitt-trigger inputs and as push-pull or drain-driver outputs. The manufacturer offers a library of more than 60 macrocells, including gates, flip-flops, and I/O buffers, and a library of 38 soft macrocells. The gate arrays are available in commercial, industrial, and military grades in ceramic or plastic DIPs as well as ceramic or plastic pin-grid-array and PLCC packages. PLCC gate arrays, approximately Fr fr 130 (M3000C2) to Fr fr 350 (M6000C2) (10,000).

Thomson Semiconductors, 43-45

Ave de l'Europe, 78140 Velizy, France. Phone (1) 39469719. TLX 240780.

Thomson-CSF Components Corp, Semiconductor Div, 301 Rte 17 N, Rutherford, NJ 07070. Phone (201) 438-2300.

Circle No 393



# GRAPHICS CARD

Providing interlaced 512×512-pixel resolution and 8-color display, the PG3200 color-graphics display module operates in a VME Bus or stand-

alone environment. Based on an EF9365 graphic-display processor and a 68121 intelligent peripheral controller, the module interfaces with raster-scan RGB monitors. Onboard memory accommodates two screen pages, and the dualported RAM is accessible via the VME Bus or the 68121. An RS-232C interface handles stand-alone operation. Onboard firmware is provided for point and vector plotting, variable-size ASCII-character generation, and the display of circles. A light pen is optional, and provision is made for image read-back and readmodify-write operations. \$1595.


Philips, Industrial & Electroacoustic Systems Div, Box 523, 5600 AM Eindhoven, The Netherlands. Phone (040) 757005. TLX 51573.

Circle No 394

Signetics Corp, 811 E Arques Ave, Sunnyvale, CA 94086. Phone (408) 739-7700.

Circle No 395

# Ultra High Speed Quad Analog Gate



The CAG-49 features a turn-on time of 13 nanoseconds (typical), 5 times faster than monolithic analog switches in the same packaging space, and low ON resistance, typically 35 ohms, which remains constant with voltage. The CAG-49 is cost effective, selling for half the price of four switches purchased independently. The space advantage cuts costs in handling, stock and inventory. It's ideal for high speed store and hold and analog gating applications. Send for our free catalog.

# TELEDYNE CRYSTALONICS

147 Sherman St. Cambridge, MA 02140 Tel. (617) 491-1670 • TWX: 710-320-1196 Send Today for Your FREE Edmund Scientific Catalog.

The new Edmund Scientific 100 page full color catalog features thousands of hard-to-find products used in science, industry, education, research and by hobbyists.

OPTICS

OPTIC



**CIRCLE NO 116** 

# **NEED ANALOG CONTROL** with changing light intensity? **USE CLAIREX** The resistance of photoconductors varies Photosensors are currently available

with light intensity. Thus, substituting a photoconductor for a resistor produces a circuit sensitive to light. Typical uses are:

- beam breakers
- · flame sensors
- · variable brightness controls
- ON-OFF switches

- · in a variety of sizes
- · in plastic, metal, or glass packages
- · with low or high resistance

For the optimum solution to each individual "light" problem, call 914-664-6602 or write Clairex,® 560 South Third Avenue, Mount Vernon, NY 10550.

# CLAIREX ELECTRONICS

**CIRCLE NO 122** 

# INTERNATIONAL


# DATACOMM IC

Combining a direct-memory-access (DMA) and a high-level data-link controller (HDLC) in one package. the MV6001EXP relieves CPU resources of the overhead involved in handling data links. To transmit or receive a block of data, the processor specifies the start address and length of the data block in memory; the device then handles the block transfer and formatting without further processor intervention. It operates at DMA rates as high as 8 MHz; HDLC frame lengths are programmable to 2k bytes. The device automatically appends a framecheck sequence. £20.46 (1000).

Plessey Semiconductors Ltd, Cheney Manor, Swindon, Wilts SN2 2QW, UK. Phone (0793) 36251. TLX 449637.

Circle No 396 Plessey Solid State, 3 Whatney Ave, Irvine, CA 92718. Phone (714) 951-5212.

Circle No 397



# 32-BIT CPU CARDS

The SYS68K/CPU-20/21 CPU modules for VME Bus systems run 16.7-MHz 68020 μPs with no-wait-state access via the FLME Bus (Force Local Memory Extension Bus) to 512k bytes of static RAM, which is housed on an accompanying SYS68K/SRAM-22 board. The only

# INTERNATIONAL

difference between the CPU-20 and the CPU-21 is that the latter contains a 68881 floating-point coprocessor: the CPU-20 has a socket for that coprocessor. Each CPU card features eight sockets for as much as 512k bytes of EPROM or 128k bytes of static RAM, one RS-232C and one RS-232C/RS-422 serial I/O port, interrupt control, and timer functions. The board's VME Bus interface is capable of 32-bit addressing and 32-bit data transfers; it includes a 7-level interrupt handler, single-level bus arbiter, and software-programmable bus-release functions. In addition to the FLME Bus, the board also has a VMX Bus interface. Firmware supplied with the board includes a debug monitor and line assembler/disassembler. The CPU-20 and CPU-21, including the 512k-byte RAM card, cost DM 16,590 and DM 17,565, respectively.

Force Computers GmbH, Daimierstrasse 9, 8012 Ottobrunn, Munich, West Germany. Phone (089) 6092033. TLX 524190.

Circle No 398
Force Computers Inc, 727 University Ave, Los Gatos, CA 95030.
Phone (408) 354-3410.

Circle No 399

# SEMICUSTOM SUPPLIES

System-Eureka semicustom power supplies are configured from standard chassis, line-input RFI filters, toroidal power transformers, and low-voltage linear or switch-mode secondary regulator modules. These modular components meet safety and emission requirements of agencies such as UL, CSA, and VDE. The RFI filter modules conform to VDE 0871B and FCC 20780B and may be fitted with listed line input components such as the line cord connector, input voltage selector, and fuse and power switches. The toroidal power transformers, listed under UL and VDE, are available with ratings of 80, 160 and 250 VA. Switch-mode secondary regulators are available with output

voltages of 5, 12, or 15V at 4A, or with an output voltage of 24V at 3A. Linear regulator modules are available for the same voltages, with either one or two isolated outputs. Switch-mode regulator modules feature current-limit adjustment, provision for switching frequency synchronization, and a power-fail status output. Both switch-mode and linear types have crowbar-overvoltage, thermal overload, and shortcircuit protection. Standard chassis assemblies accept two, three, or four regulator packages. The dimensions of a 3-regulator chassis are  $4.75 \times 12.5 \times 2$  in. A typical 3module, 4-output power supply, including the RFI filter and line connector, is priced at around \$1.50 per watt (OEM gtv).

Ulveco Power Products AB, Box 43, S-18400 Akersberga, Sweden. Phone (0764) 66060. TLX 13514.

Circle No 400



#### VIDEO PRINTER


The TP35 video printer with thermal print head produces graphic and text CRT images from composite video-input signals, separate video signals, or composite sync signals. It can print either positive or negative images on a 6-dot/mm print pitch and operates in either a high- or low-resolution mode. £1085.

Thandar Electronics Ltd, London Rd, St Ives, Huntingdon, Cambs PE17 4HJ, UK. Phone (0480) 64646. TLX 32250.

Circle No 401

# D-MOS FET TIP

# FET VIDEO SWITCH WITH DRIVER




(One channel of a four-channel CDG 309)

## More Than 60 db Off Isolation at 10 MHz

D-MOS's low capacitance makes it one of the best high frequency switches around. And when you put it on the same chip with CMOS you have an integrated circuit that can control up to 20 volts p-p...with a 5-volt logic swing.

# OFF isolation vs frequency



 $VCC = \pm 15V$ ; RL = 50 Ohms; Vgen = 4V p-p

The CDG family of integrated CMOS/D-MOS switches and-drivers offers you many choices—normally-on or -off types, "T" switch configurations, even high interswitch isolation packaging.

Want more information? Call or write for our video switch application note and catalog.



1971 N. Capitol Ave. San Jose, CA 95132 (408) 942-9100

# **NEW PRODUCTS: SOFTWARE**

# 80286 ASSEMBLER

Macro Assembler 4.0 runs under MS-DOS on computers that use the 80186, 80286, 80287, 8086, 8087, and 8088 instruction sets. The assembler comes with an interactive source-level symbolic debugger, a linker, a program-maintenance utility, a library manager, a cross-reference utility, and EXE file-packing

and header utilities. The 4.0 version allows you to assemble larger source files with more symbols and more macrotext than previous versions; additional assembly switches are also included. Screen swapping permits switching between the debugging screen and the application output. The company claims the assembler provides 100% source-

and object-code compatibility with earlier versions of its and IBM's macroassemblers. The package requires 128k bytes of RAM, MS-DOS 2.0 or higher, and one floppy-disk drive, although two drives are recommended. \$150; upgrade for registered owners, \$75.

Microsoft Corp, Box 97200, Bellevue, WA 98009. Phone (800) 426-9400; in WA, (206) 828-8080. TLX 328945.

Circle No 402



VADS, a parallel implementation of the Ada development system, runs on Sequent's (Beaverton, OR) Balance 8000 parallel computer. According to the company, the multistream nature of Ada development and execution allows the package to use the tightly coupled, parallel architecture of the Balance system for reduced development time and higher run-time performance. The package provides an Ada compiler and a set of software-development tools, which includes an interactive screen-oriented debugger, librarymanagement tools, and the run-time system. Prices start at \$15,000 for a 16-user system.

Verdix Corp, 14130-A Sullyfield Circle, Chantilly, VA 22021. Phone (703) 378-7600.

Circle No 403

# VOICE RECOGNITION

With VoiceCommand and an IBM PC, PC/XT, or PC/AT, you can operate such programs as Lotus 1-2-3 and Wordstar by voice; the personal computer accepts voice commands as it would commands entered via a keyboard. Users define such common commands as "create graph," "initialize program," and "save data," which are stored for use with other software packages. The system has space for a 500-word vocabulary, but you can overlay multiple 500-word segments for a total of 8000 words. A voice-defined menu option can replace standard soft-



- Eliminate ground-loop problems (hum, cross-talk, voltage differentials, etc.) on video and other wideband data lines.
- Insure outstanding signal transmission with over 120 dB attenuation of interference at power line frequencies.





For the ultra-wide bandwidth and low, flat insertion loss needed by broadcast or remote TV lines. For security, CCTV or Industrial Process Control systems. For high-speed Data Lines or Medical Imaging Equipment. Whatever your needs, there's a North Hills Isolation Transformer designed to meet them. Engineered for unmatched reliability. Standard insulated BNC connectors for easy installation. Backed by a 3-year warranty — it's the widest selection of Wideband Isolation Transformers available anywhere. And it's available now! Right off the shelf!

For details, dial: 516-671-5700. Or write for our new catalog.



1 Alexander Place, Glen Cove, NY 11542-3796 (516) 671-5700 Telex: 46-6886

ware menus; you can link menus to form a complete voice system. The package includes the software, a microphone, a plug-in board, and an instruction manual. \$399.


Interpath Corp, 3333 Bowers Ave, Suite 253, Santa Clara, CA 95054, Phone (408) 988-3832.

Circle No 404

routines into your applications. Without the host-language interface, \$995; host-language interface, \$495.

Unify Corp, 4000 Kruse Way Pl, Lake Oswego, OR 97034. Phone (503) 635-6265. TLX 469220.

Circle No 406



# **IMAGE PROCESSING**

PICDMS, a database-management system for image processing and model building, operates in two or more dimensions on digitized photographs, maps, and drawings. It can detect objects or edges in pictures, recognize and classify patterns, determine minimum and maximum values, calculate distances, and create histograms and statistical analyses. The software runs on Prime minicomputers, Apple II, and the IBM PC and compatibles. A 1-time license fee for microcomputer version, \$5000; minicomputer version, \$8000.

MIB Chock, 1048 24th St, Santa Monica, CA 90403. Phone (213) 828-4788.

Circle No 405

## DATABASE SYSTEM

This company's relational database-management system is available in an MS-DOS version. The package provides a comprehensive set of development tools, including SQL and fourth-generation report writer. The package is upward compatible with Unix. A host-language interface to the C language allows you to integrate existing or custom sub-

# MS-DOS LINK

The L/F-Link interface program allows the single-user MS-DOS operating system to function under the supervision of the multiuser TurboDOS operating system. The program and the company's S-100+Bus permit direct user-to-file-server communications and virtually eliminate bus contention. TurboDOS is a multiprocessor operating system that can coordinate a network of 80186 processors running at speeds as high as 8 MHz. \$495.

L/F Technologies, 2800 Lockheed Way, Carson City, NV 89701. Phone (702) 883-7611. TWX 910-395-6051.

Circle No 407


## INVENTORY SYSTEM

The Stock-Master 4.0 inventorymanagement system runs on the IBM PC, PC/XT, PC/AT, and compatible computers. The 143-program system is organized into eight subsystems that provide master-file maintenance, 12 types of transaction entry and editing, stock status reporting, transaction history detail analysis, trend analysis, purchaseorder tracking, quality-control reporting, and system-maintenance utilities. The system has an 18-character part number with two 30-character description fields. It also maintains a record of inventory balances. Object-code license fee, \$995.

Applied Micro Business Systems Inc, 177-F Riverside Ave, Newport Beach, CA 92663. Phone (714) 759-0582.

Circle No 408






# Guide features power-line protection devices

How To Correct Power Line Disturbances is a 16-pg booklet on devices that you can use to protect power lines. It contains descriptions of typical isolation transformers, line voltage regulators, line conditioners, motor-generator sets, and uninterruptible power supplies. A guide to determining the economical justification of protective devices is included.

Dranetz Technologies Inc, Box 4019, Edison, NJ 08818.

Circle No 409



# Bus products described

Containing short descriptions of more than 60 STD Bus and VME Bus  $\mu C$  boards, this industrial-control products catalog also covers support software, firmware, and

hardware. The products, based on the Z80, 8085, 68000, and 68008 µPs, include single-board computers, CPUs, memory devices, and I/O and communications devices. Also covered is the manufacturer's family of EPROM emulator/programmers. You can use the products in processand industrial-control applications, ATE, and data-acquisition systems.

Micro-Link Corp, 14602 N US Hwy 31, Carmel, IN 46032.

Circle No 410



# DMOS design-contest winners presented

Featuring the winning entries from a double-diffused MOS (DMOS) design contest conducted by the manufacturer, this 60-pg booklet includes a variety of p-channel DMOS products. Also included are DMOS application articles and information on data-sheet interpretation. The publication also contains a cross-reference and product-selection guide.

Supertex Inc, Customer Service Dept, Box 3607, Sunnyvale, CA 94088.

Circle No 411

# Catalog helps you choose circuit-board indicator

An 8-pg LED circuit-board-indicator catalog lists the company's line of LEDs, which require no lead bending or trimming. The short-



form catalog includes dimensional drawings as well as pertinent specifications so you can choose the proper LED circuit-board indicator. The catalog also lists the company's representatives.

Dialight Corp, 203 Harrison Pl, Brooklyn, NY 11237.

Circle No 412



# Electrical-discharge machines detailed

A series of wire-cut electrical discharge machines (EDM) is the subject of this 4-color, 24-pg brochure. The booklet describes how, via computer control, you can program the Agiecut machine to operate for as long as 60 hours to produce an extrusion die, a progressive die, a copper electrode, six brass template cams, and six carbide punches. The document also provides details of the machine—eg, its cutting speed and contouring capabilities.

Agietron Corp, Box 469, Addison, IL 60101.

Circle No 413

# EDN PRODUCT MART

This advertising is for new and current products.

Please circle Reader Service number for additional information from manufacturers.

#### MODEL IQ-160 FROM DIGITAL MEDIA POWERFUL AND INTELLIGENT, FIRST TRULY PORTABLE UNIVERSAL PROGRAMMER




- Programs PALPLE, IFL. PROM, EPROM, EEPROM including MOS, CMOS, NMOS, ECL, BI-POLAR
- No personality modules

  Emulates 32K x 8 EPROM/PROM
- Software updatfible for new devices RS-232 with automatic Baudrate adjust between 300 and 19,200 Baud
- Supports JEDEC and Intex Hex formats
   Built-in uttra fast logic interpreter DMLI
- Built-in data manipulation commands
- Fast/intelligent algorithms for EPROMs
   Can drive automatic handlers and
   GA-160 Gang Adapter

- Stand-alone operation for
- Lightweight (2.5 lb.) and
- 32 character LCD display
   Part numbers and operating modes selected from menus
- Tested by MMI, Ti and National Semiconductor

tal Media, Inc. • 3178 Gibrattar Avenue • Costa Mesa • CA 92626 • USA (714) 751-1373

**CIRCLE NO 138** 



#### FREE DEMO DISK

SCHEMA is a complete, integrated schematic drawing software package for IBM Personal Computers. Use SCHEMA with your PC to draw schematics and automatically generate design documentation such as Wire and Net Lists, Bills of Materials, Design Rule Checks, etc. SCHEMA is \$495 and supports most common PC hardware configurations. Call or write today for a free demo disk and brochure.

## OMATION INC.

1701 N. Greenville Ave., Suite 809 Richardson, TX 75081 (214) 231-5167

CIRCLE NO 139



# Sprague-Goodman. The world's largest selection of 5mm (or smaller) trimmer capacitors.

The most wanted features found in various models include high stability, low cost, very small size, and very high Q at high frequency.

### Sprague-Goodman Electronics, Inc.



(An affiliate of the Sprague Electric Company) 134 Fulton Ave., Garden City Park, NY 11040 516-746-1385 • TLX: 14-4533

**CIRCLE NO 140** 

# **MULTIBUS:** Your Time Has Come!

The mSBX-241™ Multimodule is a robust, precision Real-Time Clock/Calendar in SBX format with onboard battery backup.

#### General Features:

- For high performance systems:
  no wait states or software overhead
  Attaches to all SBX and BLX compatible Multibus boards
  Programmable alarm clock and periodic interrupts
- 12 or 24 hour time modes, in both BCD and binary format Internal 100 year calendar with leap year compensation
- Selectable automatic Daylight Savings compensation Contains fifty bytes of general purpose non-volatile RAM
- RMX-86/286 drivers supplied on diskette


#### For more information contact:

#### Medinova Corporation

Intelligent Systems Group 244 West Court, Palatine, Illinois 60067 Telephone (312) 934-4700

Multibus, Multimodule TM Intel Corp.

**CIRCLE NO 141** 



At last, a complete compendium of LVDT working parameters. Call us now for fast solutions to your OEM requirements.

1-800-323-7115, ext. 302



(In PA, call 1-800-323-7114)

Robinson-Halpern

CIRCLE NO 142



#### ANALOG AND DIGITAL INPUT/OUTPUT MODULES

Analog and digital connections for any computer with an RS-232 or IEEE-488 interface; built-in timer and buffer allow data acquisition while your computer is busy with other tasks. \$495.00 each BUSSter A64 - 64 digital in: B64 - 64 out: C64 -32 in/32 out: D16 - 16 analog in: others

Connecticut microComputer, Inc.

PO Box 186 Brookfield, CT 06804 TEL: 1-800-4-CMC-USA TWX: 710456 0052



#### EE/EPROM PROGRAMMER...with Eraser...the "BEST" for \$1295. **DIGELEC Model 824**

- RAM 512K, upgradeable to 2048K
- Programs 2716 to 27512, upgradeable
- MOS, CMOS, 40-pin micro P's, no adapters
- Programs virtually all mfg's, 220 + devices
- Time-saving quick-pulse & Int. algorithms
- Complete stand-alone editing, 16-char. display
- RS-232 Remote control, translation formats ■ Optional IBM-PC/AT menu-driven S.W.
  - \*SPECIAL INTRODUCTORY PRICE

PHONE 201-493-2420

DIGELEC, Inc., 1602 Lawrence, Ocean, NJ 07712

■ Also mfg of LOGIC, GANG, OEM, PC Board. & UNIVERSAL PROGRAMMERS **CIRCLE NO 144** 



FAST TRACK RESISTOR NETWORKS.

Sprague low-cost, low-profile Type 210C Econoline® Thick-Film Resistor Networks are excellent for computer, automotive, telecommunication applications. Available off-the-shelf in 6-pin, 8-pin, and 10-pin conformally-coated SIPs. Standard resistance values from 22 ohms to 1 Megohm. Write for Short-Form Catalog RN-210 to:

Sprague Electric Co.

P.O. Box 9102, 41 Hampden Road Mansfield, MA 02048-9102 **CIRCLE NO 145** 



Covering the full spectrum of your telecommunications needs


- Call Progress Detectors and Generator CMOS detectors for telephone system tones (dial tone, ringback, busy, special information); CMOS generator for standard call
- DTMF Receivers High-quality receivers for all applications.
- MF Receivers and Generator CCITT R1/R2 receivers; CMOS generator.
- DC Signalling Products Line sense relay; Dial pulse counter and hook status monitor; Binary input pulse

# TELTONE

Teltone Corporation 10801 - 120th Ave. N.E., Kirkland, WA 98033-9974 Phone (206) 827-9626 TWX 910 449-2862

#### **CIRCLE NO 146**

# 68020 Big Performance Boost!



• 500% plus performance. • Plugs into any existing 68000/68010 socket. • On-board 68881 floating point math coprocessor chip. . Runs all 68000/68010 programs. • Great for prototyping the 68020 CPU & 68881 floating point math coprocessor. • 222% Performance improvement over the 68000 at 12.5 mhz; the EDN linked list insertion Benchmark showed at 248%


**Computer System** Associates, Inc.

7564 Trade St., San Diego, CA 92121/(619) 566-3911

**CIRCLE NO 148** 



HIGH PERFORMANCE Z-80 SINGLE BOARD COM-PUTERS. Available with either Z-80A or Z-80B CPU 64-256K RAM, 2-64K ROM or EPROM, 2 or 4 RS-232 serial ports, high speed bi-directional port or I/O expansion bus. All models have 51/4 " & 8" disk controller and Centronics parallel printer port. SCSI and RS-422 ports are also available. Other products include private label systems, STD bus and IBM PC compatible boards. DAVIDGE CORP., P.O. Box 1869, Buellton, CA 93427 (805) 688-9598.




MC68020 SINGLE-BOARD COMPUTER

The GMX Micro-20 SBC provides the basis for a powerful, compact 32-bit computing system; in a 5.25" form-factor package: a 12.5MHz MC68020, 2MB of RAM, 4 serial ports, an 8-bit parallel port, floppy disk controller, SASI interface, time-of-day clock w/battery, and an optional MC68881 floatingpoint coprocessor. It includes Motorola's 020Bug monitor/debugger and hardware diagnostics in PROM. \$2200.00 (qty 25). Also available: A PROMable real-time, multi-user/multi-tasking operating system, and complete systems with cabinet, power supply and floppy/hard disk drives.

1337 WEST 37th PLACE CHICAGO, ILLINOIS 60609 (312)927-5510 TWX 910-221-4055

CIRCLE NO 149

#### **CIRCLE NO 147**



#### 68000 Multibus Board

High performance 10 MHz 68000 processor based Multibus single board computer fea-tures four DMA channels, parallel interface, timers, real time clock, dual synchronous or asynchronous serial channels, up to 1 mega-byte RAM, 256K EPROM or 128K EPROM and 64K battery backed up RAM, dual expansion connectors, on-board interface to Priam hard disk controllers.

**AMTELCO** 

4800 Curtin Drive, McFarland, WI 53558 (608) 838-4194 (800) 356-9148

**CIRCLE NO 150** 



smARTWORK® Circuit-Board-Artwork Software, For only \$895, smARTWORK® lets the design engineer create and revise printed-circuit-board artwork on the IBM Personal Computer. Forget the tedium of taping it yourself or waiting for a technician, draftsman, or the CAD department to get to your projects. With smARTWORK® you keep complete control over your circuit-board artwork from start to finish. Call or write to Wintek Corporation. 1801 South Street, Lafayette, IN 47904-2993. (317) 742-8428, (800) 742-6809

**CIRCLE NO 151** 



#### 8048 IN-CIRCUIT **EMULATOR**


E232-48 emulates Intel compatible 8048, 8049, 8050 microcomputers and their ROMless amd CMOS versions. It features:

- Real time emulation up to 11 Mhz.
   Hardware Breakpoints.
- Rs-232 interface to host sysytem.
   In-line Assembler and Disassembler.
- Complete debugging facilities.
  Software Drivers for IBM PC, CP/M-80, and CPM/86 included at no extra cost

E232-48..... ...\$1795.00 Cross Assembler (8048 & others) From

SIGNUM SYSTEMS 1820 14th Street, Suite 203

SANTA MONICA, CA 90404 (213) 450-6096



# INTRODUCING THE FIRST HD64180 SINGLE BOARD STD BUS COMPUTER

WinSystems offers the powerful Hitachi CMOS 64180 enhanced processor compatible with 8080/Z80 software. Features include 512Kb memory addressing, 2 DMA channels, 4 RS232/RS422 serial I/O, 2 16-bit timers, hardware multiply, & watchdog timer on the LPM-SBC5. Supports RAM, EPROM, & EEPROM. Available in NMOS/TTL or CMOS on the STD Bus. WinSystems Inc., P.O. Box 121361, Arlington, TX 76012. 817/274-7553

**CIRCLE NO 153** 

# A high quality video camera you can plug in and forget!



Here is a new one-piece camera designed for long-term unattended operation in machine vision, instrumentation and medical systems. Called the "Visioneer," this new camera is extremely temperature stable. When required, maintenance couldn't be simpler. All boards are juliq-in modules, and all board level maintenance can be done with just a screwdriver. Bandwidths are available up to 25 MHz, with line rates from 525 to 1023. Camera includes external drive and internal sync generator for automatic backup. If you have special requirements, ask us to customize this camera. It's designed for that, too. From the company with 20 years experience in designing video cameras of the highest quality.

#### SIERRA SCIENTIFIC

1173 Borregas Avenue, Sunnyvale, CA 94089 Telephone: (408) 745-1500 Telex: 172028 SIERRA SUVL

CIRCLE NO 154



# GO WITH THE BEST... LOW COST 8-BIT SUPPORT SYSTEM FROM TEK.

TekMate provides many standard features that you might not expect of a low-cost 8-bit support system. For less than \$10,000 TekMate delivers real time transparent emulation allowing you to analyze microprocessor activity without stopping the prototype. Call 1-800-342-5548 or write: Tektronix, SDP Division, P.O. Box 14752, Portland, Oregon 97214.

**CIRCLE NO 155** 

# OC8000



# EXPANDS PC PERFORMANCE AT A FRACTION OF NETWORKING COST

- Adds four to eight serial communication ports to IBM PC, XT, AT or compatibles.
- Standard RS-232 or optional RS-422 ports for increased transmission speed and distance.
- Supported by Xenix, Multi-Link, RTCS, QNX, and other multi-user, multi-tasking operating systems

Need more information? Call (216) 951-5922, or write STAR GATE TECHNOLOGIES, Suite 109, 33800 Curtis Blvd., Eastlake, OH 44094

STAR GATE

**CIRCLE NO 156** 



# RS-232 TO IEEE-488 CONTROLLER WITH TRANSPARENT OPERATION

Control hundreds of data acquisition, control, and test equipment systems from any RS-232 type device.

Model RG4 allows control of one IEEE-488 device

Model RGA


which must be set to device 4 \$495.00 allows control up to 15 individually addressed IEEE-488 devices from one RS-232 port \$695.00

Connecticut microComputer, Inc.

PO Box 186 Brookfield, CT 06804

TEL: 1-800-4-CMC-USA TWX: 710456 0052

**CIRCLE NO 157** 



### MULTIBUS FAILURE DETECTION/RECOVERY

Automatically resets a Multibus system after detecting a system failure from such causes as RFI, EMI, power surge, power brownout, software failure, etc. Also includes:

- · Alarm output for non-recoverable failures
- Real-time interrupt at 6 user-selectable intervals
- 24 user-definable LED's and switches

MORROW TECHNOLOGIES CORPORATION 3026 Owen Drive, Antioch, TN 37013 615-793-3555

**CIRCLE NO 158** 

# FREE

High-Temperature Glass-Encapsulated YSI THERMISTOR

#### CENT L

for testing in your OEM design.

YSI	Ohms	Tolerance	Max.
P/N	@ 25°C	0 to 70°C	Temp.
45004	2252	± 0.2°C	200°C
45008	30K	± 0.2°C	250°C

With YSI glass-encapsulated thermistors you get superior long-term stability at elevated temperatures, even where humidity may exceed 95%. For your free thermistor, please write on company letterhead with a description of your OEM application, or phone 513-767-7241.


# from Yellow Springs

Industrial Division Yellow Springs Instrument Co., Inc. Yellow Springs, Ohio 45387 USA

**CIRCLE NO 159** 



CIRCLE NO 160





#### COMPATIBLE COMPUTER

When you buy one of the following products at very affordable introductory prices.

#### UNIVERSAL PROGRAMMER

Programs EPROMS & PAL expandable to BI-POLAR and single chip micro

#### LOGIC ANALYZER

\$1,795

\$1,595

50 MHZ, 8 channel expandable to 32 channel \$1,295

# GANG PROGRAMMER

Programs 8 EPROMS with same data or different data.


#### PROTOCOL ANALYZER

\$1,595

Monitor and Simulator

ABOVE PRODUCTS AVAILABLE WITHOUT PC. Advanced Microcomputer

Systems, Inc. 2780 S.W. 14th St. mpano Bch., FL 33069 1-800-9PC-FREE



CIRCLE NO 164

# THE LITTLE BIG BOARD

The most productive development environment imaginable on a single board computer


- Uses the highly integrated 80188 with internal 8 MHz
- High level languages Basic or Forth in ROM
- Printer and modem ports
- CRT terminal port up to 19.2 K baud
- 64 K to 128 K of battery backed sRAM available
- \$299-450 ea (\$199/1000)
- Runs MS-DOS, PC-DOS, and CP/M-86 EPROM programmer
- onboard Disk controller, WD1770 Low power, < 1 Amp,</li> 5VDC only

  Battery backed time of day
- Board dimensions: 8" x 8"
- Supports 8 interrupts

Vesta Technology, Inc., 7100 W. 44th. Ave. Suite 101, Wheatridge, CO 80033 (303) 422-8088.

**CIRCLE NO 167** 


### CIRCLE NO 162



#### **ENGINEERING SIMULATION SOFTWARE**

Micro-CSMP simulates systems including: • Control and Servo systems . Robotics . High Order Filters • Chemical Processes • Stress & Strain. A full implementation of IBM's S/360 CSMP, Micro-CSMP produces graphical results in minutes, typically requiring 10-20 lines of input. LSAP analyzes linear systems producing Bode, Nyquist, and Transient Response plots, and Root-Locus diagrams. Micro-CSMP is \$850, LSAP is \$465 for PC-DOS or MS-DOS systems. California Scientific Software, 25642 Hazelnut, El Toro, CA 92630 (714)581-7654.

**CIRCLE NO 165** 



**CIRCLE NO 163** 

#### **NEW FOR SURFACE-MOUNT PC BOARDS**

Rogers off-board SURF/BUS bars carry up to 2.5 amps, save board space, let you use 2-layer boards by running signal traces under bus bars to interconnect components. Get capacitance, low impedance, reduced inductance, use less decoupling capacitors. SURF/BUS bars mount on solder pads, connect component power and ground leads. **Rogers Corp.**, 5750 E. McKellips Rd., Mesa, AZ 85205, 602/830-3370.

**CIRCLE NO 166** 

# ITT Cross-Flow **Blowers** are quieter than lans.

Less air turbulence means less noise, fewer hot spots, and – in many cases - fewer cubic feet of air needed to do a given cooling job.

ITT Cross-Flow Blowers are lower in profile, too, measuring only 2.3 inches or 60 mm high. Blowers deliver 20 to 600 cfm.

ITT Schadow Inc., a subsidiary of ITT Corpora-tion, 8081 Wallace Road, Eden Prairie, MN 55344. (612) 934-4400. For an ITT Schadow Catalog, Circle No. 105

For Sales Engineer Call/Samples, Circle No. 106

# 68000 Computer

Single board computers based on the Motorola 68000 series of micro-processors with up to 1M RAM, 32K ROM, 4 serial RS-232 ports and 2 parallel ports (expandable to 22 ports total), programmable timer module, floppy drive controller, and SASI (SCSI) interface for Winchester addition. All computers include real time multi-user/multi-tasking "Unix™ like" OS9 operating system, BASIC 09 with run time package, spread sheet, screen editor, mail and spelling programs.

Prices start at \$995.00

Write or phone

# **AAA Chicago Computer Center**

120 Chestnut Lane - Wheeling, IL 60090

(312) 459-0450

Unix is a trademark of Bell Telephone Labs. O59 and BASIC 09 are trademarks of Microware Systems Corp.

**CIRCLE NO 168** 

# **High Resolution CAD** on IBM PC

- 1024 x 768 or 640 x 400
- Color Graphics Graphics Editor Electronic Design
- PCB & IC Design
- Schematic Capture
- Interfaces to SPICE, SCICARDS, GDS II. Gerber
- 9-State Logic Simulator for PC and VAX



Chancellor Computer Corporation

1101 San Antonio Road Mountain View, CA 94043 800/222-2660

# PROFESSIONAL ISSUES

# Word-processing software, not a CAE package, is an engineer's most valued assistant


Deborah Asbrand, Staff Editor

A study of how engineers at one electronics company put personal computers and software programs to use found that, although engineers were using computer-aided engineering programs for schematic capture, logic simulation, circuittiming analysis, and functional and behavioral simulation, the programs they used most often were word processing and text editing.

As part of an effort to better assess engineers' computer needs, Texas Instruments launched a survey in 1983, asking its engineers how they spent their time, which tasks they most often performed on computers, and what kind of workstation and software packages they would find useful in their work. Topping the list of useful software programs—ahead of advanced engineering tasks such as schematic capture and logic simulation—was word processing.

A second survey, conducted in 1984, also asked engineers to rank software packages according to how useful they found them in their work. Word-processing and text-editing packages were ranked most useful by the largest number of respondents: 24%. Schematic-capture packages were listed as most important by 11.1% of the respondents; spreadsheets, by 7.2%; logic simulation, by 7%; foil generation, by 5.2%; and circuit-timing analysis, by 5%. Other functions rated important by fewer than 5% of the respondents were project scheduling, functional and behavioral simulation, timing verification, and test generation.

Three hundred engineers at the company's Houston, Austin, and Temple, TX, facilities participated



in the two surveys. Forty-four percent of the participants were electrical engineers, most of whom worked in digital, analog, and system design. The bulk of the other participants were mechanical engineers, IC designers, software engineers, and project managers.

Engineers' perceptions of how computers could assist them in their work changed in the year that elapsed between the first and second surveys. Spreadsheets, for example, rose to among the top five packages in the second study, after ranking seventh just one year earlier. Similarly, a higher percentage of engineers rated schematic-capture

programs important as compared with respondents in the first survey.


The surveys were actually part of a larger effort by TI's Data Systems Group to develop a strategy for making CAE techniques, then used by a few individuals, available to the group's entire engineering staff. Dick Shaw, manager for engineering services at Texas Instruments' Austin, TX, facility and project manager for the study, says that "a patchwork of stand-alone developments" was occurring throughout the division. One of the project's goals was "to bridge these islands of automation," according to the sur-



# THE FIRST NAME IN MAGNETIC MATERIALS THE LAST WORD IN SERVICE

Basically, PERMAG'S got the largest. most comprehensive inventory of magnetic materials anywhere in the world. And a support staff of salesmen and customer service representatives going into the field and taking orders all across the U.S.A. But if we stopped at the basics we never would've become the best known name in magnetic materials. Our salesmen aren't just





in a rigorous program at our on-going training facility in Chicago. And our customer service representatives aren't just telephone. voices: they're experienced consultants

who've helped many customers resolve tough fabrication and application problems. At PERMAG, we make sure you're not just supplied, but satisfied.

PERMAG	P	E	R	N	1	A	G
	-						

For one of our new catalogs or to see a salesman, mail the coupon. For faster assistance call toll free

1-800-346-6600 EXT. B-185

PERMAG CORP.  Have salesman call	400 Karin Lane, Hicksville, NY 11801  ☐ Please send me your latest Catalog		
NAME			
COMPANY			
ADDRESS			
CITY	STATE	ZIP	
PHONE			

#### CIRCLE NO 127

# **ISSUES**

vey report, and integrate the use of CAE.

Before the survey was conducted, groups of engineers met first to identify ways in which they could improve their performance and then to determine how CAE programs might help engineers meet those performance goals. The groups identified three top areas for potential improvement: cutting product development time, improving product quality, and enhancing their own productivity.

Shaw says that the results of the surveys at first surprised him and his colleagues. "But as we checked other surveys, they began to make more sense," he recalls. Engineers' tasks involve writing hardware specifications, memos, and reports, Shaw says—all functions that word processing facilitates.

The survey results prove to Shaw that the personal computer is an adequate tool for many engineering applications. "You don't need a big computer to do word processing, foil generation, and schematic capture," he says. A personal computer can handle most of the applications that the engineers listed as most important to them in their work, Shaw claims. As a result, rather than purchase high-end computers, the company makes its personal computer available to engineers. Almost all of the engineers at Texas Instruments are now using personal computers. according to Shaw.

An evaluation process of engineering tools, begun during the study project, has continued at the three TI facilities. After the project's final report was completed last June, approximately 30 participating engineers split up into smaller teams to continue evaluating some of the hardware and software they use.

Section Interest Quotient (Circle One) High 518 Medium 519 Low 520

# **BUSINESS/CORPORATE STAFF**

F Warren Dickson Vice President/Publisher Newton, MA 02158 (617) 964-3030 Telex 940573 Diann Siegel, Assistant

Peter D Coley National Sales Manager Newton, MA 02158 (617) 964-3030 Stacey Vorias, Assistant

NEW ENGLAND Bob Sommer, Regional Manager 275 Washington St Newton, MA 02158 (617) 964-3030

STAMFORD 06904 George Isbell, Regional Manager 8 Stamford Forum, Box 10277 (203) 328-2580

NEW YORK CITY 10016 Daniel J Rowland, Regional Manager Chris Platt, Regional Manager 475 Park Avenue South (212) 576-8014 (212) 576-8017

PHILADELPHIA AREA Steve Farkas, Regional Manager 999 Old Eagle School Rd Wayne, PA 19087 (215) 293-1212

CHICAGO AREA Clayton Ryder, Regional Manager Randolph D King, Regional Manager Cahners Plaza 1350 E Touhy Ave, Box 5080 Des Plaines, IL 60018 (312) 635-8800

DENVER 80206 John Huff, Regional Manager Joseph A Vitiello, Regional Manager 270 St Paul St (303) 388-4511

DALLAS 75234 Don Ward, Regional Manager 13740 Midway, Suite 515 (214) 980-0318

SAN JOSE 95128
Walt Patstone, Regional Manager
Bill Klanke, Regional Manager
Philip J Branon, Regional Manager
Mark Holdreith, Regional Manager
3031 Tisch Way, Suite 100
(408) 243-8838

LOS ANGELES 90064 Charles J Stillman, Jr Regional Manager 12233 W Olympic Blvd (213) 826-5818 ORANGE COUNTY/

SAN DIEGO 92715 Ed Schrader, Regional Manager Jim McErlean, Regional Manager 2041 Business Center Dr, Suite 109 Irvine, CA (714) 851-9422

PORTLAND, OREGON 97221 Pat Dakin, Regional Manager Walt Patstone, Regional Manager 1750 SW Skyline Blvd, Box 6 (503) 297-3382

UNITED KINGDOM, THE NETHERLANDS Jan Dawson, Regional Manager 39A Bowling Green Lane London EC/1R/OBJ UK 1-278-8981 Telex: 261653

BELGIUM/FRANCE
Robert Broekman
American Publishers Representatives
4 Rue Robert de Flers
75015 Paris, France
33-1-46099595
Telex: 270560

GERMANY/SWITZERLAND Wolfgang Richter Sudring 53 7240 Horb/Neckar West Germany 49-7451-7828 AUSTRIA Igal Elan Elan Marketing Group Neutor g 2, Box 84 1013 Vienna, Austria 43222-663012, 638461

SCANDINAVIA Igal Elan Elan Marketing Group Humlegardsgatan Nr 5 11446 Stockholm, Sweden 46 8 677243, 676243

SOUTHERN EUROPE Igal Elan Elan Marketing Group 13 Haifa St, Box 33439 Tel-Aviv, Israel Tel: 25 29 67

FAR EAST Ed Schrader, Director of Sales 2041 Business Center Dr, Suite 109 Irvine, CA 92715 (714) 851-9422; Telex: 940573 TOKYO 106

TOKYO 106 Kaoru Hara Trade Media Japan Inc Suite 412, Azabu Heights 1-5-10 Roppongi, Minato-ku Tokyo 106 Tel: (03) 587-0581 Telex: J28208 MEDIAHS

TAIWAN Owen Wang, Gen Mgr Ace Marketing Inc Box 26-578 Taipei, Taiwan Republic of China 86-2-703-4272 Telex: (785) 14142

PRODUCT MART Joanne Dorian, Manager 475 Park Avenue South New York, NY 10016 (212) 576-8015

CAREER OPPORTUNITIES/ CAREER NEWS Roberta Renard National Sales Manager 475 Park Avenue South New York, NY 10016 (212) 576-8048

Jennifer Purinton Eastern Sales Manager 475 Park Avenue South New York, NY 10016 (212) 576-8049

Dan Brink Western Sales Manager 2041 Business Center Dr, Suite 109 Irvine, CA 92715 (714) 851-9422

Maria Cubas Production Assistant (212) 576-8045


Cahners Magazine Division
William Platt, President
Terry McDermott, Executive Vice President
Tom Dellamaria, VP/Production & Manufacturing

Circulation
Denver, CO: (303) 388-4511
Sherri Gronli, Group Manager
Eric Schmierer, Manager

Reprints of EDN articles are available on a custom printing basis at reasonable prices in quantities of 500 or more. For an exact quote, contact Art Lehmann, Cahners Reprint Service, Cahners Plaza, 1350 E Touhy Ave, Box 5080, Des Plaines, IL 60018. Phone (312) 635-8800.

# The PC Bus:

# Cost-Effective, Board-Level Solution To System Integration



Get your dedicated system to market *months* sooner with the PC Bus. Full board-level implementation by I-Bus lets you plug together system components from hundreds of PC Bus board manufacturers, and directly execute software developed on and for the IBM® PC.

I-Bus has board-level CPU's with 8088 or 80188 processors, full disk or diskless operation and up to 160K of EPROM, 256K of RAM on board. We have the most complete line of system packaging for the PC Bus, too.

Start cutting your schedule today—give us a call today at (800) 382-4229. In California, call (619) 569-0646



I-BUS SYSTEMS

9235 Chesapeake Drive San Diego, CA 92123

# CAREER OPPORTUNITIES

# 1986 Editorial Calendar and Planning Guide

Issue Date	Recruitment Deadline	<b>EDN</b> Editorial Emphasis	EDN CareerNews
Mar. 20	Feb.21	Test & Measurement; Analog ICs; Computer Peripherals; Support Chip Directory	Mailing: 3/25
Apr. 3	Mar. 7	Communications Special Issue; Communications ICs; CAE; Buses; April Fools Supplement	Closing: 4/10
Apr. 17	Mar. 21	Power Supplies; Development Software; Memory Technology; Computer Graphics Devices (CAE-related*); Electro '86 Product Preview	Mailing: 4/22
May 1	Apr. 4	Electro '86 Show Issue; Sensors/Transducers; ICs; Test & Measurement; Display Technology	Closing: 5/8
May 15	Apr. 18	Programmable Logic Devices; CAE; Communications Components; Optoelectronics	Mailing: 5/20
May 29	May 2	Analog Technology Special Issue; Data Converters; Analog ICs	
June 12	May 16	Digital Technology Special Issue; Personal Computer Boards; Development Systems (CAE-related*); Computer ICs; NCC Show Preview	Closing: 6/19 Mailing: 6/30

# Call today for information.

East Coast Jennifer Purinton (212) 576-8049 West Coast Dan Brink (714) 851-9422 National Roberta Renard (212) 576-8048

# Forget Everything You Dislike About A Job Search...

You've thought about changing jobs, you are concerned about getting your resume to the best companies, and the right people.

You've probably answered more than your share of newspaper ads, made endless phone calls and mailed countless resumes.

You want to avoid high pressure employment agency tactics and you're worried about confidentiality.

# SoftView has changed all that . . .

SoftView is the perfect opportunity for career minded Software Engineering Professionals to get the truest picture of the local and national Software job markets.

SoftView gives you access to over 50,000 professional Software job openings confidentially without obligation. The beauty of SoftView is that it works.

Register with SoftView. When a position that best suits your background and experience is open in your area, or in an area which you are interested in we will tell you all about it.

If you are interested in the particular position and company we will arrange an introduction and subsequent interview for you. It's all up to you from there. Its all done professionally without pressure and with the utmost in confidentiality.

# Here's A Representative Sample of **Current Position Requirements.**

Software Engineers to \$45,000 3-5 yrs experience Unix "C", Aegis Communications Applications, Graphics, CAD/CAM

Documentation Manager to \$35,000 5 plus yrs experience Technical Writing/Documentation

Senior Software Engineers to \$44,000 3 plus yrs experience VAX/VMS Assembly, MACROII, EDL Process Control, Communications, Telecommunications

Senior Software Engineers to \$45,000

6-10 yrs experience PC's, IBM Mainframes MAINFRAME-MICRO LINKS

Technical Specialist to \$33,000 3 plus yrs experience Operating Systems Honeywell DPS-870's VAX II, 780, VAX II, 785 Cobol Fortran, Pascal


Principal Software Specialist 7-10 yrs experience Dec 20 VAX Systems Program Communications, internals, Assembler/MACRO Plan, install, design central timesharing facilities

Similar positions are available in New England. New York, Pennsylvania, Texas, Illinois, Georgia, California, Florida and Washington D.C.

To register for SoftView send your resume To:



Mr. Dave Callahan 270 Littleton Rd #17 Westford, MA 01886 or call (617) 692-1920



# Reaching Further Into The Future.

The device shown is a lens used in a narrow beam millimeter-wave antenna. The grooves shown on the surface of the lens are called "matching grooves". These allow electromagnetic energy to pass through the lens without reflecting from the lens surface. This particular lens design was done for an antenna intended for use on a communications satellite.

Other opportunities at Lincoln Laboratory are available in Computer Technology. Solid State, Radar Measurements, Surveillance and Control, Optics, Mechanical Engineering, and Aerospace. In all areas, there are opportunities for MS and Ph.D. level candidates to pursue theoretical study, laboratory investigation, and field tests and demonstrations.

In historic Lexington, Massachusetts, Lincoln Laboratory is within easy reach of New England's most beautiful beaches and mountains, offering year-round recreational pleasure. Our convenient location less than 15 miles from Boston provides access to cultural, educational and athletic events, from the elegance of the symphony to the excitement of Celtics' basketball.

Lincoln Laboratory is a federally funded research center operated by the Massachusetts Institute of Technology and offers competitive salaries and comprehensive benefits. Interested candidates are invited to send resumes, specifying area of interest, to: Susan B. Colcock, Box 65, MIT Lincoln Laboratory, Lexington, MA 02173.

An Equal Opportunity Employer. U.S. Citizenship Required.



Engineering

# Innovation At Work

We're Allied/Bendix Aerospace, Electrodynamics Division, a leader in the development and manufacture of advanced power controls and electromechanical equipment. We're putting innovation to work on one-of-a-kind projects for commercial and military aerospace and marine markets. Join our team of innovators in one of the following opportunities:

# Test Equipment Design Engineer

Responsible for the planning and development of processes, methods, tooling, and hydraulic equipment for testing operations of components. Requires a minimum of 5 years test design or related experience. BSME or equivalent preferred.

# Senior Project Design Engineer

Requires a minimum of 5-10 years experience in powered flight control servoactuation and hydraulic system actuators/valves. BSME or equivalent.

# Senior Manufacturing Engineer

Responsible for developing manufacturing and tooling plans. Will determine machinery, tooling and manufacturing methods and techniques. Requires 5 years related manufacturing experience and a BSME.

# **Electronics Engineer**

Responsible for designing microprocessor-based hardware and applications software for aircraft control systems. Requires a minimum of 2-4 years related experience and a BSEE or equivalent.

# **Senior Electronics Engineer**

Responsible for assisting in the design and support of aircraft anti-skid control units. Requires a minimum of 2-4 years related experience and a BSEE or equivalent.

# **Electronics Analog Engineer**

Responsible for circuit design of analog circuitry for control of marine hydraulics. Requires a minimum of 2-4 years related experience and a BSEE or equivalent.

# Senior Electronic Project Engineer

Responsible for system and circuit design of electronic aircraft control systems. Requires a minimum of 2-4 years related experience and a BSEE or equivalent.

As an Allied/Bendix team member, you will receive an outstanding benefits and compensation package that includes annual stock option, company paid retirement, stock savings plan with tax deferred features, liberal paid vacation and holiday policy, relocation assistance and more.

Interested candidates please forward your resume including salary history and requirements to: Department 1EDN, Allied/Bendix Aerospace, Electrodynamics Division, 11600 Sherman Way, North Hollywood, CA 91605.

An Equal Opportunity Employer U.S. Citizenship Required.



# **Engineering Opportunities**

San Diego Area

Cipher, the leading supplier of removable storage hardware in the computer industry, offers the best of both worlds . . . excellent engineering development programs with a well-established leader and America's finest city, San Diego, Currently, we are seeking a number of unique engineering professionals.

Read/Write Tape Head Engineer

Read/Write Circuit Design Engineers

**Quality Tape Head Engineer** 

Servo Engineers

Microcoders

Principal LSI Designer

Test Engineering Manager

Clpher offers a competitive salary and benefits package including a stock purchase and profit sharing savings plan. For consideration, please send your resume and salary history to **Duane Trimbly**, **Professional Staffing**, **Cipher Date Products**, **Inc.**, **P.O. Box 85170**, **San Diego**, **CA 92138**.

EOE M/F/H/V.



# ENGINEERING (HW/SW)

Top Producer in the largest personnel network system currently has openings for ALL Engineering and computer professionals. Over 200 offices through the U.S. and Canada. All fees, interview and relocation expenses are borne by our client companies. Please call or submit your resume to:

# RIKER PERSONNEL

8790 Purdue Road, Suite E Indianapolis, IN 46268 (317) 875-9911



''Whatever your field may be, your progress will depend upon your individual imagination. I urge you to give it free rein.''

-Arthur Collins, founder of Collins Radio Co.

# COLLINS AVIONICS TECHNOLOGY WILL INSPIRE YOU AT ROCKWELL INTERNATIONAL

Admiral Byrd communicated through Collins equipment during his historic second South Pole expedition. And Collins transmitters heralded the news of V-J Day. When the Eagle landed and when the Space Shuttle took off, Collins equipment was also there.

Thanks to the inspiration of Arthur Collins, the history of communications and avionics

technology is the history of Rockwell International's Collins Avionics Divisions. Today, we're working on more exciting advances: full-scale development of the user equipment for the NAVSTAR Global Positioning System, electronic flight displays, advanced digital flight control, communication/navigation systems, the sophisticated Joint Tactical Information Distribution System (JTIDS), and a wide range of innovative avionics.

If your success speaks as clearly for you as ours does for us, contact: John Gorman (EDN2/6), Collins Avionics Divisions, Rockwell International, 400 Collins Road NE, M/S 105-180, Cedar Rapids, IA 52498. Phone toll-free 1-800-835-9355. Equal Opportunity Employer M/F. U.S. Citizenship Required.



**Rockwell International** 

... where science gets down to business

EDN Databank	
Professional Profile	C
Announcing a new placement service for professional engineers!	
To help you advance your career. Placement Services, Ltd. has formed the EDN Databank. What is the Databank? It is a computerized system of matching qualified candidates with Service is nationwide. You'll be  The computer never forgets. When your type of job comes up, it remembers you're qualified. Service is nationwide. You'll be  Your background and career objectives will periodically be reviewed with you by a PSL professional placement person.  We hope you're happy in your current posi-	C
positions that meet the applicant's professional needs and desires. What are the advantages of this new service?  considered for openings across the U.S. by PSL and it's affiliated offices.  by PSL and it's affiliated offices.  your identity is protected. Your resume  That's why it makes sense for you to replete.	C
<ul> <li>It's absolutely free. There are no fees or charges.</li> <li>Is carefully screened to be sure it will not be sent to your company or parent organization.</li> <li>It's absolutely free. There are no fees or charges.</li> <li>Is carefully screened to be sure it will not be sure it will not completed form below, along with a copy of your resume, to: Placement Services, Ltd., inc.</li> </ul>	C
IDENTITY PRESENT OR MOST RECENT EMPLOYER	
Name Parent Company	C
Home Address: Your division or subsidiary:  City State: Zip: Location (City, State)	
Home Phone (include area code):  Business Phone if O.K. to use:	
EDUCATION  Major Field GPA Year Degree Earned College or University  Degrees (List)	C
	C
POSITIONDESIRED	C
Present or Most Recent Position From: To: Title:  Duties and Accomplishments: Industry of Current Employer:	C
The state of the s	
	C
Reason for Change:	
PREVIOUS POSITION:	
	C
Job Title:	С
Job Title:	C
Job Title:	
Job Title:	
Job Title:  Employer:  Division:  Type of Industry:  Duties and Accomplishments:  COMPENSATION/PERSONAL INFORMATION  Years Experience  Base Salary  Commission  Bonus  Total Compensation  Asking Compensation  Min. Compensation  Date Available  I Will Travel	
Job Title:  Employer:  Division:  Type of Industry:  Duties and Accomplishments:  COMPENSATION/PERSONAL INFORMATION  Years Experience  Base Salary  Commission  Bonus  Total Compensation  Asking Compensation  Min. Compensation	0 0 0
Job Title:  Employer: From: To: City: State:  Division: Type of Industry: Salary:  Duties and Accomplishments:  COMPENSATION/PERSONAL INFORMATION  Years Experience Base Salary Commission Bonus Total Compensation Asking Compensation Min. Compensation  Date Available   I Will Travel   I own my home. How long? I rent my home/apt.    Employed   Self-Employed   Unemployed   Married   Single   Height Weight    Level of Security Clearance   U.S. Citizen   Non-U.S. Citizen   My identity may be released to:   Any employer	
Job Title:  Employer:  Division:  Type of Industry:  Duties and Accomplishments:  COMPENSATION / PERSONAL INFORMATION  Years Experience  Base Salary  Commission  Bonus  Total Compensation  Asking Compensation  Min. Compensation  Date Available  Light  Moderate  Heavy  I own my home. How long?  I rent my home/apt.  Employed  Self-Employed  Married  Single  Height  Meight	
Job Title:  Employer: From: To: City: State:  Division: Type of Industry: Salary:  Duties and Accomplishments:  COMPENSATION/PERSONAL INFORMATION  Years Experience Base Salary Commission Bonus Total Compensation Asking Compensation Min. Compensation  Date Available   IWill Travel	

# ARE YOU LOOKING FOR THE RIGHT PEOPLE IN ALL THE WRONG PLACES?

Over the years, we've earned a reputation for developing successful job fairs. And now, we'd like to share our expertise with you.

"How To Get The Most Out Of A Job Fair" will help you maximize your recruitment efforts, including tips on how to be in the right place at the right time. . . for the right applicants. You'll also find information for developing an effective recruitment strategy for an event and evaluating the results. And, it's free.

To order, call (408) 970-8800. Or write to Westech ExpoCorp., 4701 Patrick Henry Dr., #1901, Santa Clara, CA 95054.



Engineers and software/computer professionals look to Westech for career opportunities.

SAN JOSE: January 20 & 21 LOS ANGELES: February 10 & 11 COSTA MESA: February 10 & 11 DALLAS: February 24 & 25 DENVER: March 10 & 11 SAN JOSE: March 24 & 25 LOS ANGELES: April 7 & 8 COSTA MESA: April 7 & 8 SEATTLE: April 28 & 29 SAN DIEGO: May 5 & 6 SAN JOSE: May 20 & 21 LOS ANGELES: June 2 & 3 COSTA MESA: June 2 & 3 PHOENIX: June 30 & July 1 SAN JOSE: July 14 & 15 DALLAS: July 28 & 29 LOS ANGELES: August 11 & 12 COSTA MESA: August 11 & 12 DENVER: August 25 & 26 SAN JOSE: September 8 & 9 SEATTLE: September 29, 30 LOS ANGELES: October 6 & 7 COSTA MESA: October 6 & 7 PHOENIX: October 27, 28 SAN DIEGO: November 3 & 4 SAN JOSE: November 17 & 18



# ADVERTISERS INDEX

AAA Chicago Computer Ctr	202
Abbott Transistor Labs Inc	97
Acopian Corp*	67
Acromag Inc	98
Adaptec Inc	161
Advanced Microcomputer	
Systems Inc	202
Airpax Corp	165
Amerace Corp	190
Ampro Computers Inc	196
Amtelco	200
Analog Devices Inc	35
Applied Microsystems Corp	14-15
AP Products Inc	179
Aries Electronics Inc	186
Asahi Glass	176
AT&T Technologies	139
Behlman Engineering Corp	88
Bering Industries	86
BICC-Vero Electronics Ltd	55
Bishop Graphics Inc	34
Brooktree Corp	110 140
Calabro Industries	170
California Scientific Software .	202
Calmos Systems Inc	194
Carroll Touch Inc	141
Chancellor Computer Corp	202
Chartered Telmos**	37
Ciprico Inc	175
Clairex Electronics	194
Computer Modules Inc	180
Computer Parts Mart	201
Computer Systems Associates	
Computer Systems Associates	200
Connecticut Microcomputer	200
Connecticut Microcomputer	200
Connecticut Microcomputer Inc	199, 201 202
Connecticut Microcomputer Inc	199, 201 202 58-59
Connecticut Microcomputer Inc	199, 201 202 58-59
Connecticut Microcomputer Inc	199, 201 202 58-59 51 .166-167
Connecticut Microcomputer Inc	199, 201 202 58-59 51 .166-167 200
Connecticut Microcomputer Inc	199, 201 202 58-59 51 .166-167 200 200
Connecticut Microcomputer Inc	199, 201 202 58-59 51 .166-167 200 200 199
Connecticut Microcomputer Inc	200 199, 20120258-5951 .166-167200199117
Connecticut Microcomputer Inc	199, 201 202 58-59 51 .166-167 200 200 199 117
Connecticut Microcomputer Inc Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan	199, 201 202 58-59 51 .166-167 200 200 199 117 103 193
Connecticut Microcomputer Inc Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc	199, 201 202 58-59 51 .166-167 200 200 199 117 103 193 184-185
Connecticut Microcomputer Inc Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp	199, 201 202 58-59 51 .166-167 200 199 117 103 193 184-185 174
Connecticut Microcomputer Inc  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek	199, 201 202 58-59 51 .166-167 200 199 117 103 193 184-185 174 173 94
Connecticut Microcomputer Inc  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc	
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics	199, 201 202 58-59 51 .166-167 200 199 117 103 193 193 174 173 174 173 94 174
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics Ferranti Electronics Ltd**	199, 201 202 58-59 51 .166-167 200 199 117 103 193 194 174 173 94 174 173
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics Ferranti Electronics Ltd** Glassman High Voltage Inc	199, 201 202 58-59 51 .166-167 200 199 117 103 193 193 174 173 174 173 94 174 173 94 174 173
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics Ferranti Electronics Ltd** Glassman High Voltage Inc GMX Inc	
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics Ferranti Electronics Ltd** Glassman High Voltage Inc GMX Inc	
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics Ferranti Electronics Ltd** Glassman High Voltage Inc GMX Inc Grayhill Inc Harris Semiconductor	
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics Ferranti Electronics Ltd** Glassman High Voltage Inc GMX Inc Grayhill Inc Harris Semiconductor HEI Inc	
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics Ferranti Electronics Ltd** Glassman High Voltage Inc GMX Inc Grayhill Inc Harris Semiconductor HEI Inc Heurikon	
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics Ferranti Electronics Ferranti Electronics Ltd** Glassman High Voltage Inc GMX Inc Grayhill Inc Harris Semiconductor HEI Inc Heurikon Hewlett-Packard Co	
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics Ferranti Electronics Ltd** Glassman High Voltage Inc GMX Inc Grayhill Inc Harris Semiconductor HEI Inc Heurikon Hewlett-Packard Co Hitachi America Ltd**  118	
Connecticut Microcomputer Inc.  Cybernetic Micro Systems Cypress Semiconductor Dash, Straus, and Goodhue Data I/O Davidge Corp Digelec Inc Digital Media Dual Systems Inc Eaton Corp Edmund Scientific Co EDN Caravan Electrocube Inc Electronic Development Corp Elek-Tek Endicott Research Group Inc Fairchild Linear Div Faraday Electronics Ferranti Electronics Ferranti Electronics Ltd** Glassman High Voltage Inc GMX Inc Grayhill Inc Harris Semiconductor HEI Inc Heurikon Hewlett-Packard Co	

Industrial Electronic	
Engineers Inc	181
Inmos Corp	10-11, 19
Integrated Devices Technology	73
Interface lechnology	142
Intersil Inc	C2
I/O Tech	197
ITT Components**	192
ITT Schadow Inc	202
Japan Aviation Electronics Ind	28-29
John Fluke Manufacturing Co I	nc6
Keithley Instruments	163
Kepco Inc	169
Kontron Electronics Inc*	65
Linear Technology Corp	152
Loral Instrumentation	177
LSI Logic Corp Marconi Instruments*	81-83
Marconi Instruments*	62
Medinova Corp	199
Metacomp Inc	126
Micro Power Systems	113
Micro Soft	69
Microtek Lab	182
Mini-Circuits Laboratories	3 4
22	2-23, 155
Molex Inc	214
Morrow Technologies Corp	201
National Instruments	188
NEC Electronics	89
Nicolet	21
Northhills Electronics	196
Northwest Instrument Systems	74-75
Omation Inc	199
Omnibyte Corp	115
Orbit Semiconductor	53
Permag	204
Philips Test & Measuring	
Instruments Inc*	24-25
Philips Test & Measuring	
Instruments Inc**	67
Plessey Microsystems	127
Precision Monolithics Inc.	71
D	
Programming Concepts Inc	36
Programming Concepts Inc Qualidyne Systems Inc	80
Qualidyne Systems Inc	80
Qualidyne Systems Inc Raytheon Semiconductor Div	49
Qualidyne Systems Inc	49
Qualidyne Systems Inc	80 49 12-13
Qualidyne Systems Inc	49 12-13 174 199
Qualidyne Systems Inc	80 49 12-13 174 199 202
Qualidyne Systems Inc	80 49 12-13 174 199 202
Qualidyne Systems Inc	80 49 12-13 174 199 202 134 168
Qualidyne Systems Inc	80 49 12-13 174 199 202 134 168
Qualidyne Systems Inc	80 49 12-13 174 199 202 134 168 159
Qualidyne Systems Inc	80 49 12-13 174 199 202 134 168 159 24-25
Qualidyne Systems Inc Raytheon Semiconductor Div RCA Solid State Div Renco Electronics Inc Robinson-Halpern Rogers Corp SBE Inc Schaffner Inc Schroff Inc Siemens Corp** Sierra Scientific Signal Transformer Co Inc	80 49 12-13 174 199 202 134 168 159 24-25 201
Qualidyne Systems Inc Raytheon Semiconductor Div RCA Solid State Div Renco Electronics Inc Robinson-Halpern Rogers Corp SBE Inc Schaffner Inc Schroff Inc Siemens Corp** Sierra Scientific Signal Transformer Co Inc Signetics Corp	80 49 12-13 174 199 202 134 168 159 24-25 201
Qualidyne Systems Inc Raytheon Semiconductor Div RCA Solid State Div Renco Electronics Inc Robinson-Halpern Rogers Corp SBE Inc Schaffner Inc Schroff Inc Siemens Corp** Sierra Scientific Signal Transformer Co Inc Signetics Corp Signum Systems	80 49 12-13 174 199 202 134 168 159 24-25 201 C4 42-43
Qualidyne Systems Inc Raytheon Semiconductor Div RCA Solid State Div Renco Electronics Inc Robinson-Halpern Rogers Corp SBE Inc Schaffner Inc Schroff Inc Siemens Corp** Sierra Scientific Signal Transformer Co Inc Signetics Corp Signum Systems Siliconix Inc	
Qualidyne Systems Inc Raytheon Semiconductor Div RCA Solid State Div Renco Electronics Inc Robinson-Halpern Rogers Corp SBE Inc Schaffner Inc Schroff Inc Siemens Corp** Sierra Scientific Signal Transformer Co Inc Signetics Corp Signum Systems Siliconix Inc Silicon Systems Inc	
Qualidyne Systems Inc Raytheon Semiconductor Div RCA Solid State Div Renco Electronics Inc Robinson-Halpern Rogers Corp SBE Inc Schaffner Inc Schroff Inc Siemens Corp** Sierra Scientific Signal Transformer Co Inc Signetics Corp Signum Systems Siliconix Inc Silicon Systems Inc Spectrum Software	
Qualidyne Systems Inc Raytheon Semiconductor Div RCA Solid State Div Renco Electronics Inc Robinson-Halpern Rogers Corp SBE Inc Schaffner Inc Schroff Inc Sciemens Corp** Sierra Scientific Signal Transformer Co Inc Signetics Corp Signum Systems Siliconix Inc Silicon Systems Inc Spectrum Software Sprague Electric Co. 31,	
Qualidyne Systems Inc Raytheon Semiconductor Div RCA Solid State Div Renco Electronics Inc Robinson-Halpern Rogers Corp SBE Inc Schaffner Inc Schroff Inc Schroff Inc Siemens Corp** Sierra Scientific Signal Transformer Co Inc Signetics Corp Signum Systems Siliconix Inc Silicon Systems Inc Spectrum Software Sprague Electric Co Sprague-Goodman	
Qualidyne Systems Inc Raytheon Semiconductor Div RCA Solid State Div Renco Electronics Inc Robinson-Halpern Rogers Corp SBE Inc Schaffner Inc Schroff Inc Sciemens Corp** Sierra Scientific Signal Transformer Co Inc Signetics Corp Signum Systems Siliconix Inc Silicon Systems Inc Spectrum Software Sprague Electric Co. 31,	

Summation Inc*	37-30
Summit Technology	18/
Sunrise Electronics	30
Tektronix Inc 8, 84-85	5, 201
Teledyne Crystalonics	193
Teledyne Semiconductor	16
Teltone Corp	. 200
Texas Instruments Inc	9-102
Topaz Semiconductor4	6, 195
Trend Circuits	93
Universal Data Systems	C3
Vectron Labs Inc	. 183
Vesta Technology Inc	. 202
Win Systems Inc	. 201
Wintek Corp	, 202
Yellow Springs Instrument	
Co Inc	. 201
Ziatech Corp	
Zilog Inc	. 151
Ziltek	170

# **Recruitment Advertising**

Allied Bendix Aerospace	208
Cipher Data Products Inc	208
MIT Lincoln Laboratory	207
Riker Personnel	208
Softfair	206
Westech	

\*Advertiser in US edition

This index is provided as an additional service. The publisher does not assume any liability for errors or omissions.

<sup>\*\*</sup>Advertiser in International Edition

# LOOKING AHEAD

EDITED BY GEORGE STUBBS

# 1990 connector market to top \$7.5 billion

Though final figures for the 1985 connector and IC-socket market are expected to show a decrease in production value of 1.4% compared with the 1984 value, production of the devices (measured in terms of their dollar worth) will grow at an average annual rate of 11.4% throughout the remainder of the decade, according to the marketresearch company Gnostic Concepts Inc (San Mateo, CA). The production value of connectors and IC sockets was \$3.9 billion in 1984; the figure in 1990 should be more than \$7.5 billion.

Gnostic Concepts attributes the 1985 decline to inventory surplus accumulated in 1984 and depleted throughout the following year. Growth in production should reach a high point in 1988 (19.9%) and a low point in 1989 (2.4%). The latter growth figure assumes a general economic recession for 1989, as predicted by Data Resources Inc (Lexington, MA).

In keeping with the high growth potential of fiber-optic systems, Gnostic Concepts predicts that fiber-optic connectors will be the fastest growing sector of the connector market. In 1984, 17.5% of the fiber-

optic connectors produced were dedicated to in-house use, particularly by providers of voice/data equipment and services. By 1990, the percentage of "captive" production should fall to 10.5%, as standards develop and volume production drives prices down.

# Market for 32-bit μPs may reach \$1B by 1990

The extent of their eventual impact remains uncertain in detail, but there is no question that 32-bit μPs will attract the attention of many component manufacturers and systems suppliers over the next few years. Electronic Trend Publications (ETP), a Cupertino, CA, publisher of reports on the electronic industry, believes the market for 32-bit μPs will certainly reach \$334 million and may be as high as \$1 billion by 1990. This range represents 13 to 39% of the total \$2.57 billion μP market.


One measure of the devices' impact is the reclassification of traditional computer categories. The 32-bit µP is the great equalizer, effectively eliminating the distinction

tions (which were beginning to blur anyway) between mainframes, minicomputers, and microcomputers, and bringing manufacturers of all types of computers into direct competition. The capabilities of even a modest desktop microcomputer based on a 32-bit  $\mu$ P should challenge the energy and imagination of the typical user.

According to ETP, the success of component manufacturers in the 32-bit market will depend on their ability to produce the more complex devices on schedule, on their ability to supplement the devices with support and peripheral chips, on the successful implementation of Unix System V and later versions, and on their ability to garner third-party support for essential system software.

ETP believes that, for systems suppliers, the question is not whether to develop a 32-bit μP-based product line, but rather which processor to choose. Choosing the right processor family is essentially a wager on a variety of factors such as compatibility with 16-bit μPs, coprocessor support, ease of design, and market trends.

#### AVERAGE ANNUAL **GROWTH IN US** CONNECTOR AND IC-SOCKET MARKET PERCENT GROWTH 1984 TO 1990 CONNECTOR TYPE PRINTED WIRING 124 PLANAR CABLE 12.2 RECTANGULAR 6.9 CYLINDRICAL 11.4 COAXIAL 10.9 FIBER OPTIC 32.5 IC SOCKET 13.0 SPECIALTY (SOURCE: GNOSTIC CONCEPTS INC)



Making the Connection Between...

# KAGING PRODUCTIVITY

From through-hole technology to surface-mount technology, Molex makes the connection.

Molex is working to help today's manufacturers develop SMT products that utilize less space and assemble with greater efficiency. Components such as our SIMM sockets are currently helping major manufacturers utilize innovative SIP technology to achieve denser circuit board packaging and increased RAM capacity. And, systems such as our automated robotic PCB assembly equipment are speeding production time and reducing labor costs.

Upgradable SIMM sockets are available in vertical, low profile, and right angle versions in single and dual row configurations.

We take a systems approach to help make your bottom line more productive.

Molex goes beyond quality SMT products to bring

Molex SIMM socket (right) takes up dramatically less board space than DIP packaging (left).

you problem-solving systems for greater productivity. Molex helps you put new technology to work in real world manufacturing situations. From design and development to

manufacturing and delivery, you can depend on Molex for interconnection technology that gives you a competitive edge.

# Connecting technologies worldwide.

Our multi-national organization offers you interconnection design, manufacturing, and technology from around the globe. with dependable supply and local service.

Call or write today for our new 16-page SIMM Technology Handbook.




As part of our intensive quality assurance efforts, CAD technology

is used in product development to identify possible stress points.


SIMM<sup>TW</sup> is a registered trademark of the Wang Corporation.

Corporate Headquarters: 2222 Wellington Ct., Lisle, IL 60532 USA, (312) 969-4550 • European Headquarters: Aldershot, England, (0252) 318221 Northern Asia Headquarters: Tokyo, Japan, 03-478-8777 • Southeast Asia Headquarters: Jurong Town, Singapore, 65-261-9733



# Concentration: spend your time nd money on what you o best.

u excel at what you do; we excel at signing and producing modems. Evote yourself to developing and arketing your products more effectely, and get the modems you need om us. We have invested heavily automated production equipment, at instrumentation and a large chnical staff so you won't have to.



# 4. Commitment: more than a promise, it's our reputation.

Supplying an edge in price/performance begins and ends with commitment. UDS is committed to the manufacture of modems—and only modems. We're also committed to the needs of OEMs, who buy over 50% of the modems we make. We have built a position as an industry leader by honoring commitments—

commitments to your quality demands, commitments to your deadlines, commitments to your demand for value.

# Reliability: because nothing costs like something that doesn't work.

nce you receive an OEM modem from UDS, install it, ip it and forget it. Our quality assurance procedure nges from incoming chip burn-in to 100% testing of all odems prior to shipment. This attention to quality assurce has put our historical reliability rate near the 99th reentile.

# Get us in your corner.

Contact us, and we'll help you corner your share of datacomm market. Let's talk specs and prices! Universal Data Systems, 5000 Bradford Drive, Huntsville, AL 35805. Telephone 205/837-8100; Telex: 752602 UDS HTV.

# Experience: we have already solved most of your problems.

ver the past 15 years, we have designed, produced and livered more than 1,500,000 modems in over 3,000 fferent configurations. We have proved our capability to Ifill nearly any form, fit and function requirement from 300 to 14,400 bps.

# Universal Data Systems

MOTOROLA INC.
Information Systems Group

UDS modems are offered nationally by leading distributors. Call the nearest UDS office for distributor listings in your area.

DISTRICT OFFICES: Atlanta, GA, 404/998-2715 • Aurora, CO, 303/368-9000 • Blue Bell, PA, 215/643-2336 • Boston, MA, 617/875-8868 • Columbus, OH, 614/895-3025 • East Brunswick, NJ, 201/238-1515 • Glenview, IL, 312/998-8180 • Houston, TX, 713/988-5506 • Huntsville, AL, 205/837-8100 • Issaquah, WA, 206/392-9600 • Mesa, AZ, 602/820-6611 • Milwaukee, WI, 414/273-8743

Minnetonka, MN, 612/938-9230 • Mountain View, CA, 415/969-3323 • Richardson, TX, 214/680-0002 • St. Louis, MO, 314/434-4919 • Silver Spring, MD, 301/942-8558 • Tampa, FL, 813/684-0615

Thousand Oaks, CA, 805/496-3777 • Tustin, CA, 714/669-8001 • Uniondale, NY, 516/222-0918 • Willowdale, Ont, Can, 416/495-0008 • Ypsilanti, MI, 313/483-2682

# **Optimum** power... low profile. The winning combination.



When it comes to getting top performance from low profile transformers, no one knows the ropes like Signal. So, when the trend toward higher power usage on PC boards developed, it was no surprise that we were ready to enter the ring. With our two latest... and largest...Flatheads, the 24 and 48VAs. Like our smaller 2.5VA, 6VA and 12VA sizes, these larger Flatheads feature a split bobbin, balanced-coil, hum-bucking construction. Their semi-toroidal configuration

struction. Their semi-toroidal configuration results in balanced windings and reduces the magnetic field radiation that can put sensitive ICs or low-level circuits down for the count.

Moreover, the Flathead's split-bobbin provides non-concentric winding for unpre-cedented insulation and isolation. Reducing inter-winding capacitance and eliminating the need for an electro-static shield.

And, although the basic design of the 24 and 48VAs isn't new, we've added more rugged plug-in pins using square wire to handle the additional weights and currents.

Making the rounds.
You'll find Signal Flatheads are the perfect decision for an array of critical low-height applications in instrumentation and semi-conductor control. They come with 115/230V 50/60Hz dual primaries.

And every one of our standard designs provides dual secondaries to be series connected for dual complementary supplies with a common return. Paralleled for double current rating. Or dual isolated for DC outputs.

# We do all the footwork.

Our PRONTO service promises to ship your prototypes within 48 hours of your order. And we make some pretty fast moves to keep that

So, if you're tired of wrestling with high power transformer problems, come to Signal for our extended line of Flatheads. Find out for yourself why we say they're a knock-out.

To get our complete free catalog, contac' Signal Transformer Co., Inc., 500 Bayviev Ave., Inwood, NY 11696. (516) 239-5777.

Our expanded line of Flathead transformers packs a one-two punch. Insilco Company FOR IMMEDIATE SPEC DATA SEE 1985/86 EEM, VOL 1, PGS. A2276-7.